

**FINAL DRAFT
PRELIMINARY ASSESSMENT
LI TUNGSTEN
GLEN COVE, NEW YORK**

**FIELD INVESTIGATION TEAM ACTIVITIES AT
UNCONTROLLED HAZARDOUS SUBSTANCES
FACILITIES — ZONE I**

**NUS CORPORATION
SUPERFUND DIVISION**

02-8907-28-PA

REV. NO. 1

**FINAL DRAFT
PRELIMINARY ASSESSMENT
LI TUNGSTEN
GLEN COVE, NEW YORK**

**PREPARED UNDER
TECHNICAL DIRECTIVE DOCUMENT NO. 02-8907-28
CONTRACT NO. 68-01-7346**


**FOR THE

ENVIRONMENTAL SERVICES DIVISION
U.S. ENVIRONMENTAL PROTECTION AGENCY**


**SEPTEMBER 18, 1989
(REVISION NO. 1: OCTOBER 18, 1989)**

**NUS CORPORATION
SUPERFUND DIVISION**

SUBMITTED BY:



**JOANN L. WAGNER
PROJECT MANAGER**



**STEVEN OKULEWICZ
SITE MANAGER**

REVIEWED/APPROVED BY:



**RONALD M. NAMAN
FACILITY MANAGER**

POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT

PART I: SITE INFORMATION

1. Site Name/Alias Li Tungsten/LI Tungsten/Wah Chang Smelting and Refining Company
of America Inc.
- Street 63 Herb Hill Road
- City Glen Cove State New York Zip 11542
2. County Nassau County Code 059 Cong. Dist. 3
3. EPA ID No. NYD986882660
4. Latitude 40° 51' 36" N Longitude 73° 38' 25" W
- USGS Quad. Sea Cliff, New York
5. Owner Glen Cove Development Company Tel. No. Unavailable
- Street 34 Market Place
- City Baltimore State Maryland Zip 21202
6. Operator Li Tungsten Tel. No. (516) 676-1313
- Street 63 Herb Hill Road
- City Glen Cove State New York Zip 11542
7. Type of Ownership
- ☒ Private ☐ Federal ☐ State
- ☐ County ☐ Municipal ☐ Unknown ☐ Other _____
8. Owner/Operator Notification on File
- ☐ RCRA 3001 Date _____ ☐ CERCLA 103c Date _____
- ☒ None ☐ Unknown
9. Permit Information
- | Permit | Permit No. | Date Issued | Expiration Date | Comments |
|--------------|------------------|----------------|-----------------|--------------------------------|
| <u>SPDES</u> | <u>NYD008249</u> | <u>Unknown</u> | <u>1987</u> | <u>Cooling water discharge</u> |

Radiation Source Material License	<u>743-0464</u>	<u>3/19/64</u>	<u>Cancelled 1971</u>	License to store, transport, and deliver radioactive compounds
Air Permit	<u>Unknown</u>	<u>Unknown</u>	<u>Unknown</u>	Air discharges from smelting operation

10. Site Status

☐ Active ☒ Inactive ☐ Unknown

11. Years of Operation 1941 to June 1985

12. Identify the types of waste units (e.g., landfill, surface impoundment, piles, stained soil, above- or below-ground tanks or containers, land treatment, etc.) on site. Initiate as many waste unit numbers as needed to identify all waste sources on site.

(a) Waste Management Areas

Waste Unit No.	Waste Unit Type	Facility Name for Unit
1	<u>Drums</u>	<u>55- and 30-Gallon Drums</u>
2	<u>Piles</u>	<u>Waste Piles/Mounds</u>
3	<u>Crates</u>	<u>Wooden Crates</u>
4	<u>Tanks</u>	<u>Tanks</u>
5	<u>Surface Impoundments</u>	<u>Mud Pond/Mud Holes</u>
6	<u>Landfill</u>	<u>Landfill</u>
7	<u>Stained Soil</u>	<u>Stained Soil</u>
8	<u>Compressed Gas Cylinders</u>	<u>Gas Cylinders</u>

(b) Other Areas of Concern

Identify any miscellaneous spills, dumping, etc. on site; describe the materials and identify their locations on site.

There are seven other areas or items of concern at this site. First, there are 23 old electrical transformers scattered around the site which are suspected to contain polychlorinated biphenyl (PCB)-contaminated oil. The oil of three transformers has been analytically tested for the presence of PCBs and only one of the three tested positive. The second area is the analytical chemistry laboratories located in the Office and Labs Building. The ceiling of this building is falling down, as a result of which the contents of some reagent bottles and containers have spilled onto the floor, producing hazardous fumes within the building. Identifiable laboratory chemicals that exist in small quantities have been overpacked and secured. Small quantities of unidentified laboratory chemicals remain in certain areas. Also, the floors of the Dice and East Buildings are flooded with water. The third item of concern is asbestos. This material is found in siding shingles, roofing tiles, tank covers, and pipe wrapping. All of these items are in a state of decay and pieces of asbestos-containing materials

have been found on the ground. The fourth item of concern is a radiation hazard. The facility smelted monazite sand and tungsten ore, which contain thorium-, radium- and uranium-bearing compounds, to produce tungsten products. These radioactive compounds are present in the crates, piles, drums, and landfill areas on the site. According to the EPA, a radiation survey was recently completed, but the results are not known. A previous radiation survey of the facility detected 64 to 251 nanocuries per gram (nCi/g) of radiation on the site, but no background radiation levels for comparison were given. The fifth area of concern is the oil recovery sump located to the west of the Dice Building and a small in-ground sump located in the northwest corner of the East Building. The latter sump contains low levels of vinyl chloride, trichloroethane, and 1,1,2-trichloroethane. The sixth area of concern is the three outfalls (003, 004, 005) from former wastewater treatment operations. These outfalls discharged into Glen Cove Creek; sediment samples collected in the vicinity of the outfalls contained elevated concentrations of nickel, chromium, lead, and tungsten. The seventh and last item of concern is a mercury spill on the floor of the Reduction Building. It has been proposed to clean up this spill by absorption with a lead-based salt.

Ref. Nos. 2, 3, 4, 8, 22, 25, 26, 28, 29

13. Information available from

Contact Amy Brochu Agency U.S. EPA Tel. No. (201) 906-6802

Preparer Steven Okulewicz Agency NUS Corp. Region 2 FIT Date 10/18/89

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 1 - Drums, 55- and 30-Gallon Drums

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York State Pollutant Discharge Elimination System (SPDES) permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The drums are scattered in small groups around the site. Some are buried in the landfill area, while others are stacked within or around the Dice Building, the New Warehouse, the north and south side of the Carbide Building, and at the southern corner of Herb Hill Road and Garvies Point Road.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

There are 3,749 55-gallon drums and 4,303 30-gallon drums that contain solid waste material. The total number of drums containing solid waste is 8,052. The quantity of waste material in some drums is unknown. Another 131 drums contain unidentified liquids.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

One hundred and one 55-gallon drums and thirty 30-gallon drums contain waste liquids, while the remaining drums (8,052) contain waste solids.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

Some drums contain raw and processed tungsten ores and residues, while others contain waste oil and hazardous liquids that include cyanide, nitric acid, hydrochloric acid, hydrofluoric acid, alkalis, carbon tetrachloride, and perchloroethylene. An unknown number of drums may contain heavy metal residues, including lead, chromium, cadmium, arsenic, tungsten, copper, nickel, zinc, barium, uranium, radium, and thorium.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The solid and liquid wastes are stored in many areas around the site. Some of the drums are overstacked, some have toppled, and some are badly corroded and leaking their contents upon the ground either within or around many buildings on the site. One hundred and eight drums containing acids, waste oil, and organics have been overpacked and/or staged to a secure area on the site. Some drums are buried within the landfill area and their condition and contents are unknown. Extensive sampling and analytical data have shown that waste materials are present in the soil and groundwater. There is a potential for waste contamination to enter groundwater, surface water, and the air.

Ref. Nos 1, 2, 3, 4, 5, 8, 25, 26, 28,

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 2 - Piles, Waste Piles/Mound

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York State Pollutant Discharge Elimination System (SPDES) permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

There are eight waste piles located on the site. Seven black waste piles are located around the natural pond in the landfill area between Herb Hill Road and The Place. One mound of waste is located behind and to the west of the Reduction Building.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

The quantity of hazardous substances present in the seven waste piles is unknown; the total volume of these piles is estimated to be 325 cubic yards. The volume and the quantity of hazardous substances present in the waste mound are unknown.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical states of the waste suspected to be disposed of in the eight waste piles include solids, powders, and sludges.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

The specific hazardous substances known to be present in the eight waste piles are the ores and residues/sludges from tungsten processing. These substances include lead, chromium, iron, barium, copper, manganese, zinc, and arsenic.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The waste piles and mound are in an open and uncovered, unpaved area; therefore, there is no containment. Extensive sampling and analytical data have shown that the waste materials on site are present in the soil and groundwater. There is a potential for these wastes to enter surface water and the air.

Ref. Nos. 1, 2, 3, 4, 5, 8, 25, 26, 28

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 3 - Crates, Wooden Crates

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The wooden crates are found at various areas on site, but are located mainly within the New Warehouse Building, on the north side of the Carbide Building, and within the Dice Building/Warehouse.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

There are 719 wooden crates of unknown size and capacity on the site.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical state of the waste type as disposed of in the wooden crates is known to be a solid.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

Specific hazardous substances known to be present in the wooden crates are raw and processed tungsten ores; heavy metals including uranium, thorium, lead, cadmium, mercury, silver, chromium, arsenic, tungsten, zinc, nickel, and barium may also be present.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

Some of the wooden crates are located in an open and uncovered area on the outside of the buildings; they have been observed to be badly weathered or collapsed and spilling their contents upon the ground. Extensive sampling and analytical data have shown that the waste materials on site are present in the soil and groundwater. There is a potential for the wastes to enter surface water and the air.

Ref. Nos. 1, 2, 3, 4, 5, 8, 25, 26, 28

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 4 - Tanks, Tanks

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The majority of the tanks are located in the Dice Building, the Warehouse Building, the East Building, the Loung Building, to the west of the Dice Building, at the southern end of the landfill area, and to the northwest of the Carbide Building. A large aboveground 500,000-gallon fuel tank is located to the north of the Mud Pond. There are also approximately eight underground tanks at unspecified locations.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

There are 224 tanks made of wood, metal, or fiberglass on site. The total capacity of these tanks is more than 2 million gallons, but at present they contain approximately 312,000 gallons of liquid. The aboveground No. 2 fuel oil tank has a capacity of 500,000 gallons.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

Sixty-four tanks contain approximately 312,000 gallons of identified liquids and residues. The contents of five tanks have been identified, although the quantity of material in them is unknown. Sixty-seven tanks contain an unknown quantity of unidentified materials. The remaining tanks (88) are empty, but are assumed to have once contained residues, sludges, and slurries. It is not known whether the 500,000-gallon No. 2 fuel oil tank currently contains any material.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

The specific hazardous substances known to be present in the waste unit include ammonium tungstate, ammonium hydroxide, spent hydrochloric acid, hydrochloric acid, aqueous ammonia, sodium hydroxide, tungsten acid, calcium chloride, cobalt chloride solution, sodium tungstate solution, cobalt sulfate solution, No. 2 fuel oil, and other unidentified liquids, residues, and sludges that contain unspecified heavy metals. A tank truck containing anhydrous ammonia has been removed from the site.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The 224 tanks are found at numerous locations throughout the site. Some are contained within buildings, eight are underground, and others are located in open, uncovered areas

aboveground. These tanks are of various sizes and are composed of wood, fiberglass, or metal. The physical condition of most of these tanks, including the underground tanks, is unknown. It is reported that many of the tanks are corroded or have collapsed linings. Fifty tanks have been inspected externally for leaks and rupture. The contents of two tanks determined not to be secure have been sampled, drained, and drummed for disposal. The 500,000-gallon No. 2 fuel oil tank is leaking into the soil and groundwater, based upon extensive sampling and analytical data. Also, high concentrations of sulfate and chloride compounds have been detected in the groundwater. There is a potential for contaminant migration into the surface water and air.

Ref. Nos. 1, 2, 3, 4, 5, 8, 25, 26, 28

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 5 - Surface Impoundments, Mud Pond/Mud Hole

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

Two settling ponds, referred to as a Mud Pond and a Mud Hole, exist on the site. Both are located immediately south of the 500,000-gallon fuel tank, along Garvies Point Road. A natural pond is located south of the landfill area near the black waste piles, east of Dickson Lane.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

The size of the Mud Pond and Mud Hole and the quantity of wastes in them are unknown. However, it is estimated that remediation of this area would require the removal of 5,000 cubic yards of material.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical states of the waste types as disposed of in the Mud Pond and Mud Hole may include sludges, fines, slurries, and liquids.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

Specific hazardous substances known to be present in the Mud Pond and Mud Hole are lead, chromium, cadmium, arsenic, tungsten, sulfate compounds, chloride compounds, and No. 2 fuel oil.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The Mud Pond was lined with a plastic liner, but has been leaking into the groundwater and surface soil, causing scarred vegetation. The Mud Hole is an unlined pond. A plume of waste/process water which contains heavy metals has been detected emanating from under the Mud Pond. Extensive sampling and analytical data indicate the potential for contaminant migration into surface water.

Ref. Nos. 1, 2, 3, 4, 5, 8

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 6 - Landfill, Landfill

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, radium, thorium oxide, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste unit is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The landfill is located in an open, uncovered, partially wooded lot between the north side of Herb Hill Road and The Place. Most of the landfill area is located to the northern end of the lot closest to The Place.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

The estimated volume of the landfill area is approximately 6,000 cubic yards. The actual quantity of hazardous waste within the landfill is unknown.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical state of the waste types as disposed of in the landfill area is unknown.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

The specific hazardous substances suspected to be present in the landfill area are the residues from the tungsten ore extraction process. South of the landfill area there is an underground plume at a depth of greater than 20 feet that contains tetrachloroethene (PCE), 1,2-dichloroethane, and trichloroethene. However, these chemicals were never used on site and have been attributed to a former dry cleaning facility to the east of the landfill area.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The containment of the landfill is unknown; it is assumed that it was not lined. Buried drums of unknown structural integrity were reported to be present in this area. Therefore, the potential exists for contaminant migration into the groundwater, soil, surface water, and air.

Ref. Nos. 1, 2, 3, 4, 5, 8

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 7 - Stained Soil, Stained Soil

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never obtained an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, thorium oxide, radium, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The age of the waste unit is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The stained soil is located along the perimeter of the Mud Pond/Mud Hole area and extends under and beyond the wooden fence to the edge of Garvies Point Road. Stained soil also is found around the black waste piles along Dickson Lane.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

The quantity of hazardous substances present within the stained soil areas is unknown. However, the volume of material to be removed from the Mud Pond/Mud Hole area is approximately 5,000 cubic yards.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical state of the waste types as disposed of in the stained soil areas include liquids, sludges, and fines.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

The specific hazardous substances known to be present in the stained soil include chloride compounds, sulfate compounds, No. 2 fuel oil, and heavy metals such as lead, chromium, cadmium, arsenic, and tungsten.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

There is no containment associated with the stained soil, which also has an organic odor. The potential exists for contaminant migration into the surface water, groundwater, and air.

Ref. Nos. 1, 2, 3, 4, 5, 8

PART II: WASTE SOURCE INFORMATION

For each of the waste units identified in Part I, complete the following six items.

Waste Unit 8 - Compressed Gas Cylinders, Gas Cylinders

1. Identify the RCRA status and permit history, if applicable, and the age of the waste unit.

Li Tungsten has never had RCRA regulatory status and never applied for an EPA ID number. The company has held a New York SPDES permit, an air permit, and a Radiation Source Material Licence from the Atomic Energy Commission for the use, storage, delivery, and transport of radioactive compounds which include monazite sand, raw tungsten ore, thorium oxide, radium, uranyl acetate, and thorium nitrate. The facility filed for bankruptcy and shut down in 1985. The compressed gas cylinders were removed from the site prior to 7/21/89. The age of the waste units is unknown.

2. Describe the location of the waste unit and identify clearly on the site map.

The gas cylinders were located within the Office and Labs Building, south of Herb Hill Road.

3. Identify the size or quantity of the waste unit (e.g., area or volume of a landfill or surface impoundment, number and capacity of drums or tanks). Specify the quantity of hazardous substances in the waste unit.

There were 22 gas cylinders of various sizes and capacities. The quantity of gas and liquids within these cylinders was unknown.

4. Identify the physical state(s) of the waste type(s) as disposed of in the waste unit. The physical state(s) should be categorized as follows: solid, powder or fines, sludge, slurry, liquid, or gas.

The physical state of the contents within the cylinders is gas or liquid.

5. Identify specific hazardous substance(s) known or suspected to be present in the waste unit.

The specific hazardous substances that were known to be present in the gas cylinders were hydrogen sulfide and chlorine. Sulfur dioxide and anhydrous ammonia were also suspected to be present in the gas cylinders.

6. Describe the containment of the waste unit as it relates to contaminant migration via groundwater, surface water, and air.

The hazardous substances were contained within metal compressed gas cylinders. These cylinders were not corroded or in any danger of leaking and have been removed from the site. Therefore, there was little or no potential for contaminants from the cylinders to enter the surface water, groundwater, or air.

Ref. Nos. 1, 2, 3, 4, 5, 8, 25

PART III: HAZARD ASSESSMENT

GROUNDWATER ROUTE

1. **Describe the likelihood of a release of contaminant(s) to the groundwater as follows: observed, alleged, potential, or none. Identify the contaminant(s) detected or suspected, and provide a rationale for attributing the contaminant(s) to the facility.**

Contaminants in the groundwater attributable to the facility were analytically identified from monitoring well samples. These contaminants include cobalt, nickel, molybdenum, cadmium, tungsten, lead, arsenic, chromium, silver, and barium, as well as chloride and sulfate compounds. Four different plumes of chemicals were found in the groundwater on the site. Two plumes contain volatile organic chemicals derived from adjacent areas and are not attributed to Li Tungsten. A plume of No. 2 fuel oil from the aboveground storage tank was evidenced by the presence of petroleum hydrocarbons in nearby monitoring wells. The last underground plume occurs below the Mud Pond which has been leaking waste/process water solutions. The plume contains sulfate compounds and elevated concentrations of lead, chromium, cadmium, tungsten, and arsenic.

Ref. Nos. 4 (Volume 1, Part 1, pp. 1-4 to 1-6; Part 4, pp. 17-21), 21, 22

2. **Describe the aquifer of concern; include information such as depth, thickness, geologic composition, permeability, overlying strata, confining layers, interconnections, discontinuities, depth to water table, groundwater flow direction.**

In the vicinity of the facility, two aquifers have been identified. From the surface downward, they are the Upper Glacial Aquifer and the Lloyd Aquifer. The Magothy Aquifer is not present in the immediate vicinity of the site. The Upper Glacial Aquifer occurs at a depth of 0 to 175 feet under Li Tungsten and consists of highly permeable Pleistocene and Holocene deposits of fine to coarse, stratified quartzose sand and gravel. It also contains thin interbeds of silt and clay.

The Upper Glacial Aquifer rests unconformably upon the Clay Member of the Raritan Formation of Cretaceous Age. The Raritan Clay (Raritan Confining Unit) ranges in thickness from 0 to 200 feet and can be found at depths ranging from 150 to 250 feet below the surface under Li Tungsten. This clay member consists mainly of light to dark grey, red, white, or yellow clay with variable amounts of silt and silty fine sand. Due to the heterogeneity of sediments within the clay member, the permeability is variable.

Below the Raritan Clay lies the Lloyd Sand Aquifer of early Cretaceous Age. It can be found at depths from 200 to 400 feet below the surface and is approximately 200 feet thick. The Lloyd Sand consists of discontinuous layers of silt, clay, sandy clay, sand, and gravel with a variable permeability.

Beneath the Lloyd Sand is crystalline bedrock composed of schist and gneiss. The total thickness of the overlying, unconsolidated sedimentary deposits in this area is greater than 400 feet. Groundwater in the Upper Glacial Aquifer flows south-southwest toward Glen Cove Creek, while in the Lloyd Sand Aquifer, it flows from north to south. Due to the heterogeneity of the Raritan Clay Member, interconnections are presumed to exist between the Upper Glacial and the Lloyd Aquifers. Groundwater in the Upper Glacial Aquifer occurs at 0 to 45 feet below the surface; the average depth of water within the monitoring wells is approximately 8 feet below the surface.

These aquifers contain the water tapped by many public supply wells for the area and have been designated as a "sole source aquifer" by the U.S. EPA. The permeability of this unit is estimated to be greater than 10^{-3} cm/sec.

Ref. Nos. 4 (Volume 1, Part 4, pp. 14-17), 12, 24

3. Is a designated sole source aquifer within 3 miles of the site?

A sole source aquifer has been designated within 3 miles of the site.

Ref. Nos. 10, 12, 24

4. What is the depth from the lowest point of waste disposal/storage to the highest seasonal level of the saturated zone of the aquifer of concern?

The lowest points of waste disposal/storage are the underground tanks and the landfill, the depth of neither of which is known. Therefore, a depth of 6 feet will be assumed. The depth to the water table in the vicinity of the landfill is approximately 14 feet. The depth from the lowest point of waste disposal to the highest seasonal level of the aquifer of concern is therefore assumed to be 8 feet.

Ref. No. 4

5. What is the permeability value of the least permeable continuous intervening stratum between the ground surface and the aquifer of concern?

The permeability value of the least permeable continuous intervening stratum between the ground surface and the Upper Glacial Aquifer is greater than 10^{-3} cm/sec.

Ref. Nos. 12, 14

6. What is the net annual precipitation for the area?

The net annual precipitation for this area, based upon the normal annual total precipitation minus the mean annual lake evaporation, is approximately 16 inches.

Ref. No. 14

7. Identify uses of groundwater within 3 miles of the site (i.e., private drinking source, municipal source, commercial, industrial, irrigation, unusable).

Groundwater within 3 miles of the site is used for public supply wells, private drinking sources, and commercial, industrial, and irrigation applications. Many wells have been closed or have restricted use due to volatile organic chemical contamination from undetermined sources.

Ref. Nos. 12, 13, 15

8. What is the distance to and depth of the nearest well that is currently used for drinking or irrigation purposes?

Distance 4400 feet

Depth 614 feet

Ref. Nos. 6, 12, 13

9. Identify the population served by the aquifer of concern within a 3-mile radius of the site.

The population served by the aquifer of concern is approximately 161,100.

Ref. Nos. 9, 16

SURFACE WATER ROUTE

10. **Describe the likelihood of a release of contaminant(s) to surface water as follows: observed, alleged, potential, or none. Identify the contaminant(s) detected or suspected, and provide a rationale for attributing the contaminants to the facility.**

A potential exists for a release of contaminants to Glen Cove Creek. The leaking Mud Hole, Mud Pond, and oil tank are located across the street (Garvies Point Road) from Glen Cove Creek. Chemicals identified from surface soil and water samples around these leaking sections include arsenic, selenium, silver, barium, cobalt, chromium, copper, iron, manganese, nickel, strontium, vanadium, zinc, lead, antimony, thallium, aluminum, tungsten, cadmium, titanium, and molybdenum.

Ref. Nos. 1, 4 (Volume 1, Part 1, pp.1-14 to 1-15), 21, 22

11. **Identify and locate the nearest downslope surface water. If possible, include a description of possible surface drainage patterns from the site.**

The nearest downslope surface water is Glen Cove Creek, which flows southwest and is adjacent to the south property boundary. This creek then flows into Hempstead Harbor and Long Island Sound.

Ref. No. 6

12. **What is the facility slope in percent? (Facility slope is measured from the highest point of deposited hazardous waste to the most downhill point of the waste area or to where contamination is detected.)**

The facility slope, as measured from the northern boundary of the landfill to outfall No. 005, is 4.0 percent.

Ref. Nos. 4, 5, 6, 22

13. **What is the slope of the intervening terrain in percent? (Intervening terrain slope is measured from the most downhill point of the waste area to the probable point of entry to surface water.)**

The slope of the intervening terrain, as measured from outfall No. 005 to Glen Cove Creek, is approximately 33 percent.

Ref. Nos. 4, 5, 6, 22

14. **What is the 1-year 24-hour rainfall?**

The 1-year 24-hour rainfall for this area is approximately 2.7 inches.

Ref. No. 14

15. **What is the distance to the nearest downslope surface water? Measure the distance along a course that runoff can be expected to follow.**

The distance from outfall No. 005 to Glen Cove Creek is approximately 30 feet.

Ref. Nos. 4, 5, 6, 22

16. Identify uses of surface waters within 3 miles downstream of the site (i.e., drinking, irrigation, recreation, commercial, industrial, not used).

Surface water uses within 3 miles downstream of the site include recreational and commercial.

Ref. Nos. 6, 20

17. Describe any wetlands, greater than 5 acres in area, within 2 miles downstream of the site. Include whether it is a freshwater or coastal wetland.

Not applicable; there are no wetlands greater than 5 acres in area within 2 miles downstream of the site.

Ref. No. 20

18. Describe any critical habitats of federally listed endangered species within 2 miles of the site along the migration path.

There are no known critical habitats of federally listed endangered species within 2 miles downstream of the site. However, Hempstead Harbor is a waterfowl wintering area most noted for scaup, canvasback, and black ducks, and is a nursery/feeding habitat for striped bass, bluefish, Atlantic silverside, menhaden, winter flounder, and blackfish. Hempstead Harbor has been designated as a "significant coastal fish and wildlife habitat" by the NYS Department of State under Policy 7 of the Waterfront Revitalization and Coastal Resources Act of 1981.

Ref. Nos. 7, 20, 23, 25

19. What is the distance to the nearest sensitive environment along or contiguous to the migration path (if any exist within 2 miles)?

No sensitive environments have been identified along Glen Cove Creek or Hempstead Harbor within 2 miles.

Ref. Nos. 7, 20, 23, 25

20. Identify the population served or acres of food crops irrigated by surface water intakes within 3 miles downstream of the site and the distance to the intake(s).

Not applicable. There are no crops irrigated by surface water intakes within 3 miles downstream of the site.

Ref. Nos. 6, 11

21. What is the state water quality classification of the water body of concern?

The state water quality classification for Hempstead Harbor north of Bar Beach is Class SA (suitable for shell fishing for market purposes and primary/secondary recreation). The state water quality classification for Glen Cove Creek is Class I (secondary contact recreation except for primary recreation and shell fishing).

Ref. No. 18

22. Describe any apparent biota contamination that is attributable to the site.

Biota contamination attributable to the site exists along the grassy area around the Mud Pond, Mud Hole, and waste piles. Data on contamination of biota within Glen Cove Creek is unavailable at this time.

Ref. Nos. 4, 5, 8

AIR ROUTE

23. Describe the likelihood of a release of contaminant(s) to the air as follows: observed, alleged, potential, none. Identify the contaminant(s) detected or suspected, and provide a rationale for attributing the contaminant(s) to the facility.

There is a potential for release of contaminants to the air. Tank covers, siding shingles, roofing tiles, and pipe wrapping, all of which are known to contain asbestos, are in a state of decay. Analyses of indoor and outdoor air samples from the site indicate the presence of little or no volatile organic chemicals and airborne metals; analyses also indicate little or no airborne asbestos particulates. Larger tanks containing aqueous ammonia, hydrochloric acid, and tungsten acid are in an unknown condition and could potentially leak. Also, within the Laboratory Building, the contents of several drums and containers have spilled onto the floor and are producing hazardous vapors.

Ref. Nos. 4 (Volume 1, Part 1, pp. 1-6; Volume 2, Part 6), 8, 25, 26, 27, 28

24. What is the population within a 4-mile radius of the site?

The population within a 4-mile radius of the site is approximately 67,900.

Ref. No. 17

FIRE AND EXPLOSION

25. Describe the potential for a fire or explosion to occur with respect to the hazardous substance(s) known or suspected to be present on site. Identify the hazardous substance(s) and the method of storage or containment associated with each.

There is a potential for fire or explosion to occur with respect to the hazardous substances known to be present on the site. The hazardous vapors within the laboratory pose a serious threat of fire or explosion.

Ref. Nos. 4 (Volume 2, Part 6), 8, 25, 26, 28

26. What is the population within a 2-mile radius of the hazardous substance(s) at the facility?

The population within a 2-mile radius of the hazardous substances at the facility is approximately 35,400.

Ref. No. 17

DIRECT CONTACT/ON-SITE EXPOSURE

27. Describe the potential for direct contact with hazardous substance(s) stored in any of the waste units on site or deposited in on-site soils. Identify the hazardous substance(s) and the accessibility of the waste unit.

There is a potential for direct contact with hazardous substances stored in the waste units at the southeast corner of Herb Hill and Garvies Point Roads, and along the southern portion of Garvies Point Road across from the Hawkins Fuel Oil Company. At the corner there are stacked 30-gallon drums of unknown contents. Although these drums are behind a wooden fence, they are stacked higher than the fence and could topple onto the sidewalk. Along Garvies Point Road, the Mud Pond and Mud Hole and fuel oil tank have scarred and blackened the grass and the base of the trees. This scarring can be found from the aforementioned area to the edge of the roadway. The remainder of the site is fenced off from public access with wooden and chain-link fences. The site is also surrounded by yellow caution tape and patrolled by a private security force.

Ref. Nos. 5, 8, 25

- 28. How many residents live on a property whose boundaries encompass any part of an area contaminated by the site?**

There are no residents who live on a property whose boundaries encompass any part of an area contaminated by the site.

Ref. No. 5

- 29. What is the population within a 1-mile radius of the site?**

The population within a 1-mile radius of the site is approximately 9,900.

Ref. No. 17

PART IV: SITE SUMMARY AND RECOMMENDATIONS

Li Tungsten is located in an industrial area on approximately 26 acres along the north bank of Glen Cove Creek in the city of Glen Cove, Nassau County, New York. From the 1940s to the early 1980s, tungsten ores imported from Mainland China were smelted at this facility for the making of tungsten carbide powder, tungsten wire and welding rods. In 1985, the company filed for bankruptcy; the property is presently owned by the Glen Cove Development Company.

Although the site is presently inactive, most of the wastes generated by the facility remain on site. These wastes include 17,000 tons of solid residue/ore materials in piles, in a landfill, in wooden crates, and in 30- and 55-gallon drums. Some of the drums are overstacked and some have toppled and have broken open, spilling their contents upon the ground. One hundred and eight drums containing acids, waste oil, and organics have been overpacked and/or staged to a secure area on site. The remaining unsound drums are also recommended for overpacking to eliminate the potential for a release of their contents. Elsewhere on the site, there are approximately 312,000 gallons of various liquids stored in 224 above- and below- ground tanks of unknown physical condition, some of which contain hazardous organic and inorganic liquids. The inorganic liquids include spent or unused hydrochloric acid and aqueous ammonia. Fifty tanks have been inspected for leaks and rupture. Two tanks were determined not to be secure and have been drained and/drummed for disposal. An analytical laboratory contains reagents that are known to be spilled or leaking. Small quantities of identifiable chemicals have been overpacked and secured, while small quantities of unidentified chemicals remain in some areas. There are also 23 electrical transformers on site that potentially contain PCB-contaminated oil.

Removal activities have already begun with respect to some of the surficial containers and the contents of some of the tanks. A site investigation conducted by a consulting firm was completed in May of 1988, during which samples were taken from 10 existing groundwater monitoring wells and 13 more monitoring wells were installed. Analyses of samples from these wells identified four underground plumes within the groundwater of the Upper Glacial Aquifer. One plume occurs at a depth of approximately 20 feet along the eastern boundary of the site and was found to contain several dry cleaning solvents related to tetrachloroethylene. The plume is believed to originate from a dry cleaning facility that formerly occupied the property adjacent to the site. Another plume was found along the western boundary of the site and was traced to an adjacent property formerly occupied by a petrochemical company. Both plumes are moving south towards Glen Cove Creek. Another plume occurs in the vicinity of a leaking 500,000-gallon No. 2 fuel oil tank north of Garvies Point Road. The last plume is located around the Mud Pond, which contains waste processing water

PART IV: SITE SUMMARY AND RECOMMENDATIONS (CONT'D)

and heavy metals. Chloride and sulfate compounds, and concentrations of lead, cadmium, tungsten, chromium, arsenic, barium, and silver have been detected in samples collected from this area. The materials leaking from the tank and the pond have also scarred the surface in this area. Asbestos fibers from decaying tank covers and pipe wrapping materials are known to be present on the grounds. Similarly, waste piles containing raw and processed tungsten ores are known to contain radioactive radium, uranium, and thorium compounds used in the ore refining process. The United States Environmental Protection Agency issued an Administrative Order on Consent to the Glen Cove Development Company on 7/21/89, outlining initial actions to be taken at the site. The site is scheduled for a cleanup of hazardous wastes including, but not limited to, the removal of drums, the contents of the tanks, laboratory chemicals, and electrical transformers by May 1990, but plans for cleanup of the groundwater and soil have not been finalized. Development as a residential area is planned for the site. Based upon the high target population potentially affected by groundwater contamination and the potential for direct contact with some of the wastes on site, the Li Tungsten site is recommended for a **HIGH PRIORITY** site inspection.

Soil samples should be collected from all known and suspected areas of surficial contamination and analyzed for Target Compound List (TCL) contaminants and screened for radioactivity. These areas include the landfill and waste piles north of Herb Hill Road, the mound located west of the Reduction Building, the corner of Garvies Point Road where the Mud Pond is located, and the areas where outdoor drums and crates are found. Samples collected from the area of suspected fuel oil contamination, north of the Mud Pond along Garvies Point Road, should be analyzed for petroleum hydrocarbons. Surface water and sediment samples should be collected from the on-site surface impoundments, the three outfalls, and from Glen Cove Creek upstream and downstream of the site. These samples should also be analyzed for TCL contaminants and screened for radioactivity. Samples should also be collected from all groundwater monitoring wells and analyzed for TCL contaminants. Well water samples collected in the vicinity of the fuel oil tank and the sump west of the Dice Building should also be analyzed for petroleum hydrocarbons. Continuous air monitoring is recommended to determine the presence of asbestos particulates and inorganic hazardous vapors during the site inspection and/or remedial activities.


ATTACHMENT 1

103818

**LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK**

CONTENTS

**Figure 1: Site Location Map
Figure 2: Site Map
Exhibit A: Photograph Log**




(QUAD) SEA CLIFF, N.Y.

SITE LOCATION MAP**LI TUNGSTEN, GLEN COVE, N.Y.**

SCALE: 1" = 2000'

FIGURE 1

103820



103821

SITE MAP
LI TUNGSTEN, GLEN COVE, LONG ISLAND, N.Y.

NOT TO SCALE

FIGURE 2



Exhibit A
Photograph Log
LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK
JULY 20, 1989

LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK
JULY 20, 1989

PHOTOGRAPH INDEX

ALL PHOTOGRAPHS TAKEN BY DEBORAH COHEN

<u>Photo Number</u>	<u>Description</u>	<u>Time</u>
1P-1	Aboveground tanks along Herb Hill Road, looking north.	1205
1P-2	South view of main entrance to site.	1209
1P-3	South view of main entrance to site showing stacked drums and wooden pallets.	1210
1P-4	North view along Garvies Point Road showing scarred vegetation, fuel oil tank, and monitoring well.	1220
1P-5	Southeast view of Hawkins Fuel Oil Company and the Warehouse Building.	1221
1P-6	East view of monitoring well GM-8 along Herb Hill Road near surface storage tanks.	1230
1P-7	Entrance to New Warehouse Building showing open door and 55-gallon drum.	1231
1P-8	Stacked, grey 30-gallon drums on the corner of Herb Hill Road and Dickson Lane.	1232
1P-9	Entrance to Reduction Building showing storage tank and 55-gallon drums.	1223
1P-10	Black waste piles on Dickson Lane looking east.	1240

LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK



1P-1

1205

Aboveground tanks along Herb Hill Road, looking north.
July 20, 1989




1P-2

1209

South view of main entrance to site.
July 20, 1989

LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK



1P-4

North view along Garvies Point Road showing
scarred vegetation, fuel oil tank, and monitoring well.

1220



1P-3

South view of main site entrance showing stacked drums
and wooden pallets. Both photos taken July 20, 1989.

1210

LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK



1P-5

1221

Southeast view of Hawkins Fuel Oil Company and the Warehouse Building. July 20, 1989




1P-6

1230

East view of monitoring well GN-8 along Herb Hill Road near surface storage tanks. July 20, 1989

LI TUNGSTEN
GLEN COVE, NASSAU COUNTY, NEW YORK



1P-8

1232

Stacked, grey 30-gallon drums on the corner
of Herb Hill Road and Dickson Lane. July 20, 1989



1P-7

1231

Entrance to the New Warehouse Building showing open
door and 55-gallon drum. July 20, 1989

LI TUNGSTEN
GLEN COVE, MASSAU COUNTY, NEW YORK



1P-10

Black waste piles on Dickson Lane looking east
July 20, 1989

1240



1P-9

Entrance to Reduction Building showing storage tank
and 55-gallon drums. July 20, 1989

1223

ATTACHMENT 2

REFERENCES

1. Letter from Robert A. Becherer, Regional Hazardous Substances Engineer, New York State Department of Environmental Conservation, to Charles Fitzsimmons, U.S. EPA, Edison, NJ, 5/9/89.
2. Letter from John A. Miele, Associate Radiophysicist, Licensing Section, NYS Department of Labor, Division of Industrial Hygiene, to F.H. Lee, Radiation Safety Officer, Wah Chang Smelting and Refining Company of America, Inc., 11/30/71.
3. Telecon Note: Conversation between Charles Fitzsimmons, U.S. EPA, Edison, NJ, and Steven Okulewicz, NUS Corp. Region 2 FIT, 7/31/89.
4. Li Tungsten Site Investigation Report, Volumes 1 and 2, RTP Environmental Associates Inc., May 1988.
5. Preliminary Assessment Off-Site Reconnaissance Information Reporting Form, Li Tungsten, TDD No. 02-8907-28, NUS Corp. Region 2 FIT, Edison, NJ, 7/20/89.
6. Three-Mile Vicinity Map, compiled from U.S. Department of the Interior, Geological Survey Topographic Maps, 7.5 minute series, Sea Cliff, NY, 1968, photorevised 1979; Bayville, NY-Conn., 1967; Mamaroneck, NY-Conn., 1967; Hicksville, NY 1967, photorevised 1979.
7. U.S. Department of the Interior, Fish and Wildlife Service, Atlantic Coast Ecological Inventory, NY-Conn.-NJ, 1980.
8. Waste Characterization Report - Li Tungsten Site, Glen Cove, New York, Volume 1, Enviropact Northeast, Inc. 4/29/88.
9. New York State Atlas of Community Water System Sources, NYS Department of Health, Division of Environmental Protection, Bureau of Public Water Supply Protection, 1982.
10. Monthly fluctuations in the quality of ground water near the water table in Nassau and Suffolk Counties, Long Island, New York. U.S. Geological Survey Water Resources Investigations 78-41, 1978.
11. U.S. Department of Agriculture, Soil Conservation Service, Soil Survey of Nassau County, NY, 1985.
12. Hydrogeology and ground-water quality of the northern part of the town of Oyster Bay, Nassau County, New York, in 1980. U.S. Geological Survey Water Resources Investigations, Report 85-4051, 1985.
13. List of wells within 3 miles of Li Tungsten, compiled from Tables 4 and 5 from Reference No. 12.
14. Uncontrolled hazardous waste site ranking system, A user's manual, 40 CFR, Part 300, Appendix A, 1986.
15. Telecon Note: Conversation between Don Myott, Nassau County Department of Health, Bureau of Public Water Supply, and Brian Dietz, NUS Corp. Edison, NJ, 3/29/89.
16. Nassau County Planning Commission, Water Supply and Water Districts Map. 10/84.
17. General Sciences Corporation, Graphical Exposure Modeling System (GEMS). Landover, Maryland, 1986.

REFERENCES (Cont'd)


18. Telecon Note: Conversation between Jim Gilmore, New York State Department of Environmental Conservation, and Steve Okulewicz, NUS Corp., Edison, NJ, 8/7/89.
19. Telecon Note: Conversation between Debra Rothberg, Jones, Day, Revis, and Pogue Law Office, and Steve Okulewicz, NUS Corp., Edison, NJ, 8/4/89.
20. Telecon Note: Conversation between Jim Gilmore, New York State Department of Environmental Conservation, and Steve Okulewicz, NUS Corp, Edison, NJ, 8/8/89.
21. Letter from Agnes Gara, Assistant Sanitary Engineer, NY State Department of Health, to Robert J. Mangan, Director of Public Works, Glen Cove NY. 9/28/87.
22. NYSDEC memorandum from R.A. Becherer to Li Tungsten File, Subject: Analytical Data. 7/15/86.
23. Letter from John W. Ozard, Senior Wildlife Biologist, NYSDEC Wildlife Resources Center, to David J. Grupp, NUS Corp., Edison, NJ. 4/10/87
24. Federal Register/Volume 49, Number 16/Tuesday, January 24, 1984. Aquifers underlying Kings and Queens Counties, New York Determination.
25. U.S. EPA Region II, Administrative Order on Consent, Index No. II CERCLA-90215, In the Matter of Li Tungsten Site, 7/21/89.
26. Letter and laboratory reports from James A. Perazzo, Associate-Manager of Geosciences, Fred C. Hart Associates, to Charles Fitzsimmons, Environmental Engineer, U.S. EPA Region II, 9/21/89.
27. Telecon Note: Conversation between Charles Fitzsimmons, U.S. EPA, Edison, NJ, and Steven Okulewicz, NUS Corp. Region 2 FIT, 10/3/89.
28. Laboratory report, Nytest Environmental Inc., Li Tungsten, 9/21/89.
29. Telecon Note: Conversation between Robert Thessifeld, Nassau County Department of Health, and Steven Okulewicz, NUS Corp. Region 2 FIT, 10/23/89.

REFERENCE NO. 1

103832

New York State Department of Environmental Conservation
Building 40—SUNY, Stony Brook, New York 11794

(516) 751-2617



Thomas C. Jorling
Commissioner

May 9, 1989

Mr. Charles Fitzsimmons
OSEPA
Woodbridge Avenue
Edison, NJ 08837

MC:MS211

Re: Li Tungsten
Glen Cove, NY

Dear Mr. Fitzsimmons:

As per our telephone conversation, attached are data pertaining to the Li Tungsten site, Glen Cove, from our files. The following information pertains to the regulatory status of the site:

1. The facility had a New York State Discharge Permit (SPDES) NYD 008249. I was not able to obtain a copy of the permit, but this can be pursued if necessary. I am attaching copies of the company's discharge monitoring report.

2. The facility never had RCRA regulatory status. The company never obtained an EPA ID number. In spite of this fact, the Department inspected the facility in December, 1985. The inspection did not indicate that any hazardous waste was being generated from the facility operation. A copy of the salient portions of the inspection is attached.

3. The RCRA inspection report indicates the facility had an Air Permit. Since the Nassau County Health Department (NCHD) administers the air program for DEC in Nassau County, I suggest you contact the NCHD if you would like information on their Air Permit.

103833

Mr. Charles Fitzsimmons

2.


OSCEPA

Re: Li Tungsten, Glen Cove, NY

Samples of materials on site and soil samples have been taken and analyzed over the past few years. Copies of the sampling results are enclosed.

I hope you will find this information useful in your work at the site.

Very truly yours,



Robert A. Becherer, P.E.
Regional Hazardous Substances
engineer

RAB:mz


cc: G. Brachner

T. Candela

103834

ONLY 4 NASSAU	DATE PRODUCED 07-02-82	PAGE 1 of 2
243	REPORT PERIOD 07-01-82 THRU 07-31-82	1

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
SPDES — DISCHARGE MONITORING REPORT



SEE THE REVERSE SIDE OF PART 4 FOR INSTRUCTIONS

PARAMETER/UNITS	OUT FALL	MONITORING LOCATION	LIMIT	MINIMUM MONITORING	AVERAGE	MAXIMUM	EX.	TYPE	FREQUENCY
	003	EFFLUENT VALUE 0100055050301	REPORTED VALUE	MONITORING	0.088	NO LIMITS		METERED	CONTINUOUS
	004	EFFLUENT VALUE 0230056050401	REPORTED VALUE	MONITORING	0.010	NO LIMITS		METERED	INSTANT
	005	EFFLUENT VALUE 0300055050501	REPORTED VALUE	MONITORING	0.020	NO LIMITS		METERED	INSTANT
TURE	003	EFFLUENT VALUE 0400010030301	REPORTED VALUE	*****	*****	90.0000		METERED	CONTINUOUS
TURE	005	EFFLUENT VALUE 0500010030501	REPORTED VALUE	*****	*****	90.0000	0	GRAB	MONTHLY
	003	EFFLUENT VALUE 0600400120301	REPORTED VALUE	*****	*****	9.0000	0	GRAB	MONTHLY
	004	EFFLUENT VALUE 0700400120401	REPORTED VALUE	*****	*****	10.0000	0	GRAB	CONTINUOUS
	005	EFFLUENT VALUE 0800400120501	REPORTED VALUE	*****	*****	9.0000	0	GRAB	MONTHLY
(AS YH3)	004	EFFLUENT VALUE 0900610020401	REPORTED VALUE	*****	*****	29.2000	0	24 HR COMP	2/MONTH
-003	004	EFFLUENT VALUE 1000740020401	REPORTED VALUE	*****	*****	23.5000	0	24 HR COMP	2/MONTH

I hereby affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements made herein are punishable as a Class A misdemeanor pursuant to Section 10.45 of the Penal Law.

NAME AND TITLE

Charles Gow Vice President 8/25/82

☒ 1 PERMITTEE
☐ 2 AGENT

DATE

8/25/82

LI TUNGSTEN CORP
53 HERB HILL ROAD
GLEN COVE, NY 11542

RECEIVED

AUG 26 1982

NY0008245

04 YPI 02

35 17 SUB 02 SH 01

PART 1-ENCON COPY

103835

AGENCY: NASSAU DATE PRODUCED: 07-02-82 PAGE: 2 of 2

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

SPDES — DISCHARGE MONITORING REPORT



SEE THE REVERSE SIDE OF PART 4 FOR INSTRUCTIONS

REPORT PERIOD: 07-01-82 THRU 07-31-82

PARAMETER/UNITS	OUT FALL	MONITORING LOCATION	LIMIT	MINIMUM	AVERAGE	MAXIMUM	EX.	TYPE	FREQUENCY
			*****	*****	5.2000	11.0000		24 HR COMP	27 MONTH
	004	EFFLUENT VALUE	REPORTED	*****	0.25	0.30	0		
		100951020401	VALUE	*****					
			LIMIT	*****	0.2000	0.0000		24 HR COMP	27 MONTH
TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.0004	0.001	0		
		201002020401	VALUE	*****					
			LIMIT	*****	0.3000	0.0000		24 HR COMP	27 MONTH
TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.002	0.006	0		
		301051020401	VALUE	*****					
			LIMIT	*****	3.0000	6.0000		24 HR COMP	27 MONTH
SE-TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.02	0.16	0		
		401055020401	VALUE	*****					
			LIMIT	*****	3.0000	6.0000		24 HR COMP	27 MONTH
IM-TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.02	0.13	0		
		501105020401	VALUE	*****					
			LIMIT	*****	75.0000	140.0000		24 HR COMP	27 MONTH
	004	EFFLUENT VALUE	REPORTED	*****	0.42	0.42	0		
		605001020401	VALUE	*****					
			LIMIT	*****	0.0000	0.0000		24 HR COMP	27 MONTH
TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.03	0.04	0		
		795005020401	VALUE	*****					
			LIMIT	*****	0.4500	0.5000		24 HR COMP	27 MONTH
TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.02	0.04	0		
		895009020401	VALUE	*****					
			LIMIT	*****	7.0000	14.0000		24 HR COMP	27 MONTH
TOTAL	004	EFFLUENT VALUE	REPORTED	*****	0.04	0.05	0		
		995012020401	VALUE	*****					
			LIMIT	*****	5.0000	11.0000		24 HR COMP	27 MONTH
AS S)	004	EFFLUENT VALUE	REPORTED	*****	0.02	0.02	0		
		2039901020401	VALUE	*****					

I hereby affirm under penalty of perjury that information provided on this form is true to the best of my knowledge and belief. False statements made herein are punishable as a Class A misdemeanor pursuant to Section 160.50 of the Penal Law.

NAME AND TITLE

Charles C. Gow Vice President

☒ 1 PERMITTEE
☐ 2 AGENT

DATE

8/25/82

L1 TUNBSTEIN CORP
55 HERB HILL ROAD
GLEN COVE NY 11542

NY0000249
04 MPI 02
AS 17 SUB 02 SW 0

PART 1—ENCON COPY

9E8E0T

INSPECTION FORM

REGION: 1
Major: Non-Major: ✓
TSDF: Substitution:

NEW YORK STATE INDUSTRIAL HAZARDOUS WASTE MANAGEMENT ACT


(Chapter 639, Laws of 1978)

Prepared for:

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Henry G. Williams, Commissioner

Division of Solid and Hazardous Waste
Norman H. Nosenchuck, Director

Send to: Compliance Inspection Section
50 Wolf Road - Room 207/415
Albany, New York 12233-0001



EPA I.D. NUMBER: N Y

NO projective files no EPA 110.

*HANDLER'S NAME (Corporate):

(Division):

*HANDLER'S MAILING ADDRESS: 63 Herkimer Rd.

City, State & Zip Code

*HANDLER'S LOCATION ADDRESS: Glens Cove NY 11542
(if different than mailing)

City, State & Zip Code

*HANDLER'S TELEPHONE NUMBER: () Extension:

*FULL NAME OF HANDLER'S CONTACT: (Mr.) (Ms.) Steven Li

*SIGNATURE OF HANDLER'S CONTACT:

*TITLE OF HANDLER'S CONTACT: Superintendent

INSPECTION DATE: 12/13/85 TIME OF INSPECTION: 10 (a.m.) (p.m.)

COUNTY: Hamilton E/A NUMBER: 2 8 2 4 5 6

INSPECTOR'S NAME: R. Frei

TITLE: Asst. Dir. of Compliance

NAME: R. Frei

TITLE: Asst. Dir. of Compliance

CHECK ONE: Copy of THIS form () has (X) has not been given/sent to the Handler.

REPORT PREPARED BY: Robert A. Bachman

DATE: 12/13/85

REPORT APPROVED BY: Robert A. Bachman

DATE: 12/16/85

(Inspection Form 85-86)

New York State Department of Environmental Conservation
Division of Solid and Hazardous Waste
50 Wolf Road, Albany, New York 12233

PART I

General Information and Classification of Facility

1. Identification of Hazardous Waste - 371

Yes No

A. Is there reason to believe the facility has hazardous waste on-site? If yes, what leads you to believe it is hazardous waste? Check appropriate box/boxes and attach any applicable correspondence with DEC or EPA:

(1) ☐ Company recognizes that its waste is hazardous during the inspection.

(2) ☐ Company admitted the waste is hazardous in its RCRA notification and/or Part A permit application.

(3) ☐ EPA testing (SWA-46) has shown characteristics of:

☐ ignitability - 371.3(b);

☐ corrosivity - 371.3(c);

☐ reactivity - 371.3(d);

☐ EP toxicity - 371.3(e)

☐ Has revealed hazardous constituents (please attach analysis report) 371.4(a)(2), Appendix 22, Appendix 23

(4) ☐ The material is listed in the regulations as a hazardous waste from non-specific sources 371.4(b).

(5) ☐ The waste material is listed in the regulations as a hazardous waste from specific sources. 371.3(c).

(6) ☐ The material or product is listed in the regulations as discarded commercial chemical products, off-specification species, container residues and spill residues thereof. 371.4(d).

(7) ☐ Company is unsure, but they have reason to believe that waste materials are hazardous. (Explain) _____

(8) ☐ If don't know, please explain: _____

Their waste was not hazardous
all was tested by HCSS Co. There
was no indication of a reaction &
more test were done.

B. Is there reason, other than those above, for you to believe that there is hazardous waste on site? (Explain) _____

C. What other environmental permits are held by the company, relative to hazardous waste management?

☒ SPDES Permit Number ☒ Air Permit Number

_____ Part 364 Industrial Waste Transporter Permit (indicate this company's permit number if any)

Please describe other relevant (if any) permits and give the name, address, Part 364 Permit Number and EPA I.D. Number of transporter(s) used by company.

D. If the facility is a treatment, storage or disposal facility, have they:

_____ Submitted a Part A application. _____ Have changes been made that are not reflected in the Part A application? Should the Part A be modified by the Company? _____ If so, explain.

_____ Submitted a Part B application.

_____ Been granted a Part 373 permit.

If so, when does it expire: _____

Please attach or explain any special conditions or variances - 360.1(g) _____

PART III

Comments, Conclusions and Recommendations Section

Facility Name

Si Chuan

EPA I.D. No.

Date of Inspection

12/12/21

General Comments and Conclusions (cite appropriate State regulations in violation and attach additional sheets and other information as required)

Common release from airfield
(from 1st Airfield) dumpster.
(1) Process involves take for extraction
than it is neutralized and
mixed is discharged to creek. (SPEDE
Monitors.) No hazardous waste dis-
posed to the National Park. Samples
taken from the dump. No solid
waste. What we want to see
if closure plan or cleanup is
necessary.

LABORATORY REPORT
CHEMICAL EXAMINATION OF INDUSTRIAL
AND HAZARDOUS WASTES
Division of Laboratories and Research
Nassau County Department of Health

- 1 ☒ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No. _____
Field No. UN-183

Source Information (Please Print)

Premises Li Tungsten
Address 63 Herb Hill Rd.
Town Colson Cove
Collection Point Outfall 004

Month _____ Day 27 Year 85
Date Collected _____

Date Received _____

Date Reported _____

Collection Time 12:30pm

Collected By: V. N. [Signature]

Sampler's Comments:

Bureau:
1 ☐ Land Resources Management
9 ☐ Other (specify)

Sample Type:
A ☒ Water D ☐ Waste Solvent
B ☐ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
	Aluminum mg/l	<u>3.9</u>	15	Chloride mg/l		29	Chromium hex. mg/l	
	Arsenic mg/l	<u>0.005</u>	16	Cyanide mg/l		30		
3	Barium mg/l		17	Fluoride mg/l		31		
4	Cadmium mg/l		18	MBAS mg/l		32		
5	Chromium, Total mg/l		19	pH		33		
6	Copper mg/l	<u>0.07</u>	20	Phenols mg/l		34		
7	Iron, Total mg/l	<u>4.10</u>	21	Solids, Suspended mg/l		35		
8	Lead mg/l	<u>0.32</u>	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	<u>0.17</u>	23	Sulfate mg/l		37		
10	Mercury mg/l		24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	<u>20.05</u>	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l		26	Nitrite nitrogen mg/l		40		
13	Silver mg/l		27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	<u>20.07</u>	28	Total Phos. mg/l		42		

Examiner's Comments:

ONLY METAL BOTTLE SUBMITTED

103841

LABORATORY WORKSHEET

ANALYTICAL EXAMINATION FOR TRACE ORGANIC
CONSTITUENTS IN WATER, HAZARDOUS WASTES
AND SOLID WASTES

Division of Laboratories and Research

Nassau County Department of Health

- 1 ☐ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Field No.

N. No. (Public Water Supply Only)

Source Information (Please Print)

Premises

61 Turgsten

Address

63 Herl Hill Rd

Town

Glen Cove

Collection Point

outfall 004

Well No.

Date Collected

Month

Da

Date Received

Date Reported

Collection Time

Collected By:

Sampler's Comments:

- sample on ice

Bureau

- 1 ☒ Land Resources Management
2 ☐ Public Water Supply
3 ☐ Water Pollution Control
4 ☐ Environmental Sanitation
9 ☐ Other (specify)

SAMPLE TYPE

AQUEOUS

NON-AQUEOUS

1	Community Well	5	Surface Water	1	Soil
2	Non-Community Well	7	Waste Water	2	Sludge
3	Private Well	(8)	Industrial Effluent	3	Waste Solvent
4	Monitoring Well	9	Raw Supply Water	4	Oil
5	Drinking Water	10	Distribution Water	5	Other (specify)

ANALYSIS TYPE

2	Purgeable halogenated hydrocarbons	I	Phthalates
B	Purgeable halogenated hydrocarbons - gases	J	Herbicides
C	Purgeable nonhalogenated hydrocarbons	K	Nitrosamines
D	Halogenated pesticides	L	Benzidines
E	Polychlorinated biphenyls	M	Nitroaromatic hydrocarbons
F	Polycyclic aromatic hydrocarbons	N	Haloethers
G	Aldehydes + ketones	O	Chlorinated hydrocarbons
H	Phenols	P	Other (specify)

Examiner's Comments:

DEC 05 1985

103842

LABORATORY REPORT
CHEMICAL EXAMINATION OF INDUSTRIAL
AND HAZARDOUS WASTES
Division of Laboratories and Research
Nassau County Department of Health

- 1 ☐ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No. 24
Field No. VN-180

Source Information (Please Print)

Premises

Li Tungsten

Date Collected

Month Day

10 7

Address

63 Herb Hill Rd

Date Received

Town

Glen Cove

Date Reported

Collection Point

catch basin / lagoon. soil
Sample

Collection Time

10 :00

Collected By:

U. Nigro

Sampler's Comments:

- Extraction procedure, please
- DEC sample taken during hurricane

Bureau:

- 1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☒ Water D ☐ Waste Sol
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent
1	Aluminum mg/l	3.0	15	Chloride mg/l		29	Chromium hex. mg/l
2	Arsenic mg/l	0.037	16	Cyanide mg/l		30	Final pH
3	Barium mg/l	<0.5	17	Fluoride mg/l		31	
4	Cadmium mg/l	0.063	18	MBAS mg/l		32	
5	Chromium, Total mg/l	<0.01	19	pH INITIAL	3.5	33	
6	Copper mg/l	4.10	20	Phenols mg/l		34	
7	Iron, Total mg/l	10.80	21	Solids, Suspended mg/l		35	
8	Lead mg/l	0.38	22	Solids, Total Diss. mg/l		36	
9	Manganese mg/l	0.27	23	Sulfate mg/l		37	
10	Mercury mg/l	INTER- FERED	24	Ammonia nitrogen mg/l		38	
11	Nickel mg/l	0.10	25	Kjeldahl nitrogen mg/l		39	
12	Selenium mg/l	<0.003	26	Nitrite nitrogen mg/l		40	
13	Silver mg/l	?	27	Nitrate nitrogen mg/l		41	
14	Zinc mg/l	0.72	28	Total Phos. mg/l		42	

Examiner's Comments

Agnes

2 samples broke

103843

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL HAZARDOUS WASTES

of Laboratories and Research

Department of Health

- 1 ☒ Routine
- 2 ☐ Resample
- 3 ☐ Special
- 4 ☐ Complaint
- 5 ☐ Other

Lab. No. 13197

Field No.

UN-183

Information (Please Print)

Location: Li-Tunester
63 Herb Hill Rd.
Golden Cove

on Point: outfall 004 (SDES)

Date Collected: 11-27-85
Date Received: 8
Date Reported: 8

Collection Time: 12:30pm

Collected By: UN-183

Comments:

Bureau:
1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:
A ☒ Water D ☐ Waste Solvent
B ☐ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
um 2.0 mg/l	3.9	15	Chloride mg/l		29	Chromium hex. mg/l	
Arsenic mg/l	0.005	16	Cyanide mg/l		30		
arium mg/l		17	Fluoride mg/l		31		
Cadmium mg/l		18	MBAS mg/l		32		
Chromium, Total mg/l		19	pH		33		
Copper mg/l	0.07	20	Phenols mg/l		34		
Iron, Total mg/l	4.10	21	Solids, Suspended mg/l		35		
Lead 0.05 mg/l	0.32	22	Solids, Total Diss. mg/l		36		
Manganese mg/l	0.17	23	Sulfate mg/l		37		
Mercury mg/l		24	Ammonia nitrogen mg/l		38		
Nickel mg/l	26.05	25	Kjeldahl nitrogen mg/l		39		
Selenium mg/l		26	Nitrite nitrogen mg/l		40		
Silver mg/l		27	Nitrate nitrogen mg/l		41		
Zinc mg/l	0.07	28	Total Phos. mg/l		42		

Miner's Comments:

ONLY METAL BOTTLE SUBMITTED

103844

B

LABORATORY REPORT
 CHEMICAL EXAMINATION OF INDUSTRIAL
 AND HAZARDOUS WASTES
 Virginia Laboratories and Research
 Sussex County Department of Health

- 1 ☐ Routine
 2 ☐ Resample
 3 ☒ Special
 4 ☐ Complaint
 5 ☐ Other

Lab. No.

3652

Field No.

UN196

Source Information (Please Print)

Location: Li Tungsten
63 Herb Hill Rd.
Green Cove
 Collection Point: composite of sludge from
6 drums on Li property

Sampler's Comments:

- claylike; dk brown color } FROM
 - EP Toxicity } DRUMS
 } STORING
 } ORE

Month Day Year
 Date Collected 12 13 85
 Date Received DEC 13 85
 Date Reported 8

Collection Time 11 : amCollected By: V. Nigro

Bureau:

- 1 ☒ Land Resources Management
 9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
 B ☒ Soil E ☐ Oil
 C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1) Aluminum <u>20</u> mg/l	<u>25.0</u>	15	Chloride mg/l		29	Chromium hex. mg/l	
2) Arsenic mg/l	<u><0.005</u>	16	Cyanide mg/l		30	<u>FINAL pH</u>	<u>5.5</u>
3) Barium mg/l	<u><0.5</u>	17	Fluoride mg/l		31		
4) Cadmium <u>0.02</u> mg/l	<u>0.33</u>	18	MBAS mg/l		32		
5) Chromium, Total mg/l	<u><0.01</u>	19	pH <u>INITIAL</u>	<u>10.3</u>	33		
6) Copper <u>1.0</u> mg/l	<u>34.5</u>	20	Phenols mg/l		34		
7) Iron, Total mg/l	<u>0.41</u>	21	Solids, Suspended mg/l		35		
8) Lead mg/l	<u>0.04</u>	22	Solids, Total Diss. mg/l		36		
9) Manganese <u>0.6</u> mg/l	<u>20.0</u>	23	Sulfate mg/l		37		
10) Mercury mg/l		24	Ammonia nitrogen mg/l		38		
11) Nickel <u>20</u> mg/l	<u>32.0</u>	25	Kjeldahl nitrogen mg/l		39		
12) Selenium mg/l	<u><0.005</u>	26	Nitrite nitrogen mg/l		40		
13) Silver mg/l		27	Nitrate nitrogen mg/l		41		
14) Zinc <u>50</u> mg/l	<u>21.5</u>	28	Total Phos. mg/l		42		

Examiner's Comments

103845

LABORATORY REPORT
 CHEMICAL EXAMINATION OF INDUSTRIAL
 AND HAZARDOUS WASTES
 Division of Laboratories and Research
 Nassau County Department of Health

- 1 ☐ Routine
 2 ☐ Resample
 3 ☒ Special
 4 ☐ Complaint
 5 ☐ Other

Lab. No.

13651

Field No.

UN-195

Source Information (Please Print)

Premises *Li Tungsten* Date Collected *12 13 85*
 Address *63 Herb Hill Rd* Date Received *DEC 13 1985*
 Town *Glen Cove* Date Reported *8*

Collection Point *composite of recharge basin soil across street from Li Tungsten Pt.* Collection Time *10:50 am*
 Collected By: *C. Mignard*

Sampler's Comments:

*- sample orange } Large
 - EP Toxicity } settling pond*

Bureau:

- 1 ☒ Land Resources Management
 9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
 B ☒ Soil E ☐ Oil
 C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1 Aluminum <i>2.0</i> mg/l	<i>25.0</i>	15	Chloride mg/l		29	Chromium hex. mg/l	
2 Arsenic mg/l	<i>0.015</i>	16	Cyanide mg/l		30	<i>FINM pH</i>	<i>5.6</i>
3 Barium mg/l	<i><0.5</i>	17	Fluoride mg/l		31		
4 Cadmium <i>0.02</i> mg/l	<i>0.094</i>	18	MBAS mg/l		32		
5 Chromium, Total mg/l	<i>0.02</i>	19	pH <i>INITIAL</i>	<i>9.5</i>	33		
6 Copper <i>1.0</i> mg/l	<i>4.45</i>	20	Phenols mg/l		34		
7 Iron, Total mg/l	<i>0.10</i>	21	Solids, Suspended mg/l		35		
8 Lead <i>0.05</i> mg/l	<i>0.08</i>	22	Solids, Total Diss. mg/l		36		
9 Manganese <i>0.6</i> mg/l	<i>13.3</i>	23	Sulfate mg/l		37		
10 Mercury mg/l		24	Ammonia nitrogen mg/l		38		
11 Nickel <i>2.0</i> mg/l	<i>6.75</i>	25	Kjeldahl nitrogen mg/l		39		
12 Selenium mg/l	<i><0.005</i>	26	Nitrite nitrogen mg/l		40		
13 Silver mg/l		27	Nitrate nitrogen mg/l		41		
14 Zinc mg/l	<i>10.5</i>	28	Total Phos. mg/l		42		

Analyst's Comments

103846

LABORATORY REPORT
 CHEMICAL EXAMINATION OF INDUSTRIAL
 AND HAZARDOUS WASTES
 Division of Laboratories and Research
 Nassau County Department of Health

- 1 ☐ Routine
 2 ☐ Resample
 3 ☐ Special
 4 ☐ Complaint
 5 ☐ Other

Lab. No. 1913

Field No. V11-76

Source Information (Please Print)

Premises Li Turnerton

Address Haul Hill

Town Glen Cove

Collection Point across the road from Li Turnerton

Sample soil/runoff - running in SE direction

Sampler's Comments:

See Toxicity

- across street.

Date Collected Month 6 Day 8 Year 8
 Date Received
 Date Reported

Collection Time

Collected By: J. J. J.

Bureau:

- 1 ☒ Land Resources Management
 9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
 B ☒ Soil E ☐ Oil
 C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1 Aluminum mg/l	<0.5	15	Chloride mg/l		29	Chromium hex. mg/l	
2 Arsenic mg/l	<0.005	16	Cyanide mg/l		30	final pH	3.1
3 Barium mg/l	<0.5	17	Fluoride mg/l		31		
4 Cadmium mg/l	<0.001	18	MEAS mg/l		32		
5 Chromium, Total mg/l	<0.01	19	pH initial	38	33		
6 Copper mg/l	0.14	20	Phenols mg/l		34		
7 Iron, Total mg/l	0.19	21	Solids, Suspended mg/l		35		
8 Lead mg/l	0.09	22	Solids, Total Diss. mg/l		36		
9 Manganese mg/l	0.33	23	Sulfate mg/l		37		
10 Mercury mg/l	<0.005	24	Ammonia nitrogen mg/l		38		
11 Nickel mg/l	<0.05	25	Kjeldahl nitrogen mg/l		39		
12 Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13 Silver mg/l	<0.05	27	Nitrate nitrogen mg/l		41		
14 Zinc mg/l	0.13	28	Total Phos. mg/l		42		

Sampler's Comments

MAY 10 1986

103847

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL AND HAZARDOUS WASTES

Division of Laboratories and Research

County Department of Health

- 1 ☒ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No.

1914

Field No.

VII-74

Source Information (Please Print)

Premises *61 Turner*

Address *101 Turner*

Town *Turner*

Collection Point *Access to land - Turner*

northernmost pile of soil - access - Turner

Sampler's Comments:

*- SP Toxicity
- Li property*

Date Collected *4* *4* *8*
Date Received *8*
Date Reported *8*

Collection Time *1:15 PM*

Collected By: *V. N. N.*

Bureau:

- 1 ☐ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1	Aluminum mg/l	<0.5	15	Chloride mg/l		29	Chromium hex. mg/l	
2	Arsenic mg/l	0.033	16	Cyanide mg/l		30	<i>final pH</i>	3.1
3	Barium mg/l	<0.5	17	Fluoride mg/l		31		
4	Cadmium mg/l	<0.001	18	MBAS mg/l		32		
5	Chromium, Total mg/l	<0.01	19	pH <i>initial</i>	3.8	33		
6	Copper mg/l	0.17	20	Phenols mg/l		34		
7	Iron, Total mg/l	0.64	21	Solids, Suspended mg/l		35		
8	Lead mg/l	0.04	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	0.16	23	Sulfate mg/l		37		
10	Mercury mg/l	<0.0005	24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	<0.05	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l	<0.05	27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	0.12	28	Total Phos. mg/l		42		

Examiner's Comments

103848

MAY 16 1966

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL HAZARDOUS WASTES

Division of Laboratories and Research

Nassau County Department of Health

- 1 ☒ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No.

1915

Field No.

11N-75

Source Information (Please Print)

Premises *Li Tungsten*

Address *2000 Hill Rd*

Town *Glenn Cove*

Collection Point *near the first barrel Tungsten*

wide pile of soil - west of forced tank

Sampler's Comments:

AP Toxicity

- across Janet St.

Month *4* Day *5* Year *86*

Date Received

Date Reported

Collection Time *1:20 PM*

Collected By: *1. N. M. M.*

Bureau:

- 1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1 Aluminum mg/l	<i><0.5</i>	15	Chloride mg/l		29	Chromium hex. mg/l	
2 Arsenic mg/l	<i>0.041</i>	16	Cyanide mg/l		30	<i>final pH</i>	<i>3.6</i>
3 Barium mg/l	<i><0.5</i>	17	Fluoride mg/l		31		
4 Cadmium mg/l	<i><0.001</i>	18	MBAS mg/l		32		
5 Chromium, Total mg/l	<i><0.01</i>	19	pH <i>initial</i>	<i>3.6</i>	33		
6 Copper mg/l	<i>1.17</i>	20	Phenols mg/l		34		
7 Iron, Total mg/l	<i>3.75</i>	21	Solids, Suspended mg/l		35		
8 Lead mg/l	<i><0.04</i>	22	Solids, Total Diss. mg/l		36		
9 Manganese mg/l	<i>0.15</i>	23	Sulfate mg/l		37		
10 Mercury mg/l	<i><0.0005</i>	24	Ammonia nitrogen mg/l		38		
11 Nickel mg/l	<i><0.05</i>	25	Kjeldahl nitrogen mg/l		39		
12 Selenium mg/l	<i><0.005</i>	26	Nitrite nitrogen mg/l		40		
13 Silver mg/l	<i><0.05</i>	27	Nitrate nitrogen mg/l		41		
14 Zinc mg/l	<i>0.13</i>	28	Total Phos. mg/l		42		

Examiner's Comments

103849

MAY 16 1986

REFERENCE NO. 2

November 30, 1971

Address Reply To:

Radiological Health Unit

Wah Chang Smelting and Refining
Company of America, Inc.
63 Herb Hill Road
Glen Cove, New York 11542

Refer To:

LD464

Att: Mr. F. H. Lee
Radiation Safety Officer

Dear Mr. Lee:

This is in reply to your letter of October 29, 1971.

Our findings indicate that your firm has satisfactorily complied with the State of New York Industrial Code Rule No. 38, "Radiation Protection" governing the possession and use of radiation sources. Accordingly, your New York State License No. 743-0464 and your Registration No. LD464 are hereby cancelled.


Your attention is directed to the Code Rule and in particular, the provisions pertaining to licensing and the maintenance and disposition of records of inactivated installations. Should you desire to resume use of radiation sources at some future date, it will be necessary for you to re-register with, or obtain a license from, this Department.

Please contact us directly if you have any questions, or if we may be of further assistance to you.

Very truly yours,

Morris Kleinfeld, M.D.
Director

JAM:pc
cc: Committee on Licensing


by: John A. Miele
Associate Radiophysicist
Licensing Section

103851

STATE OF NEW YORK
RADIOACTIVE MATERIALS LICENSE

Page 1 of _____ Pages

Pursuant to the Labor Law and Industrial Code Rule No. 38, and in reliance on statements and representations heretofore made by the licensee designated below, a license is hereby issued authorizing such licensee to transfer, receive, possess and use the radioactive material(s) designated below; and to use such radioactive materials for the purpose(s) and at the place(s) designated below. This license is subject to all applicable rules, regulations, and orders now or hereafter in effect of all appropriate regulatory agencies and to any conditions specified below.

Licensee 1. Name Wah Chang Smelting and Refining Company of America, Inc. 2. Address 63 Herb Hill Road Glen Cove, New York		3. License number <div style="text-align: center;">743-0464</div>
		4. Expiration date <div style="text-align: center;">Valid until terminated</div>
		5. Reference number <div style="text-align: center;">1</div>
6. Radioactive materials (element and mass number) 1. Thorium 2. Thorium	7. Chemical and/or physical form 1. Thorium oxide 2. Thorium nitrate	8. Maximum quantity licensee may possess at any one time 1. 2300 pounds 2. 750 pounds Total thorium not to exceed 4500 curies <i>15 Ci (now in calculation)</i> <div style="text-align: right;"><i>AN</i></div>

CONDITIONS

9. Authorized use. (Unless otherwise specified, the authorized place of use is the licensee's address stated in Item 2 above.)
1. As insulator in vacuum furnace.
 2. Production of thoriated tungsten powder as step in manufacturing of welding rods.
10. The licensee shall conduct operations involving the use of sources of radiation in compliance with the requirements of New York State Industrial Code Rule No. 38, "Radiation Protection".
11. Any disposal of radioactive waste by the licensee by burial, through the sanitary sewer, or by other release to the environment shall be in accordance with the provisions of Part 16, New York State Sanitary Code Records of all such disposal shall be maintained by the licensee. Monitoring procedures shall be instituted where necessary to demonstrate that concentrations and quantities of radioactive material so disposed of do not exceed permissible levels.
12. The agreement material described in Items 6, 7 and 8 above:
- A. Shall be used only by or under the supervision of either A. Morra or A. Bathie
 - B. Shall not be used in or on human beings, in products intended for uncontrolled distribution to the general public, nor in field applications where radioactivity is released.

FOR THE NEW YORK STATE DEPARTMENT OF LABOR

Date _____

by _____

STATE OF NEW YORK
RADIOACTIVE MATERIALS LICENSE

Page 4 of 2 Pages

License Number 743-0464

Reference Number: 1

- C. Shall be possessed and used by the licensee in accordance with statements, representations and procedures contained in his application dated February 26, 1964, and in related documents as follows:
1. Letter to the United States Atomic Energy Commission dated February 20, 1961, signed by Allen Lau.
 2. So much of Part 40, Title 10, Code of Federal Regulations as is applicable to operations of the licensee and not in conflict with Code Rule 33 or the other conditions of this license.

103853

Date March 19, 1964

APA:jfb

Form COI-6bSL (8-63)

FOR THE NEW YORK STATE DEPARTMENT OF LABOR

by *Nathan Solomon*
Nathan Solomon, Ph.D., M.D.

Chief, Radiological Health Unit

For: Morris Kleinfeld, Director. DTH

RADIOLOGICAL HEALTH INVESTIGATION REPORT

C. FIRM NAME

High Chang Smelting & Refining Co. of America Inc.

F. ADDRESS

3 Herdhill Road, Ellen Cove, Sali, D. of.

G. PERSON SEEN & TITLE

Mr. Henry Lee, Chief Chemist

H. COPIES OF INSTALLATION

Grade School - Group of factory buildings

I. FINDINGS

A. DATE OF VISIT

11/7/62

J. TYPE OF VISIT

Initial

K. REGISTRATION NO

0704

L. LICENSE NO

SLB-135

M. INDUSTRY

Metal Refining

N. NO. OF WORKERS EXPOSED

19

O. NAME OF R.S.O. OR REPRESENTATIVE

Henry Lee

P. INSPECTED BY

T. J. Kelly

Q. REPORT REVIEW BY

		SOURCES IN VIO.			SOURCES IN VIO.		
		IC	NA		IC	NA	
3	Exemptions from C. R. 38		X	26.1b			Radiation Instruments
4a	Registration	X		26.2			Equipment Surveys
b	Changes in Reg'n. Data	X		26.3			Material Surveys
5.1	Unlicensed Use or Poss'n.	X		26.4			Unsealed Sources Surveys
5.2	Exemptions from Licensing		X	26.5			Sealed Sources-Leak Test
6.1a	Radioactivity Increase		X	26.6			Check of Protect. Devices
b	Rad'y. in Food or Drug		X	27			Exit from Controlled Area
6.2a	Notification of Receipt		X	28			Eating, etc., in Rad. Area
b	Unauthorized Disposal		X	29a			Decontam. Vacated Inst.
c	Labeling		X	b			Survey of Vacated Inst.
d	Compliance with Instructions		X	30			Pers. Monitoring Equipment
e	Source Leak Testing		X	31.2a			Posting Radiation Area
f	Competent Test Personnel		X	b			Posting High Rad. Area
g	Failure of Shielding		X	c			Posting Airb. Rad. Area
7	Lic. Application Inadequate	X		d			Posting Rad. Material Area
8a	Lic'g. - Proposal Unsafe	X		32.2			Labeling of Containers
b	Lic'g. - Personnel Unqualified	X		33			Labeling of Rad. Equipment
	Compliance with Lic. Terms	X		34.1			Instruction of Personnel
	Special Nuclear Mat'l. Excess		X	34.2			Avail'ty. of Rule 38, etc.
11	Duration of License	X		34.3			Posting Notice to Employees
12	Renewal of License	X		34.4			Med. Services and Reports
18a	More than 20 Days Use		X	35.1a			Secure Storage of Sources
b	Failure to Notify Dept.		X	b			Hazards in Mat'l. Storage
c	Compliance with C. R. 38		X	35.2			Fire Protection for Mat'l's.
d	Compliance with License		X	36.1a			For Surveys and Tests
21.1a1	To Whole Body <input type="checkbox"/> Qr. <input type="checkbox"/> Yr.	X		b			For Transfer of Material
2	To Hands, etc. <input type="checkbox"/> Qr. <input type="checkbox"/> Yr.	X		c			For Personnel Exposure
3	Skin <input type="checkbox"/> Qr. <input type="checkbox"/> Yr.	X		d			For Medical Evaluations
b	To Minors	X		36.2			Records Preservation
c	Lifetime	X		37.1a			of Theft or Loss
21.2	Controlled Area Int. Exposure	X		b			of Exces. Ext. Exposure
22.1a	Uncon. Area Ext. Annual Dose	X		c			of Exces. Int. Exposure
b	Uncon. Area Ext. Dose Rate	X		37.2			Exposure Reports to Emp.
22.2	Uncon. Area Internal Dose		X	38			Cooperation in Inspection
23	Disposal of Rad. Waste		X	39a			Transportation Safeguards
24	Unauthorized Human Use		X	b			Transport Rule Exemption
25	Qualified R.S.O.	X					
26.1a	Surveys		X				

R. RECOMMENDATIONS TO FIRM

None 4/11/64 (Thorium Nitrate and Oxide)

S. COMMENTS TO SUPERVISOR

1. The company shall make a further radiation survey of the Thorium Nitrate and Thorium Oxide Process and Storage Building to ascertain the degree and type of contamination. Surveys should be performed periodically and the results reported (26.1-26.4)

1. See page 2

T. COMMENTS TO SUPERVISOR: None


INVESTIGATION REPORT

DIVISION OF INDUSTRIAL HYGIENE
RADIOLOGICAL UNIT

1. NAME OF FIRM <i>West Chester Smelting & Refining Co. of America Inc.</i>	2. REGISTRATION NO. <i>0464</i>	3. DATE OF REGISTRATION <i>11/26/50</i>
4. ADDRESS <i>63 Sherbourn Road, Glen Cove, L.I.C., N.Y.</i>		
5. REPORT PREPARED BY <i>T. J. Hill</i>	6. REVIEWED BY	7. DATE REPORT PREPARED <i>11/26/50</i>

4. The radioactive material in storage should be provided with reasonable protection against loss, leakage or dispersion by fire effects or by water, hose streams or other means used to fight fire. (38-35-2)

103855



UNITED STATES
ATOMIC ENERGY COMMISSION
WASHINGTON 25, D. C.

IN REPLY REFER TO

10-943
CAL:POS

Webb Chang Smelting & Refining Company of
America, Inc.,
Woolworth Building
New York 7, New York

Attention: Mr. Allen Lau, Ass't Treasurer

SOURCE MATERIAL LICENSE

License No. D-607

Dated: DEC 6 1957

Gentlemen:

Pursuant to the Atomic Energy Act of 1954 and Section 40.21 of the Code of Federal Regulations, Title 10 - Atomic Energy, Chapter 1, Part 40 - Control of Source Material, you are hereby licensed to receive possession of and title to sixteen hundred (1600) pounds of uranium and thorium compounds during the term of this license, for use as an analytical reagent and in the manufacture of thoriated tungsten wire and columbite metal at your plant locations at Glen Cove, New York and Albany, Oregon.

You are further licensed to transfer and deliver possession of and title to refined source material to any person licensed by the Atomic Energy Commission, within the limits of his license.

As a condition of this license, you are required to maintain records of your inventories, receipts and transfers of refined source material.

This license is subject to all the provisions of the Atomic Energy Act of 1954 now or hereafter in effect and to all valid rules and regulations of the U. S. Atomic Energy Commission, including 10 CFR 20, "Standards For Protection Against Radiation."

Neither this license nor any right under this license shall be assigned or otherwise transferred in violation of the provisions of the Atomic Energy Act of 1954.

This license shall expire December 1, 1958.

CC: Document room
Formal file
Suppl. file
State Health Dep.
Inspection

FOR THE ATOMIC ENERGY COMMISSION

Chief Materials Section
Licensing Branch
Division of Civilian Application

Enclosure:
10 CFR 20

103856

FORM AEC-1
1-5-52

UNITED STATES OF AMERICA
ATOMIC ENERGY COMMISSION

Form approved
Budget Bureau No. 25-2000-1

APPLICATION FOR AEC LICENSE TO
TRANSFER, DELIVER, EXPORT OR RECEIVE
URANIUM OR THORIUM SOURCE MATERIAL

Forward to District Federal Administrator, Title 10-
Atomic Energy Part 26-Control of Source Material

TO: U. S. Atomic Energy Commission
P. O. Box 30, Ansonia Station
New York 23, N. Y.

NAME
AND
ADDRESS
OF
APPLICANT
FIRM,
IND.
OR
INDIV.

Wah Chang Smelting & Refining Co.
of America, Inc.
63 Harbhill Road
Glen Cove, New York

3. PREVIOUS AEC LICENSE NUMBER, IF ANY.

R-150

INSTRUCTIONS

File two (2) copies of this application with
the U. S. Atomic Energy Commission, P. O.
Box 30, Ansonia Station, New York 23, N. Y.
This application may be used for an original
license or for the renewal of a license. In
the case of a renewal, this application should
be received by the Commission on or before
30 days before the expiration of the previous
license. Complete blocks 1, 2, 3, 4, and 5
if you combine two or more of the activities of
Producer, Processor, Distributor, Reporter, or
Consumer, complete each of the applicable
blocks numbered 4 through 5.

1. INVENTORY. INVENTORY OF SOURCE MATERIALS OWNED AND POSSESSED AS OF

February 29, 1952

(Specify date of last inventory)

INSTRUCTION: Include all source material in your possession or under your control, regardless of location. Include any source material you have
possession of but which is owned by others, whether or not they are licensees of the Commission. Please specify that part of your inventory which is
owned by other persons, listing the name, address, and quantity owned by each. Do not include in this inventory any raw source material not
yet removed from its place of deposit to source.

(a) Raw Source Material

DESCRIPTION OF MATERIAL	ESTIMATED PERCENT URANIUM OR THORIUM	QUANTITY IN INVENTORY (Gross form)	NAME AND ADDRESS OF OWNER, IF DIFFERENT FROM THAT IN BLOCK 1 ABOVE

(b) Refined Source Material

DESCRIPTION OF MATERIAL	GRADE (Chem., CP, U.S.P., etc.)	PERCENT OF URANIUM OR THORIUM	QUANTITY (Lb.)	NAME AND ADDRESS OF OWNER, IF DIFFERENT FROM THAT IN BLOCK 1 ABOVE
Uranyl Acetate Reagent	CP	55.90% by wt.	0.620 lbs.	
Thorium Nitrate Crystals	CP	41.66% by wt.	85.753 lbs.	

103857

COPY

Form AEC-410
(1-61)

UNITED STATES
ATOMIC ENERGY COMMISSION

SOURCE MATERIAL LICENSE


Pursuant to the Atomic Energy Act of 1954, and Title 10, Code of Federal Regulations, Chapter 1, Part 40, "Licensing of Source Material," and in reliance on statements and representations heretofore made by the licensee, a license is hereby issued authorizing the licensee to receive, possess and import the source material designated below; to use such material for the purposes (a) and (b) of the regulations in said Part 40. This license shall be deemed to contain the conditions specified in Section 183 of the Atomic Energy Act of 1954 and is subject to all applicable rules, regulations, and orders of the Atomic Energy Commission, now or hereafter in effect, including Title 10, Code of Federal Regulations, Chapter 1, Part 20, "Standards for Protection Against Radiation," and to any conditions specified below.

Licensee		3. License No.
1. Name	Wah Chang International Corporation 100 Church Street	STI-782, as amended
2. Address	New York 7, N. Y.	4. Expiration Date
		January 31, 1968
		5. Docket No.
		40-7216
6. Source Material	7. Maximum quantity of source material which licensee may possess at any one time under this license	
Monazite Sands	import 50 long tons	

CONDITIONS

8. Authorized use (Unless otherwise specified, the authorized place of use is the licensee's address stated in Item 2 above.)

This license authorizes only the import of the above specified source material in accordance with the procedures described in the application dated January 14, 1965.



FEB 2 1965

For the U. S. ATOMIC ENERGY COMMISSION

Date of issuance _____

U. S. GOVERNMENT PRINTING OFFICE : 1962 O - 632985

Robert L. Layfield
Division of Materials Licensing

COPY

103858

REGISTRATION OF SOURCES OF RADIATION

(See Over For Instructions)

L-1113

State of New York
Department of Labor

Reg. No. _____
Date _____

Owner-Name Wah Chang Smelting & Refining Co. of America, Inc. Address 63 Herb Hill Road, Glen Cove, N.Y.

2. Confines of Installation Same

3. RADIATION PRODUCING EQUIPMENT (Use Additional Sheets if Necessary)

NASSAU

TYPES OF RADIATION SOURCES	Number		Size or Rating of Each Machine or Unit	Purpose or Use
	Fixed	Mobile		
Industrial X-Rays				
Medical or Dental X-Rays				
Radiative Static Eliminators				
Beta Ray Gauge				
Nuclear Reactors				
Particle Accelerators				
High Voltage Equipment				
Other (Specify)				



4. RADIOACTIVE MATERIALS

TYPES	Number		Sealed	Un-Sealed	Source Strength	Estimated Quantity Used Annually	Average Quantity on Hand	Purpose or Use
	Fixed	Mobile						
Thorium Oxide	250	100	450			20 - 50 lbs.	800 lbs.	Furnace Lining
Thorium Nitrate		25	50			300 - 400 lbs.	75 lbs.	Thoriated Wire

5. Name and Address of Person in Charge of Radiation Protection

1. Henry Lee 2. Stanley Grecz
Qualifications 1. Chief Chemist 2. Safety Director

June 12, 1958

Date

Signature of Person in Charge of Radiation Protection

103859

0464

SURVEY RESULTS

103860

LR 202 81

Lab. Page 2478

Firm 1011 Heavy Metals - Glen Cove Install # 10464

☐ Sealed: ☒ Unsealed

of Samples ☐ Q tip; ☐ Filter; ☒ Other Nuclides TH Survey Date 11/9/71 Radiophysicist free

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) \pm J	REMARKS
			GROSS	NET \pm J		
						TH analysis 11/9/71
						~ 100mls water as in in Spec. Bkt
						0-2.0 mls in 1/2 - 10 min net NFX One 3 pls areas.
						for Spec. Act. in pCi/ml (div by 100)
1	14.3	1.0	14.3	-7.00 \pm 1.89	-40.19 \pm 32.50	
1	161	1.0	161	1.0 \pm 5.67	0.47 \pm 7.98	
1	210	1.0	210	0.00 \pm 6.48	0.00 \pm 7.53	
1	28	1.0	2.80	-1.63 \pm 0.85	-0.64 \pm 1.01 / 2mls = -0.32 \pm 0.51 pCi/ml	
						or total of ~ 100 mls = -32 \pm 51 pCi/100 mls
						No significant amts of activity of'd for TH in water from storage pit.

Count for TH vs TH Std, Instrument 4318 - S-257 Detector Bio gas, prop. Windowless

Voltage 2000 Gain 5.4 uncal Date Counted 11/9-10/71 Radiochemist BFB/LSC

Background 4.43 CPM; Factor 0.3943 pCi/cpm (net)

$3F_2 = 1.1829$

Robert F. Blaw 11/19/71
SIGNATURE (UNIT REVIEW)

Robert F. Blaw 11/19/71
SIGNATURE (SECTION REVIEW)

SURVEY RESULTS

103861

LR 200 71 Final SurveyLab. Page 2850Firm Will Murray Associates, Inc. (Pittsburgh) Install # LC40-1☐ Sealed; ☒ Unsealed# of Samples 23 ☐ Q tip; ☒ Filter; ☐ Other Nuclides 71 Survey Date 11/2/71 Radiophysicist Blais

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) - SJ	REMARKS
			GROSS	NET \pm		
1	5	5	1.20	± 0.87	± 2.03	
2	7	5	1.80	± 0.99	± 1.24	
3	5	5	1.00	± 0.38	± 1.00	
4	3	5	0.60	± 0.32	± 0.84	
5	5	5	1.00	± 0.38	± 1.00	
6	7	5	1.40	± 0.43	± 1.13	
7	8	5	1.60	± 0.45	± 1.18	
8	21	5	4.20	± 0.68	± 1.79	
9	2	5	0.40	± 0.29	± 0.76	
10	5	5	1.00	± 0.38	± 1.00	
11	14	5	2.80	± 0.57	± 1.50	
12	5	5	1.00	± 0.38	± 1.00	
13	13	5	2.60	± 0.55	± 1.45	
14	13	5	2.60	± 0.55	± 1.45	
15	4	5	0.80	± 0.28	± 0.74	
16	3	5	0.60	± 0.32	± 0.84	
17	11	5	2.20	± 0.51	± 1.34	
18	13	5	2.60	± 0.55	± 1.45	
19	1	5	0.20	± 0.25	± 0.66	
20	3	5	0.60	± 0.32	± 0.84	

Count for X vs Ac²²⁶ Std, Instrument A-25C on 4318 Detector 216 gas proportionalVoltage 1200 Gain 5.4 inoperative Date Counted 11/1/71 Radiochemist BlaisBackground 1.414 CPM; Factor 0.577 pCi/cpm (net)0.15130352 = 2.691Robert F. Blais 11/11/71

SIGNATURE (UNIT REVIEW)

Robert F. Blais 11/11/71

SIGNATURE (SECTION REVIEW)

Lab. Page 6

of Samples 23 ☐ Q tip; ☒ Filter; ☐ Other Nuclides Th, U, Pu Survey Date 10/28/71 Radiophysicist AHJ

$$alg\ total = 57.39 \pm 10.09\%$$

$134 \text{ g/mol} / 5 \text{ ar.}$ $3\bar{5} = 1.440$

Robert F. Blais 11/11/71
SIGNATURE (UNIT REVIEW)

[Signature]
SIGNATURE (SECTION REVIEW)

SURVEY RESULTS

LR 200 87Lab. Page 1Firm West Bay, Louisiana State Install # 1000 Sealed: ☐ Unsealed: ☐# of Samples 23 ☐ Q tip; ☐ Filter; ☐ Other Nuclides ¹³⁷Cs, ¹³⁴Cs, ¹³⁸Cs Survey Date 11/3/71 Radiophysicist John

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 1\sigma$	REMARKS
			GROSS	NET $\pm 1\sigma$		
1	758	40	18.95	-1.50 ± 1.95	-7.00 ± 15.99	
2	770	40	19.25	-1.20 ± 1.95	-3.20 ± 16.05	
3	710	40	17.75	-2.50 ± 1.95	-7.20 ± 15.72	
4	806	40	20.15	-0.50 ± 2.01	-0.80 ± 16.21	
5	696	40	17.40	-3.00 ± 1.97	-8.17 ± 16.05	
6	766	40	19.15	-1.30 ± 1.94	-3.47 ± 16.05	
7	767	40	19.15	-1.27 ± 1.94	-2.35 ± 16.05	
8	901	40	22.53	-2.00 ± 2.07	+5.53 ± 16.69	
9	688	40	17.20	-3.20 ± 1.94	-8.67 ± 16.64	
10	710	40	17.75	-2.20 ± 1.95	-7.20 ± 15.72	
11	731	40	18.28	-2.17 ± 1.97	-5.79 ± 15.89	
12	698	40	17.45	-3.00 ± 1.95	-8.00 ± 15.72	
13	829	40	20.95	+0.53 ± 2.04	+1.41 ± 16.45	
14	800	40	20.00	-0.45 ± 2.01	-1.19 ± 16.21	
15	761	40	19.63	-1.42 ± 1.99	-3.77 ± 16.05	
16	675	40	16.85	-3.57 ± 1.93	-4.50 ± 15.56	
17	643	40	16.65	-4.37 ± 1.91	-11.66 ± 15.40	
18	667	40	16.68	-3.77 ± 1.93	-10.06 ± 15.56	
19	766	40	19.15	-1.30 ± 1.94	-3.47 ± 16.05	
20	625	40	15.88	-4.57 ± 1.91	-12.18 ± 15.40	

Count for ¹³⁷Cs vs ¹³⁴Cs Std, Instrument 40-362 R.D.F.H. Detector Geant-ScintillationVoltage optofact set Gain 51% 40-900 Date Counted 11/3-9/71 Radiochemist AE 1/4/73Background 20.45 CPM; Factor 2.658 pCi/cpm (net) ¹³⁷Cs 14% - 36.136% $3\sigma = 8.004$ Robert F. Blair 11/11/71
SIGNATURE (UNIT REVIEW)D. J. Brown 11/11/71
SIGNATURE (SECTION REVIEW)

SURVEY RESULTS

LR 200 51Lab. Page 248Firm Wich Energy Development, Inc. Install # 61064 Sealed: ☒ Unseal# of Samples 33 ☐ Q tip; ☒ Filter; ☐ Other Nuclides H₃ Survey Date 10/6/64 Radiophysicist RFB

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 3\sigma$	REMARKS
			GROSS	NET $\pm 1\sigma$		
31 21	837	40	21.15	$+9.45$ ± 2.03	$+11.25$ ± 16.37	alg total H ₃ pb with H ₃ 23 fpo
32 22	1655	40	41.35	$+20.92$ ± 2.49	$+55.54$ ± 20.08	$\tau = 64.08$
33 23	766	40	19.15	$+11.50$ ± 1.94	$+31.47$ ± 16.05	$- = -115.17$
						alg = -51.09 ± 77.41 pCi
18 8	401	40	22.53	$+2.05$ ± 3.60	$+5.60$	Using PK method
23 13	837	40	20.93	$+6.53$ ± 3.17	-2.64 ± 2.04	Activity calculation
31 21	837	40	20.93	$+6.45$ ± 2.91	-2.43 ± 2.03	-4.09 ± 16.69
32 22	1655	40	41.35	$+20.93$ ± 2.49	-29.52 ± 2.49	-7.10 ± 16.45
						-6.53 ± 16.37
						-77.35 ± 20.08
						about 4 all mean H ₃ pb
						by -97.07 ± 34.93 pCi H ₃

Count for H₃ vs 11.24 Std, Instrument YC-362-BDFH Detector liquid scintillationVoltage opt factor set Gain 51% 40-400 Date Counted 11/3-9/64 Radiochemist RFBBackground 20.45 CPM; Factor 2.688 pCi/cpm (net) 11.24 net 14pk = 36.136%

$$3\sigma = 8.664$$

Robert F. Blair 11/11/71
SIGNATURE (UNIT REVIEW)Dr. James J. Strain
SIGNATURE (SECTION REVIEW)

SURVEY RESULTS

LR 200 61Lab. Page 24 of 24Firm Gen. ElectricInstall # 20464Sealed: ☐ Unse# of Samples 23 ☐ Tip: ☐ Filter: ☐ Otherdes 15 dphSurvey Date 10/28/71Radiophysicist John

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 3\sigma$	REMARKS
			GROSS	NET $\pm 1\sigma$		
1	1372	40	34.20	+1.17 -1.17	+1.32 -1.17	
2	1223	40	30.53	+1.73 -1.73	+1.17 -1.17	
3	1169	40	29.23	+3.10 -3.10	+2.08 -2.08	
4	1301	40	32.53	+0.20 -0.20	+0.13 -0.13	
5	1256	40	31.40	+0.13 -0.13	+0.62 -0.62	
6	1298	40	32.45	+0.12 -0.12	+0.08 -0.08	
7	1237	40	30.93	+1.40 -1.40	+0.94 -0.94	
8	1729	40	43.23	+10.40 -10.40	+7.30 -7.30	
9	1164	40	29.10	+3.23 -3.23	+2.16 -2.16	
10	1278	40	31.95	+0.35 -0.35	+0.25 -0.25	
11	1344	40	33.60	+1.27 -1.27	+0.85 -0.85	
12	1236	40	30.90	+1.43 -1.43	+0.96 -0.96	
13	1697	40	41.93	+9.60 -9.60	+6.43 -6.43	
14	1432	40	35.80	+3.47 -3.47	+2.32 -2.32	
15	1245	40	31.13	+1.20 -1.20	+0.80 -0.80	
16	1207	40	30.18	+2.15 -2.15	+1.44 -1.44	
17	1153	40	28.83	+3.50 -3.50	+2.35 -2.35	
18	1212	40	30.30	+2.03 -2.03	+1.36 -1.36	
19	1247	40	31.18	+1.15 -1.15	+0.77 -0.77	
20	1176	40	29.40	+2.93 -2.93	+1.96 -1.96	

Count for GM vs GM Std, Instrument 7.0 362 R D F HDetector General ScintillationVoltage opt Gain 5.1% 40-1000Date Counted 11/3-9/71Radiochemist RFB/RRBackground 32.33 CPM: Factor 0.670pCi/cpm (net) Calc on #34 = 33.056% $3\sigma = 2.010$ Robert F. Blais 11/11/71
SIGNATURE (UNIT REVIEW)D. J. ... 11/11
SIGNATURE (SECTION REVIEW)

SURVEY RESULTS

103868

LR 200 71

Lab. Page 2412

Firm 1011 Hwy 101, Topeka, KS Install # 10110 ☐ Sealed; ☒ Unsealed

of Samples 23 ☐ Q tip; ☒ Filter; ☐ Other Nuclides 137Cs Surv Date 10/28/71 Radiophysicist Jones

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 3\sigma$	REMARKS
			GROSS	NET $\pm 2\sigma$		
31 21	1645	40	41.13	$+5.36$ -5.37	$+5.45$ ± 5.45	avg total C14 pb as C14 std
32 22	7398	40	184.95	$+152.62$ -4.66	$+162.26$ ± 9.37	$+ = 126.59$
33 23	1241	40	31.02	-1.36 -2.92	-0.87 ± 5.07	$- = -17.86$
						avg = $+108.93 \pm 25.82 pCi$
16210g PK reference of following corrected net CPM						
18 8	1729	40	43.23	$+10.45$ -5.72	$+6.75$ ± 2.75	Activity based on C14 std $\pm 3\sigma$ $+6.80 \pm 5.53$
23 13	1677	40	41.93	$+9.66$ -2.23	$+7.43$ ± 2.73	$+6.30 \pm 5.49$
31 21	1645	40	41.13	$+8.86$ -5.37	$+3.49$ ± 2.71	$+5.28 \pm 5.45$
32 22	7398	40	184.95	$+152.62$ -4.66	$+147.96$ ± 4.66	$+97.19 \pm 9.37$
above 4 all + C14 pb						
total = $116.07 \pm 13.37 pCi$						

Count for C14 pb vs C14 std, Instrument TC 362 BDFH Detector Reginald V. C. H. H. H.

Voltage cpb fact net Gain 5.1% 40-1000 Date Counted 11/3-9/71 Radiochemist RFB

Background 32.33 CPM; Factor 0.670 pCi/cpm (net) C14 std 113K = 33.056%

$3\sigma = 2.010$

Robert F. Blais 11/11/71
SIGNATURE (UNIT REVIEW)

D. James L. Stein 11/11
SIGNATURE (SECTION REVIEW)

INVESTIGATION REPORT

DIVISION OF INDUSTRIAL HYGIENE
RADIOLOGICAL UNIT

1. NAME OF FIRM <i>Wah Chang Div. Tekong Inc.</i>	2. REGISTRATION NO. <i>10464</i>	3. DATE OF REGISTRATION
4. ADDRESS <i>Allen Cove</i>	5. REPORT PREPARED BY <i>A. Jones</i>	6. REVIEWED BY <i>[Signature]</i>
		7. DATE REPORT PREPARED

On 10/30/71 I visited the above place to perform a company survey of their facilities, as their plant was being shut down on 10/31/71. I responded to a call from H. Lee, who was there. He indicated that he had performed a survey but had not recorded it as yet. I said I would pick it up when I would be next.

On arrival I met with Mr. Lee & H. Hughes acting plant manager who will remain as the process until 12/31/71 when Wah Chang-Edison's license expires. Most workers were told off 10/30/71 including H. Lee & H. Hughes.

There are two areas of concern at Wah Chang. One was a pit where containers of Tl-201 were stored for a long period of time & the other was an old radiation plant where Tl-201 was used in the mfg. of the welding rods. Mr. Lee indicated a survey performed in both areas. Also I saw several disposal vessels in 12 1/2 gal cans of Thorium ~~oxide~~ ^{nitrate} (labeled as such) which showed a packing sheet showing that all Tl-201

INVESTIGATION REPORT

DIVISION OF INDUSTRIAL HYGIENE
RADIOLOGICAL UNIT

1. NAME OF FIRM	2. REGISTRATION NO.	3. DATE OF REGISTRATION
4. ADDRESS		
5. REPORT PREPARED BY	6. REVIEWED BY	7. DATE REPORT PREPARED

Previously an order was received for a shipment to be made to Wat Ching in Huntsville Ala. Although the shipment had not left as yet, I was assured that it would leave on 10/24/71.

I instructed Mr. Zie to contact Mr. Hester to send us letter with firm survey and to include a copy of the shipping sheet.

I then made and conducted a deep survey of both area.

Action: Please letter to be sent pending lab results.

REFERENCE NO. 3

103871

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

7/31/89

TIME:

13:50

DISTRIBUTION:

FILE - LI TUNGSTEN TDD 07-8907-78-PA
KRIC NYJLPA

BETWEEN:

CHARLES FITZSIMMONS

OF:

EPA-EDISON

PHONE:

(701) 371-6608

AND:

STEVE OKULEWICZ

NUS FIT EDISON NTS.

DISCUSSION:

LI TUNGSTEN - CURRENT INFO & SITE STATUS

MR. FITZSIMMONS INFORMED ME THAT THE CORRECT NAME
OF THE SITE IS LI TUNGSTEN, NAMED AFTER ITS OWNER
AND THAT THE SITE IS CURRENTLY OWNED BY OLD COURT
SAVINGS AND LOAN CORPORATION OF BALTIMORE MARYLAND.

THIS SAVINGS & LOAN CORPORATION LEASED THE SITE TO

LI TUNGSTEN FROM 1984-1985, AFTER WHICH LI TUNGSTEN
WENT BANKRUPT IN 1985. LI TUNGSTEN WAS ORIGINALLY

OWNED BY WAN CHANG SMELTING COMPANY FROM 1940 TO
1985. THE SITE IS IN THE CLEAN UP PROCESS AND ALL

SURFICIAL CONTAINERS INCLUDING TANKS, CRATES, DRUMS,
PONDS, LABORATORY REAGENTS AND SOME OF THE WASTE
FILES WILL BE REMOVED BY JANUARY OF 1990,

PROVIDED THE PLAN REMAINS ON SCHEDULE. NO GROUNDWATER

ACTION ITEMS:

CLEAN UP IS SCHEDULED AT THIS TIME. A RADIATION
SURVEY WAS JUST COMPLETED, BUT ITS RESULTS ARE
NOT KNOWN PRESENTLY. PLANT WAS SHUT DOWN IN 1985.

REFERENCE NO. 4

103873

LI TUNGSTEN SITE INVESTIGATION REPORT (Volume 1)

Prepared For:
Campon Realty Corp.
445 Fifth Avenue
New York, NY 10016

Prepared by:
RTP Environmental Associates, Inc.
400 Post Avenue
Westbury, NY 11590

May, 1988

DRAFT

103874

VOLUME 1

LI TUNGSTEN SITE INVESTIGATION REPORT

TABLE OF CONTENTS

SECTION

Volume 1

- 1.0 Executive Summary
- 2.0 Introduction
- 3.0 Review of Regulatory Issues Related to Site Development
- 4.0 Hydrogeologic Investigation and Soil Gas Survey

Volume 2

- 5.0 Site Residues and Transformer Removal
- 6.0 Tank Cleaning, Removal of Asbestos and Demolition of Structures

APPENDIX

Li Tungsten Health and Safety Plan

Excerpts Discussing Tungsten Processing, Tungsten Alloys and Tungsten Compounds

SECTION 1.0

EXECUTIVE SUMMARY

LI TUNGSTEN SITE ENVIRONMENT INVESTIGATION REPORT

1.0 EXECUTIVE SUMMARY

This site environmental investigation report summarizes the activities and findings of RTP Environmental Associates, Inc. and subcontractors at the Li Tungsten, Glen Cove, New York site. An investigation of site groundwater, soils, structures and equipment focused on determining the nature and extent of any potential or existing environmental contamination. The overall goal of the study was to determine the appropriate procedures and estimated costs for closure of the site, prior to its future intended use as a residential development.

The investigation protocol is detailed in the RTP contract with Campon Realty Corporation. RTP has successfully completed all the terms and conditions of its contract. The study began on March 25, 1988 and ended on May 13, 1988. The time frame for this investigation was limited and the study was designed to uncover the maximum amount of information about site remediation requirements within this limited time frame. Furthermore, coordination with regulatory agencies was restricted by the terms of RTP's contract in this phase of work. Thus, the study cannot be considered a comprehensive assessment of all site environmental matters as may be required by regulatory agencies for purposes of planning site remediation and obtaining a complete clean bill of health. The estimated costs for remediation, preferred alternatives and schedules may need adjustment once coordination with regulatory agencies is initiated.

This executive summary contains a discussion of the findings, outlining the specific cost/benefits of various alternatives. The supporting documents, as supplied by RTP subcontractors, have been provided in the remainder of this report for completeness.

As a preface to the discussion of findings, we note that our investigation has uncovered several new and significant environmental contamination problems at the site. These include underground plumes of oil contaminated soils and solvent contaminated groundwater. Specifically, the identified PCE plume was found to be rather extensive, a hazardous VOC plume from the Mattiace property was identified, and subsurface oil contamination was found in two separate locations. Due to the conditions of low soil permeability, we are forced to predict a rather lengthy period for remediation of these conditions. Finally, the uppermost groundwater throughout the facility shows evidence of infiltration by metals from processing activities at the facility. Thus, the site has substantial environmental problems that go beyond those typically associated with conversion of industrial sites to residential use. This does not mean that remediation sufficient to satisfy regulatory requirements is not attainable. In fact, our review of remediation procedures, costs and schedules indicates that the concept of a successful cleanup plan is a plausible one and that serious discussions with regulatory agencies in this regard may prove worthwhile. Nonetheless, it is important to keep in mind that the site has been found to pose some ~~substantial remediation challenges~~, each of which has alternative methods of resolution.

The costs provided and the schedules given in Section 1.4 pertaining to remediation recognize the uncertainties described above and are intended to be best estimates of actual costs, if site remediation as envisioned by RTP begins within the next few months. Costs and schedules are based upon

current New York State requirements and our estimates of how applicable review procedures will be implemented in this case. Costs and time lines will likely expand should New York State pass new legislation or if remediation is delayed for a lengthy period.

This executive summary consists of five subsections covering the various aspects of study findings and conclusions.

1.1 QUALITY AND QUANTITIES OF MATERIALS ONSITE

The following is a brief discussion of the types and quantities of materials onsite. The details are provided in the annotated sections of this report.

Stored Materials

An estimated volume of 11,000 cubic yards, 17,000 tons of solid residue/ore materials are onsite. These materials are contained in various drums, crates, piles, etc. in almost all areas of the site and are present as landfill material in a significant portion of the northwest and northern portions of the site. These have been screened for metals and E.P. Toxicity and have been shown to contain substantial heavy metal concentrations but to be non-toxic. When detailed analyses are conducted for remediation, some materials may be analyzed as being E.P. toxic. An estimated volume of 350,000 ~~gallons~~ liquids are stored onsite. These liquids will be best handled by transporting offsite to a disposal location. An estimated 131,000 ~~gallons~~ hazardous organic liquids are stored onsite and these will need to be manifested and removed. Three main laboratory areas with substantial chemical inventories have been identified which will require special treatment. These should be packed and removed from the site.

*Removal
of these
materials
will
be
flushed*

Subsurface Conditions

A tetrachloroethene (PCE) plume is one of several plumes that have been detected onsite as shown in Figure E-1. The exact plume extent will need to be better defined. The area surrounds groundwater monitoring wells GM-9, GM-3D, EMW-1 and GM-6. Purportedly a dry cleaning fluid was discharged on an adjoining property.

Discussions with the current tenant of the adjoining property suggest that there was never dry cleaning on the site, however, the Nassau County Department of Health (NCDOH) has a record of dry cleaning solvents on the adjoining property.

A 1,1,1 trichloroethane plume has been detected onsite and its aerial extent is roughly estimated in Figure E-1. The plume is in the vicinity of a groundwater monitoring well GM-10 and the likely source is the Mattiace property. This property is currently under investigation by the USEPA, New York State Department of Environmental Conservation (NYSDEC) and NCDOH and is currently undergoing remediation.

An oil plume has been detected under the 500,000 gallon No. 2 "fuel tank" and is also located on Figure E-1. This tank was leased by an oil supplier and numerous spills have been reported to NCDOH at this site. A smaller partially remediated spill was detected on the southwest corner of the property near Glen Cove Creek.

A waste/process water solution plume which contains heavy metals has been detected onsite emanating from under the location of the mud pond (Figure E-1).

COMPLET
BY
PREPARED
BY
PROJECT
NO.


DATE
4 88

SCALE
SHOWN

PREPARED
BY

RTP ENVIRONMENTAL ASSOC., INC

N1342L11-1047



EXPLANATION

II

PARCEL NUMBER

PROPERTY/PARCEL
BOUNDARY

--- INFERRED EXTENT OF OIL PLUME

● MONITORING WELL LOCATION

— INFERRED EXTENT OF VOC PLUME WITH
CONCENTRATION OF 100 ppb OR GREATER

NOTE: REFER TO TABLE 3 FOR CONCENTRATIONS OF
VOCs DETECTED IN MONITORING WELLS SAMPLED IN SPRING 1987 AND SPRING 1988

INFERRED EXTENT OF PLUME OF VOCs IN SHALLOW GROUND-WATER SYSTEM
IN THE VICINITY OF LI TUNGSTEN, GLEN COVE, NEW YORK

FIGURE

E-1

103882

Finally, a significant but undetermined volume of site soils have been contaminated by the above materials.

Structures and Related Materials

There are 224 tanks of various sizes and shapes that have been inventoried during the site study. The total capacity of tanks is over 2,000,000 gallons. The tanks range from empty to full on current inventory, and approximately 350,000 gallons of liquid is in the tanks.

There are six (6) main buildings with associated ancillary equipment and support structures onsite that need to be removed. There is also a large inventory of scrap machinery and equipment that resides onsite. ~~There are~~ 23 transformers onsite believed to contain PCB (polychlorinated biphenyl), contaminated oils. There is a substantial asbestos inventory onsite which includes the sidings on buildings, tank covers, and pipe coverings.

1.2 IMMEDIATE HAZARDS

Several immediate hazards have been identified during the course of our site investigation work. All identified hazards were provided to Glen Cove Development Company in a project memorandum along with the recommendation that these hazards be remediated immediately. It is our understanding that the Glen Cove Development Company is currently developing a plan for addressing all identified immediate hazards. Once the plan is completed, the site would be in a relatively stable condition.

1.3 CURRENT AND FUTURE LIABILITIES

There are several rules and regulations that are applicable to the various parties involved in the Li Tungsten site. The critical rules deal with conditions that are immediate threats to the environment (e.g. oil spills) and the requirements once a party becomes involved. In summary, if an immediate threat to the environment or to human health exists, there are reporting obligations. If an owner has knowledge of such a condition onsite, then the owner is responsible for its remediation to the satisfaction of the regulatory agencies. The extent of liability, the potential for enjoining other potentially responsible parties (PRP) to assist in the cleanup and the general rules that apply or may apply to the various parties involved are addressed in greater detail in Section 3 of this report.

In this regard, RTP has reported to the Nassau County Health Department (NCDOH) and the New York State Department of Environmental Protection (NYSDEC) the results of the groundwater sampling program that fall into the reportable category.

This includes the oil contamination that surrounds the 500,000 gallon fuel tank, the organic plume that appears to be coming from the Mattiace property and the tetrachloroethene and organic plume that appears to be coming from the former laundry (Crown-Dyckman Uniforms) property.

1.4 MEASURES FOR SITE REMEDIATION

In all likelihood, whether or not Campon Realty decides to purchase the parcels, NYSDEC will classify the site as an inactive hazardous waste site and then require the owner to develop and implement a remediation plan to

cleanup the site. This is standard procedure for any site currently classified as an industrial site that is no longer in operation or is being converted to residential use in New York State (especially on Long Island). In addition, now that the NCDOH and NYSDEC have knowledge of the organic and oil spills that are uncontrolled on the property, there will be a cleanup action required regardless of ownership. The overall site cleanup and remediation plan will at a minimum, have several elements. Each of the currently identified elements are outlined in Table E-1.

The cost estimates in Table E-1 are separated into a best estimate which means the likely cost of cleanup and a conservative estimate if difficulties arise during remediation. The basis for each cost estimate and schedule is addressed below. Please recognize these prices are likely to hold for approximately 60-days from the date of this report. Delays in beginning remediation beyond that point will likely cause an increase in cleanup and remediation prices.

Liquids/Sludges in Tanks

RTP estimates that ~~350,000~~ gallons of various liquid waste need to be pumped and disposed. An additional 188,000 gallons will be produced during the cleaning of the tanks. This total comes to 538,000 gallons which at \$0.52 per gallon for removal and disposal amounts to a remediation cost of \$279,800. A one hundred percent contingency fee has been added to provide a conservative estimate of cleanup of \$559,600. This is based upon the fact that disposal costs vary due to available capacities of disposal facilities and the types of wastes involved. The current owner is likely to remediate 130,000 gallons of onsite liquids for a total savings of \$84,500. With remediation, the best estimate is therefore \$195,300, while the conservative estimate does not assume any immediate remediation.

TABLE E-1

ESTIMATED COSTS AND SCHEDULE FOR REMEDIATION

Material/Element	Estimated Cost of Cleanup (Best Estimate)	Estimated Cost of Cleanup (Conservative Estimate)	Schedule
1. Liquids/Sludges in Tanks	\$ 195,300	\$ 559,600	3-4 months
2. Tank Cleaning	203,000	243,600	3-4 months
3. Structural Demolition/Removal	1,020,000	1,530,000	6 months
4. Asbestos Removal/Disposal	486,300	656,300	2 months
5. Laboratory Packing/Disposal	65,500	236,000	2 months
6. Solid Waste Removal/Disposal	549,100	3,657,000	3-4 months
7. Transformer Removal/Disposal	85,700	119,400	2 months
8. PCE Spill Cleanup	675,000	1,100,000	5-10 years
9. Mattiace Spill Cleanup	550,000	975,000	5-10 years
10. No. 2 Oil Spill Cleanup	150,000	300,000	2 months
11. Mud Pond Cleanup	575,000	1,300,000	6 months
Subtotal Cost	\$ 4,554,900	\$ 10,677,100	
Management Cost	<u>750,000</u>	<u>1,500,000</u>	
TOTAL PROJECT COST	\$ 5,304,900	\$ 12,177,100	

Tank Cleaning

In order to neutralize the tankage in preparation for demolition, the tanks will be triple rinsed and the contents removed. The cost for this activity is \$203,000. A small contingency of twenty percent for unforeseen circumstances was added for the conservative estimate.

Structural Demolition/Removal

The structural demolition/removal of materials includes the demolition of all structures to grade and clearing the site. It assumes the materials to be disposed (including wood, steel and concrete debris) are acceptable to standard landfills and that most of the work will be completed by non-union labor. The cost is estimated at \$1,020,000. A modest contingency factor of fifty percent has been added to include removal of some of the materials as special waste or hazardous waste and the use of special labor. Costs for delaying demolition cannot be estimated.

Asbestos Removal/Disposal

The asbestos removal estimates are based on a visual inspection of the current site condition by an asbestos removal specialist. The largest cost item is the removal/disposal of the asbestos transite panels from the Dice Building (\$320,000). A total cost of \$486,300 includes the removal and disposal of additional asbestos observed around piping, tanks and building structures. (A contingency fee of thirty five percent) has been added to include additional asbestos that may be found hidden behind piping and other structures as demolition proceeds. The roof panels of the reduction

building may also test positive for asbestos and allowances must be made for that possibility. Before actual asbestos remediation begins, we would recommend a full engineering survey be completed to allow for bidding of the job at competitive rates.

Laboratory Packing/Disposal

There are three primary laboratories onsite that will be packed, shipped and disposed. A rough estimate is provided in that the exact price will be based on what specifically is found, the packing/shipping requirements and disposal requirements. A best estimate price is given at \$65,500 with a conservative estimate of \$236,000. The best estimate only includes testing, removing and disposing of the labs as packed. The conservative estimate includes complete lab packing, testing, disposal and removal of gas cylinders.

Solid Waste Removal/Disposal

Several scenarios are possible for the removal/disposal of solid wastes from the site. Which scenario is chosen will be highly dependent on regulatory agency requirements, which continue to become more restrictive and therefore more costly. In August, for example, there may be a new landfill law in New York and costs will escalate if the current law changes. The estimates assume various disposal options depending on material classification. The cheapest disposal options assume a landfill in Wayne, Michigan for a disposal cost of \$115/ton of material while the Model City, New York fill comes in at \$200 to \$260/ton depending on whether the material is hazardous or non-hazardous. Mr. John Li could take the materials to his plant in Buffalo, and in that case the price would probably be about \$35/ton for

removal plus transport in bulk or about a third of the best estimate price (\$167,000). Therefore, the costs as explained in the Enviropact Study can range from \$549,100 to \$3,657,000.

Transformers and Articles

The Empire Environmental proposal suggests slightly differing prices for removal/disposal of the transformers and PCB articles onsite. ~~The price~~ price assumes oil at 500 ppm or less of PCB. The conservative price assumes a 10,000 ppm PCB concentration which is above the values tested in stored oils onsite.

PCE Dry Cleaning Spill

The PCE organic contamination plume appears to be entering the property from the Northeast from the location of the former Crown-Dyckman Uniforms property. Current estimated cost for a pump and treat option is \$250,000 for capital equipment and \$85,000 per year operational costs. Two options, a 5 year and 10 year cleanup scenario at \$675,000 and \$1,100,000 for plume remediation, respectively, are provided. These are speculative costs that will depend on the final design and agency requirements relative to how clean is clean before a clean bill of health can be issued. Obviously, the final cleanup requirements may extend the cleanup period. Since the plume is not a result of Li Tungsten activities, the cost of cleanup would be borne by the owner initially but may be recoverable from the Federal USEPA, State, City or other PRPs.

Mattiace Property Spill

Sampling of the groundwater well placed to the north of the Mattiace property detected organic contamination that is suspected to be moving northward at a depth of 5 feet. The EPA is currently remediating the Mattiace parcel and this cleanup would likely include the parcel to the north of Mattiace. The restrictions that might be placed by NCDOH, may or may not include the prevention of construction of residential units. If the owner is forced to cleanup because of schedules/ requirements, the estimated costs of cleanup are approximated at \$125,000 capital cost with a \$85,000 per annum cost of operation/testing. This does not include the installation of a slurry wall to contain the Mattiace plume. As in the above example, 5 year and 10 year options are presented as the best and conservative cost estimates but may be extended because of final cleanup requirements.

No. 2 Fuel Oil Spills

The 500,000 gallon fuel tank onsite was placed onsite and leased by Hawkins Fuel Oil. Several spills have been reported and purportedly remediated. Our survey found substantial fuel oil contamination in the soils under the diked area surrounding the tank. The survey also noted a minor oil spill near the Creek at GMW-3 and GMW-5. Both of these spills are noted on Figure E-1. The cost to remediate the soil contamination is estimated by assuming that 1,000 cubic yards are to be removed. Thus, the best estimate price is \$150,000 and conservatively 2,000 yards may need to be removed at a cost of \$300,000. We would recommend that the excavated material be tested and disposed of via an asphalt processing plant.

Mud Pond Remediation

The mud pond is located just south of the 500,000 gallon fuel tank. The mud pond liner is leaking and therefore the pond area will probably need to be remediated. It is likely that regulatory agencies will be involved in the cleanup and therefore costs and schedules are somewhat speculative.

Assuming 5,000 yards of material will need to be removed at \$115/yd (best estimate, non-hazardous) and \$260/yd (conservative estimate, hazardous), the costs of cleanup are \$575,000 and \$1,300,000 respectively.

1.5 ESTIMATED TOTAL COST OF SITE REMEDIATION

The total cost of site remediation will be a function of the known elements as well as several unknown elements based on 1987 dollars. The known elements are the first seven items listed in Table E-1 from Liquids/Sludges in Tanks thru Transformer Removal/Disposal. These costs are likely to be fairly accurate estimates with the largest uncertainty being the Solid Materials Removal and Disposal element. To narrow down the range of costs for this option, regulatory agency as well as possible current tenant/owner discussions are necessary.

The unknown elements include the following:

- PCE Spill Remediation
- Mattiace Spill Remediation
- Oil Spill Remediation
- Mud Pond Remediation
- Metals in Groundwater/Soils
- Glen Cove Creek Cleanup

The first three elements on this list are probably attributable to third parties: one of whom is out of business (Crown-Dyckman Uniforms), one of whom is an EPA superfund site owner (Mattiace) and, finally, one who is still in business (Hawkins Fuel Oil). The remaining three are associated, in whole or in part, with activities at the Li Tungsten site over the years it was in operation.

The mud pond remediation costs have been estimated in that it is likely the regulatory agencies will want some remediation of the mud pond before giving the site a clean bill of health. The last two elements of this list, Metals in Groundwater and Glen Cove Creek Cleanup, have not been placed on the remediation cost estimate tabulation. At this point it is impossible to estimate whether these will need to be addressed or if addressed, what level of cleanup will be recommended. This is because tungsten contamination is rare and little information is currently available on health/environmental effects. For example, the health effects standards as well as recommended cleanup procedures for tungsten, have not been established by regulatory agencies. We would anticipate a lengthy tedious process for the regulatory agencies to accomplish this. Nevertheless, if it is determined that something must be done, RTP recommends that in the process of conducting discussions concerning site remediation with regulatory officials, the two unresolved questions raised by the cleanup of Glen Cove Creek and the metal contamination ~~be~~ be addressed as discussed below.

~~First, we suggest that~~ we propose that an integrated study of Glen Cove Creek be undertaken by the regulatory agencies. Second, we suggest that a health effects criteria review for tungsten be performed by an independent consultant with several components. A literature review of health

effects would be compiled. A draft criteria document would then be prepared establishing the known health effects. Finally, acceptable environmental and health levels would be proposed for use by regulatory agencies to support their decisions on site remediation.

Finally, management/liaison contractors will be necessary to discuss with the owner/state/other parties the variety of cleanup options, to develop specifications and acquire bids, to negotiate cleanup methods, to develop remediation plans, to evaluate bids, to manage site remediation, to perform final testing, to provide legal assistance, etc. These services are estimated to cost \$750,000 for completing the necessary tasks to get the site ready for development with a contingency of an additional \$750,000 if the likely worst case conditions were to apply.

In summary, based on the information gathered over the course of the site assessment, the total cost of cleanup/remediation including management is \$5,304,900, best estimate. By definition, the best estimate price is the likely cost of cleanup, if everything goes according to plan with little leeway for unforeseen problems or delays and basic concurrence by regulatory officials.

The conservative estimate to cleanup/remediate the site is \$5,177,100 and accounts for several conditions, terms and items that may cause problems. The largest item in the conservative estimate is the solid waste removal element which is \$3.7 million assuming that thirty percent of the materials are removed and disposed of as hazardous materials according to federal and state laws.

Finally, both estimated prices could be reduced substantially under several assumptions.

- o Should John Li move materials to his Buffalo Tungsten Facility at \$35/ton the solid waste removal/disposal costs could drop by as much as sixty five percent or more.
 - o Should EPA/DEC remediate the PCE spill, the actual cost of the project would be only in time/conditions placed on development. Total savings \$675,000 to \$1,100,000, respectively.
 - o Should EPA/DEC remediate the Mattiace spill, the actual cost of the project would be only in time/conditions placed on development. Total savings \$550,000 to \$975,000, respectively.
 - o Should EPA/DEC/others remediate the fuel oil spill, the total savings could be \$150,000 to \$300,000, respectively.
 - o Should the current owner remediate the immediate hazards onsite, cost savings of approximately \$200,000 could be realized on the conservative estimate only.
- [o Environmental Quality Bond Act monies are potentially available to address the Glen Cove Creek and metals contamination issues.

In conclusion, discussions with Mr. Li, Glen Cove Development Company and regulatory agencies will reveal the likelihood of each of the above potential actions and the probably extent of adjustments to cost estimates.

SECTION 2.0

INTRODUCTION


2.0 INTRODUCTION

2.1 Background.

This report describes the results of an environmental investigation performed at the former site of the Li Tungsten Corporation in Glen Cove, New York. The purpose of the investigation was to evaluate the existence and extent of potential environmental contaminants in order to estimate the appropriate procedures and costs for remediation of the site for residential development.

An aerial photo of the Li Tungsten plant is shown in Figure 1 and provides an overview of the size and complexity of the facility. Figure 2 is a site plan, which defines the major structures and features of the site. During industrial operations at the facility (which began in the 1940's), raw ore and scrap materials processing and smelting operations were conducted to produce tungsten products for sale to industry and the government. A detailed description of tungsten (tungsten alloy properties, tungsten processes, tungsten compounds, tungsten uses, etc.) is presented in the Appendix to this report. RTP has acquired standard aerial photos of the site and they are available as far back as 1950.

Most of the acid extraction, refining and processing operations for tungsten took place on the parcel of property south of Herb Hill Road and east of Garvies Point Road. Here numerous tanks of metal, fiberglass and wooden construction are found both inside and outside the buildings used for processing (Dice Building, East Building and Lounge Building). These were used during extraction, mixing and wastewater treatment operations. Also found on this parcel are offices and chemical laboratories where a



REFERENCE NO. 5

103898

PRELIMINARY ASSESSMENT
OFF SITE RECONNAISSANCE
INFORMATION REPORTING FORM

Date: 7/20/89

Site Name: LI TUNGSTEN

TDD: 02-8807-78

Site Address: 63 HERB HILL ROAD
Street, Box, etc.

GLEN COVE
Town

NASSAU
County

NEW YORK
State

NUS Personnel:	Name	Discipline
	<u>STEVEN OKUNAKI</u>	<u>GEOLOGIST</u>
	<u>DEBORAH COHEN</u>	<u>CIVIL ENGINEER</u>

Weather Conditions (clear, cloudy, rain, snow, etc.):

OVERCAST

Estimated wind direction and wind speed: NONE

Estimated temperature: 75°F

Signature: [Signature]

Date: 7/20/89

Countersigned: [Signature]

Date: 7/20/89

PRELIMINARY ASSESSMENT
INFORMATION REPORTING FORM

Date: 7/20/89

Site Name: LI TUNGSTEN

TDD: 02-8907-28

Site Sketch:

Indicate relative landmark locations (streets, buildings, streams, etc.).
Provide locations from which photos are taken.

SEE ATTACHED SHEET

Signature: Tom O'Neil

Date: 7/20/89

Countersigned: Debra Sun

Date: 7/20/89

PRELIMINARY ASSESSMENT
INFORMATION REPORTING FORM

Date: 7/20/89

Site Name: LI TUNGSTEN

TDD: 02-8907-78

Notes (Periodically indicate time of entries in military time):

ARRIVED ON SITE AT 12:00 PM. BACKGROUND
READING ON MINI-RAD = 0.01 MR/HR. PARKED VEHICLE
ON HERB HILL ROAD NEAR LARGE ABOVE GROUND TANKS,
WHICH ARE FENCED OFF WITH 6-CHAIN LINK AND YELLOW CAUTION TAPE.
TOOK PHOTO F1. WALKED TO PLANT MAIN ENTRANCE GATE WHICH WAS
PADLOCKED, SAW RUSTING STACKED 55-GALLON DRUMS AND
WOODEN PALLET. BUILDINGS WINDOWS ARE BOARDED UP BUT
SOME DOORS ARE OPEN. TOOK PHOTOS OF SIGN (F2) AND
STACKED DRUMS (F3), STARTING TO RAIN. MOVED VEHICLE TO
GARVIES POINT ROAD ACROSS FROM HAWKINS FUEL COMPANY.
PARKED NEXT TO MUD POND WHICH IS FENCED OFF FROM VIEW
BY 6' WOODEN FENCE. SOIL ~~AND~~ BETWEEN FENCE AND PONDWAY
IS BLACKENED AND STAINED, ALSO SMELLS "ORGANIC".
TOOK PHOTO OF MONITORING WELL IN FRONT OF FENCE AND MUD
POND (F4). PHOTO OF LARGEST BUILDING NEXT TO HAWKINS FUEL OIL
COMPANY (F5), WELL # EMW-4, PADLOCKED. MOVED VEHICLE TO
CORNER OF HERB HILL ROAD AND DICKSON LANE. PHOTO OF
MONITORING WELL GM-8 IN AREA OF ABOVE GROUND TANKS - FENCED OFF.
PHOTO (F6). NO PILES SEEN IN THIS AREA. STORM DRAINS ALONG HERB
HILL ROAD.

Signature: Tom O'Reilly

Date: 7/20/89

Countersignature: DMW

Date: 7/20/89

PRELIMINARY ASSESSMENT
INFORMATION REPORTING FORM

Date: 7/20/89

Site Name: LI TUNG SIEN

TDD: 02-8907-38

Notes (Cont'd):

TOOK PHOTO OF ENTRANCE TO NEW WAREHOUSE BUILDING
THROUGH CHAIN LINK FENCE (PHOTO ⁵⁹⁷⁷F7), PHOTO ⁵⁹⁷⁸(F8) OF
GREY 30-GALLON DRUMS STAKED ABOVE WOODEN FENCE ON
CORNER OF HART HILL ROAD (SE CORNER) AT INTERSECTION.
MOVED VEHICLE NORTH ALONG DICKSON LANE AND PARKED
ACROSS FROM REDUCTION BUILDING. TOOK PHOTO OF ⁵⁹⁷⁹(F9)
UNCOVERED, BLACK, FINE GRAINED PILES (3 IN NUMBER) ⁵⁹⁸⁰(F10)
APPROXIMATELY 50 FEET FROM RYADWAY (DICKSON LANE) ON
EAST SIDE OF ROAD. PHOTO ⁵⁹⁸¹(F9) OF ENTRANCE TO OPEN
REDUCTION BUILDING SHOWING 55-GALLON RUSTED DRUMS.
NO READINGS ABOVE BACKGROUND ON MINI-RAD. LEFT
SITE AT 1:00 P.M. (EASIER ACCESS TO SITE ALONG
LANDING ROAD AND MAKE LEFT TURN TO ELLWOOD AVE).

Attach additional sheets if necessary. Provide site name, TDD number, signature, and countersignature on each.

Signature: Jim O'Reilly

Date: 7/20/89

Countersignature: Bob Sw

Date: 7/20/89

PRELIMINARY ASSESSMENT
INFORMATION REPORTING FORM

Date: 7/20/89

Site Name: LT TUNG TEN

TDD: 07-8907-28

Photolog: DE BORMA COHEN - PHOTO GRAPHIC

Frame/Photo Number	Date	Time	Photographer	Description
✓ F1 (52P1)	7/20/89	7:05	D.C.	- VIEW OF TRUCK GROUP TRUCKS LOOKING NORTH ON HUAH HILL ROAD.
✓ F2 (52P2)	7/20/89	17:09	D.C.	- MAIN ENTRANCE OF LT TUNG TEN - SEEN - SOUTH VIEW
✓ F3 (53P3)	7/20/89	17:10	D.C.	- STAKED TREES, NORTH VIEW IN MAIN ENTRANCE, SOUTH VIEW
✓ F4 (54P4)	7/20/89	17:20	D.C.	- MUD ROAD, MONITORING WELL SCATTERED VEGETATION, NORTH VIEW
✓ F5 (55P5)	7/20/89	17:21	D.C.	- LT WAREHOUSE AND ADJACENT HANDLING FUEL CO. SE VIEW
✓ F6 (56P6)	7/20/89	17:30	D.C.	- EAST VIEW OF AREA IN FRONT OF TRUCKS AND MONITORING WELL GAT-8.
✓ F7 (57P7)	7/20/89	17:31	D.C.	- ENTRANCE TO NEW WAREHOUSE BUILDING SHOWING OPEN DOORS - DRUMS
✓ F8 (58P8)	7/20/89	17:37	D.C.	- GREY STAKED TREES ON CORNER SE VIEW OF HANDLING CORNER
✓ F9 (59P9)	7/20/89	17:53	D.C.	- ENTRANCE TO REFLECTION POOL SHOWING TREES AND BUILDINGS
✓ F10 (60P10)	7/20/89	17:40	D.C.	- OPEN AREA FENCE ON EAST SIDE OF REFLECTION POOL

Attach additional sheets if necessary. Provide site name, TDD number, signature, DICKSON
and countersignature on each.

Signature: Don Cohen

Date: 7/20/89

Countersignature: Don Cohen

Date: 7/20/89


LI TUNGSTEN 103904-1047
 1/20/89

103904-1047



COMPILED BY V GLASSER
 PREPARED BY S SCHAEFFNER
 PROJECT NO. V GLASSER
 DATE 4-88
 SCALE SHOWN
 FILE NO
 N1342L11-1047

RTP ENVIRONMENTAL ASSOC., INC.
 Glen Cove, New York



• PHOTO
 SITE #
 ARROW SHOWS
 DIRECTION OF
 PHOTO

ENTRANCE TO
 PLANT

EXPLANATION

- II PARCEL NUMBER
- MONITORING WELL LOCATION
- PROPERTY/PARCEL BOUNDARY
- == DIRT ROAD

SUBJECT

LOCATION OF MONITORING WELLS, LI TUNGSTEN FACILITY,
 GLEN COVE, NEW YORK

FIGURE

2

103904

REFERENCE NO. 6

103905

REFERENCE NO. 7

103906

New York

N. Y.—CONN.—N. J.

1:250 000-scale map of Atlantic Coast Ecological Inventory



Produced by
U. S. FISH AND WILDLIFE
SERVICE
1980

436	Bittern
437	Great blue heron (S)
438	Wood ibis (S)
439	Anhinga
440	Little blue heron (S)
441	Yellow-crowned night heron (S)
442	Black-crowned night heron
443	Florida sandhill crane (S)
444	Louisiana heron (S)
445	Limpkin (S)
446	Roseate spoonbill (S)
447	Snowy egret (S)
448	Magnificent frigate-bird (S)
449	Reddish egret (S)
450	Clapper rail
451	King rail
452	Virginia rail
453	Sora rail
WATERFOWL (461-500)	
461	Waterfowl
462	Swans
463	Geese
464	Dabbling ducks
465	Diving ducks
466	Common eider
467	Marlequin duck
468	Wood duck
469	Fulvous tree duck
470	Loons
471	Grebes
472	Brant geese
473	Snow goose
474	Gadwall
475	Black duck
RAPTORS (501-530)	
501	Raptors
502	Owls
503	Kites
504	Hawks
505	Bald eagle (F)
506	Osprey (S)
507	Peregrine falcon (F)
508	Copper's hawk (S)
509	Swallow-tailed kite
510	Marsh hawk (S)
511	Southeastern American kestrel (S)
512	Florida burrowing owl (S)
SEABIRDS (531-550)	
531	Seabirds
532	Petrels, shearwaters, and albatrosses
533	Pelican and allies
534	Alcids
535	Brown pelican (F)
536	Black guillemot
537	Leach's petrel
538	Razorbill
539	Common puffin
540	Double-crested cormorant
541	Gannet
542	Wilson's petrel
543	Northern phalarope
544	Audubon's shearwater
545	Greater shearwater
546	Shearwaters
547	Petrels
548	Jaegers
549	White pelican
SONGBIRDS AND OTHERS (551-600)	
551	Songbirds and others
552	Red-cockaded woodpecker (F)
553	Chachalaca
554	Bachman's warbler (F)
555	Wild turkey
556	American woodcock
557	Pileated woodpecker
558	Swainson's warbler
559	Ruffed grouse
560	Bobwhite
561	Mourning dove
562	Warblers
563	Ring-necked pheasant
564	Bank swallow
565	Dusky seaside sparrow (F)
566	White-crowned pigeon (S)
REPTILES AND AMPHIBIANS (601-700)	
601	Eastern narrow-mouthed toad (S)
602	Eastern indigo snake (F)
603	American alligator (F)
604	Northern diamondback terrapin
605	Amphibians
606	Greater siren
607	Bog turtle (S)
608	Gopher tortoise (S)
609	Eastern tiger salamander (S)
610	Northern fence lizard
611	Five-lined skink
612	Map turtle
613	Plymouth red-bellied turtle (F)
614	Eastern diamondback rattlesnake
615	Carolina gopher frog
616	Florida gopher frog (S)
617	Atlantic salt marsh watersnake (F)
618	American crocodile (F)
619	Florida Keys mole skink (S)
620	Florida black-headed snake (S)
621	Pine barrens tree frog (S)
622	Northern pine snake (S)
623	Corn snake (S)
624	Timber rattlesnake (S)
625	Southern gray tree frog (S)
MAMMALS (701-800)	
701	Beaver
702	White-tailed deer

AQUATIC ORGANISMS
Shown in BLUE, species with special status shown in RED (F) or (S) indicates species protected by Federal or State Legislation (see text)

SYMBOL	SPECIES
↓	PLANTS (1-50)
●	1 Irish moss
●	2 Rockweed
●	INVERTEBRATES (51-100)
●	51 Crabs
●	52 Mussels
●	53 Oysters
●	54 Scallops
●	55 Clams
●	56 Worms
●	57 Shrimp
●	58 American lobster
●	59 Blue crab
●	60 Eastern oyster
●	61 European oyster
●	62 Bay scallop
●	63 Deep-sea scallop
●	64 Calico scallop
●	65 Surf clam
●	66 Hard clam
●	67 Soft shell clam
●	68 Brackish-water clam
●	69 Bloodworm
●	70 Sandworm
●	71 White shrimp
●	72 Brown shrimp
●	73 Northern shrimp
●	74 Rock crab
●	75 Jonah crab
●	76 Whelk
●	77 Ocean quahog
●	78 Pink shrimp
●	79 Stone crab
●	80 Spiny lobster
●	FISH (101-200)
●	101 Sharks, skates, rays
●	102 Herring
●	103 Salmon and trout
●	104 Catfish
●	105 Cod
●	106 Sunfish and bass
●	107 Drum
●	108 Flatfish
●	109 Longnose gar
●	110 Shortnose sturgeon (F)
●	111 Atlantic sturgeon (S)
●	112 American eel
●	113 Blueback herring
●	114 Hickory shad
●	115 Alewife
●	116 American shad (S)
●	117 Atlantic menhaden
●	118 Atlantic herring
●	119 Gizzard shad
●	120 Tarpon
●	121 Atlantic salmon
●	122 White catfish
●	123 Channel catfish
●	124 Yellow bullhead
●	125 Brown bullhead
●	126 Flat bullhead
●	127 Sea catfish
●	128 White perch
●	129 Striped bass
●	130 Black sea bass
●	131 Redbreast sunfish
●	132 Warmouth
●	133 Bluegill
●	134 Largemouth bass
●	135 Black crappie
●	136 Sheepshead
●	137 Spotted seatrout
●	138 Weakfish
●	139 Spot
●	140 Atlantic croaker
●	141 Southern kingfish
●	142 Northern kingfish
●	143 Gulf kingfish
●	144 Red drum
●	145 Star drum
●	146 Black drum
●	147 Summer flounder
●	148 Southern flounder
●	149 Winter flounder
●	150 Rainbow smelt
●	151 Atlantic tomcod
●	152 Threadfin shad
●	153 Carp
●	154 Atlantic mackerel
●	155 Chain pickerel
●	156 White bass
●	157 Northern puffer
●	158 Silver perch
●	159 Florida pompano
●	160 Bluefish
●	161 Spanish mackerel
●	162 Cobia
●	163 Mullet
●	164 White crappie
●	165 Redear sunfish
●	166 Smallmouth bass
●	167 Yellow perch
●	168 Pumpkinseed
●	169 Atlantic herring
●	170 Atlantic cod
●	171 Pollock
●	172 Haddock

000-00

103908

TERRESTRIAL ORGANISMS

Shown in BROWN, species with special status shown in RED-(F) or (S) indicates species protected by Federal or State Legislation (see text)

SYMBOL

SPECIES

PLANTS (301-350)

- 301 Eastern hemlock
- 302 Spleenwort (S)
- 303 Spider lily (S)
- 304 Pond bush (S)
- 305 Watermilfoil (S)
- 306 Hooded pitcher plant (S)
- 307 Tree
- 308 Prickly pear cactus (S)
- 309 Trailing arbutus (S)
- 310 Eastern bumelia
- 311 Pitcher plant
- 312 Baldcypress
- 313 Redbay
- 314 Seaside alder
- 315 Box huckleberry
- 316 Purple fringeless orchid
- 317 Pink lady's slipper
- 318 Ebony spleenwort (S)
- 319 Orchids (S)
- 320 Golden club (S)
- 321 Florida beargrass
- 322 East-coast coontie
- 323 Fall-flowering ixia
- 324 Jackson-vine
- 325 Spoon-flower
- 326 Curtiss milkweed
- 327 Sea lavender
- 328 Hand fern
- 329 Needle palm
- 330 Yellow squirrel-banana
- 331 Beach creeper
- 332 Florida coontie
- 333 Four-petal pawpaw
- 334 Bird's nest spleenwort
- 335 Burrowing four-o'clock
- 336 Beach star
- 337 Silver palm
- 338 Dancing lady orchid
- 339 Tamarindillo
- 340 Fuch's bromeliad
- 341 Everglades peperomia
- 342 Buccaneer palm
- 343 Slender spleenwort
- 344 Pineland jacquemontia
- 345 Mahogany mistletoe
- 346 Florida thatch
- 347 Twisted air plant
- 348 Long's bittercress
- 349 Venus's flytrap

INVERTEBRATES (351-400)

- 351 Monarch butterfly
- 352 Zebra butterfly

BIRDS (401-600)

SHOREBIRDS (401-430)

- 401 Shorebirds
- 402 Terns
- 403 Gulls
- 404 Forster's tern
- 405 Arctic tern
- 406 Least tern (S)
- 407 Roseate tern (S)
- 408 Common tern
- 409 Great black-backed gull
- 410 Herring gull
- 411 Laughing gull
- 412 Black skimmer (S)
- 413 Turnstones
- 414 Plovers
- 415 Piping plover
- 416 American oystercatcher (S)

WADING BIRDS (431-460)

- 431 Wading birds
- 432 Herons
- 433 Egrets
- 434 Rails
- 435 Ibises
- 436 Bitterns
- 437 Great blue heron (S)
- 438 Wood ibis (S)
- 439 Anhinga
- 440 Little blue heron (S)
- 441 Yellow-crowned night heron (S)
- 442 Black-crowned night heron
- 443 Florida sandhill crane (S)
- 444 Louisiana heron (S)
- 445 Limpkin (S)
- 446 Roseate spoonbill (S)
- 447 Snowy egret (S)
- 448 Magnificent frigate-bird (S)
- 449 Reddish egret (S)
- 450 Clapper rail (S)
- 451 King ra
- 452 Virginia ra
- 453 Sora ra

WATERFOWL (461-500)

- 461 Watertow
- 462 Swans
- 463 Geese
- 464 Dabbling ducks
- 465 Diving ducks
- 466 Common eider
- 467 Marle duck
- 468 Wood duck
- 469 Fulvous tree duck

HABITAT USE

Shown in RED for species with special status, BLUE for aquatic organisms and BROWN for terrestrial organisms

- | | |
|------------------------------|------------------------------------|
| a Spawning ground | f Sport fishing/hunting area |
| b Nursery | g Migratory area |
| c Commercial harvesting area | h Nesting area |
| d Adult concentration | i Unusual distribution or specimen |
| e Overwintering area | |



TRANSVERSE MERCATOR PROJECTION

BLACK NUMBERED LINES INDICATE THE 10,000 METER UNIVERSAL TRANSVERSE MERCATOR GRID, ZONE 18

103910

REFERENCE NO. 8

WASTE CHARACTERIZATION REPORT

LI TUNGSTEN SITE

GLEN COVE, NEW YORK

PREPARED FOR

RTP ENVIRONMENTAL ASSOCIATES, INC.
400 POST AVENUE
WESTBURY, NEW YORK 11590

PREPARED BY

ENVIROPACT NORTHEAST, INC.
540 PALMER ROAD
YONKERS, NEW YORK 10701

APRIL 29, 1988

VOLUME I

103912

1.2 SITE DESCRIPTION AND LOCATION

The Li Tungsten facility (Figure 1), located in Glen Cove, New York, consists of several parcels of land, approximately 20 acres in size. Due to the size of the property and for the purpose of reporting data, the parcels were specifically identified as follows:

- * Area A is located south of Herb Hill Road and east of Garvies Point Road. Five buildings are located in this area. However for sampling purposes, Area A represents only the outdoor areas (Figure 2).

- * Area D refers to the Dice Building, a warehouse which is located on the southern side of Area A. The south wall of the Dice Building is bordered by the Glen Cove Creek. All sampling was done inside the building (Figure 2).

- * Area B is located to the east of Dickson Lane and north of Herb Hill Road. The area is presently used as a parking lot to the south and is mostly wooded to the north. There are no buildings located in this area (Figure 3).

- * Area C refers to the parcel of land west of Dickson Lane and north of Garvies Point Road. There are two buildings on this property; the New Warehouse and the Reduction Building. On the south end there is a lined lagoon. Just north of the lagoon is a large fuel tank (Figure 4).

2.0 FIELD EFFORT

2.1 SITE RECONNAISSANCE

2.1.1 HEALTH & SAFETY

Due to the current condition of the site, a health and safety plan, identifying the expected hazardous material and levels of safety necessary to protect the health and safety of Enviropact Northeast, Inc. field personnel was developed (Attachment 2).

2.1.2 SUMMARY OF SITE RECONNAISSANCE

A preliminary site reconnaissance was performed on March 25, 1988 to identify the solid waste on site in order to ascertain the type of material that would be included in the inventory. This inspection was performed by two Enviropact Northeast, Inc. personnel, a representative of RTP Environmental Associates, Inc. and a representative of Li Tungsten, the former site owner. During the inspection the Li Tungsten representative pointed out materials on site which would require disposal and material which would be retained by the previous owner. As a result of this inspection the following solid wastes were identified for disposal:

(a) In area A (Figure 2), drums, crates and piles were identified outside of buildings. The majority of this material was located on the north side of the Dice building, the south

side of the Carbide building, and adjacent to the East Building. Additional material was also stored along the property fence on the corner of Herb Hill Rd. and Garvies Point Road. The material was primarily stored in 55 and 30 gallon drums, many of which had corroded with their contents spilling on the concrete pavement. Liquid drums were also dispersed throughout the area, however the Li Tungsten representative could not identify their contents, but assured us that they did not contain organics a statement which was later found to be inaccurate.

(b) Inspection of the Loung building indicated the presence of asbestos. All 30 gallon drums stored in this building were empty according to the Li Tungsten representative. Upon examination this was confirmed.

(c) Inspection of the East building indicated the presence of numerous tanks but no solid waste or any other type of solid materials. The area inside this building was flooded with water.

(d) The Li Tungsten representative was asked on several occasion if chemicals other than those stored in the tanks were present on site. He repeatedly denied that any type of chemical, organic or non-organic, was being stored on site and did not identify the laboratory area as an area of concern.

(e) The inspection of the Dice and Warehouse Building, area D (Figure 2), revealed the warehousing of large quantities of

processed ore. Most of this material was stored in 55 and 30 gallon drums, and crates. The material seemed to be stored in lots identified by I.D. numbers. The Li Tungsten representative was asked if quantities could be retrieved by lot number. His response was that it would be time consuming and that much of the information was not available on site. Many of the drums showed signs of corrosion, especially in areas where flooding had occurred. Much of the material had spilled onto the floor. Drums were dangerously stacked three and four drums high, and close together, making access for sampling a problem. The Li Tungsten representative estimated that approximately 1 million pounds of processed ore was being warehoused in this building. Some of the material was being prepared for shipment, but no indication was given as to what specific lots would be removed. Overall this building contained the major portion of the solid waste which would need to be disposed of.

(f) Opposite and to the south of the Dice Building there is a partially covered storage area. This area is being used to store old equipment with no evidence of solid waste was being stored.

(g) The Carbide building contained no solid waste. On the outside of this building facing Herb Hill Road, several transformers were identified. The Li Tungsten representative was asked if the transformer oil had been recently tested. He indicated that some transformers had been tested and that he would provide RTP this information.

(h) Three concrete settling tanks were identified on the west side of the Dice building. According to the Li Tungsten representative these received processed water from the Dice Building which was then transferred to the lagoon located in area C across the road.

(i) Three outfalls were referred to, but not identified. The Li Tungsten representative was asked to provide the old SPDES permit. Examination of the permit indicated that the facility was required to monitor 17 parameters including pH and heavy metals.

(j) Area C (Figure 4), west of Dickson Lane was also inspected. In this area a lagoon and two small mud holes were identified as having received process water from the facility. The lagoon was lined and partially covered with what was assumed to be rain water. Upon closer inspection of the liner it was apparent that it had been perforated by vegetative growth. The lagoon contained sludge that had apparently settled out during previous years. The two small mud holes also showed signs of having received discharge during previous years.

(k) The New Warehouse building also located in area C was inspected. The building is used to store large quantities of materials which according to the Li Tungsten representative will be removed and retained by the former owner. Based on his instruction no attempt was made to identify the type of material located in this building.

(l) Outside the New Warehouse building quantities of materials similar to those previously identified in area A and D

were identified and inspected. The material are stored along the south, west and east walls of the building in crates and 55 gallon drums. It was indicated that these materials would need to be inventoried and disposed of. Outside and east of the building in question several transformers were also identified .

(m) The Reduction building houses the refractory furnaces. No solid waste or other types of solid materials were identified. Outside this building several transformers were also identified.

(n) West of the Reduction building the landscape slopes upward to an area where additional material was identified. This material was identified as wastes from the refractory furnaces by the Li Tungsten representative. Although the landscape naturally slopes upward in the surrounding area it would appear that past disposal practices had created a sizeable man made mound. At the summit of this mound, several piles of distinctly colored material were also identified. No additional information was provided on the extent of filling that was performed in this area in the past.

(o) Across the street from the Reduction Building and new Warehouse Building is a vacant lot referred to as area B. The area is partially wooded to the north, with clearings spotted throughout. At one such clearing which can be seen from the road, seven piles of material similar to those reported in area C were identified. Apparently this area also had been partially filled, since it did not conform with the general slope of the landscape. A clearing to the south and adjacent to Herhill Rd. formerly used as a parking area - by Li Tungsten employees is

presently being used to store junked cars. The drainage in this area is to the south. Overland runoff is captured by an intermittent creek that empties into a small pond.

2.2 INVENTORY OF WASTE

Based on this preliminary reconnaissance, Enviropact Northeast formulated its approach to conduct a comprehensive inventory of the solid waste material that would require disposal. The approach entailed the enumeration of all drums and crates, and measurements of piles to determine approximate volumes. The inventory was performed in conjunction with the sampling effort in order to save time. A team of three Enviropact personnel which consisted of a chemist, a remediation expert and a technician performed the inventory and collected samples of the materials previously identified. In addition to making an inventory of the solid waste the team identified and enumerated drums containing liquids. These drums were not sampled. The base map indicates the location of the material inventoried (Figures 5 through 8). The result of the inventory is found in Tables 1 through 4.

2.2.1 SOLIDS

AREA A

A physical inventory of the number of drums, crates, and piles of material was made. Approximately 155 crates, 826 fifty-five gallon drums (Figure 5), and 480 thirty gallon drums were counted in this area. Based on the capacity of these containers,

estimated volumes (cubic yards) were developed and converted to tons by multiplying by a weight factor of 1.5 tons/cu. yd. The only exception was A-12, where boundaries and height of the waste were used to determine volumes. As a result, the total volume and tonnage in area A was estimated to be 942 cu. yds. and 1413 tons, respectively. (See Table 1.)

AREA D

A physical inventory of the number of drums, crates, and piles of material was made (Figure 8). Approximately 288 crates, 2726 fifty-five gallon drums, and 3,823 thirty gallon drums were counted in this area. Total volume and tonnage was determined as previously described in Area A. As a result, the total volume and tonnage in Area D was estimated to be 1,588 cu. yds. and 2,382 tons, respectively (See Table 2).

AREA B

As previously described, the bulk of the material in this area was either in piles or landfill. In view of this situation, Enviropact requested that a surveyor develop estimated volumes for this area. As a result of the surveyor's input, approximately 325 cu. yds. were estimated for the seven piles of material, and 6,000 cu. yds. for the landfill area west of the intermittent creek, and north of the pond (Figure 6). Using the weight conversion factor, approximately 9500 tons of material has been identified in this area (See Table 3).

AREA C

The two major sources of material in this area were identified in crates and drums, and in a filled-in area behind

the Carbide Building (Figure 7). Approximately 276 crates and 197 fifty-five gallon drums were counted outside the New Warehouse Building. As a result of the surveyor's input, it was estimated that approximately 2000 cu. yds. of filled material may be found in Area C. Using the weight conversion factor, approximately 3494 tons of material has been identified in this area. (See Table 4.)

2.2.2 LIQUIDS

Although not in the original scope of work, Enviropact conducted a preliminary inventory of liquids in drums throughout the site. A total of 64 fifty-five gallon drums were identified in Area "A". In area "D" a total of 37 fifty-five gallon drums and 30 thirty gallon drums were identified as containing liquids. With the exception of the 30 drums which were tested for P.C.B., all other drums contents were not analyzed. Many of these drums showed signs of deterioration.

Also not included in the original scope of work was the cost estimate for the disposal of the liquids in the tanks. Table 5, to the best of our knowledge, summarizes the results of the a liquid inventory conducted by American Environmental-Technologies Corp. Based on their inventory, 64 tanks were identified to contain 312,000 gallons of liquid material. In addition to the 69 tanks which had been identified by contents and volume of contents, approximately 67 could not be included in our inventory because of unavailable information on current

contents and volumes. It should be noted that the bulk of the tanks were located in areas A and D.

2.2.3 MISCELLANEOUS WASTE

At the request of RTP, Enviropact conducted a preliminary inventory and review of areas needing immediate action. These areas of concern were identified by RTP. Subsequently, Enviropact was asked to develop cost estimates for corrective action. The following areas were identified as needing immediate action:

(a) Secure lab chemicals located in office/lab building. Approximately 9,500 sq. ft. of laboratory space was used to store various types of laboratory chemicals. The chemicals are in liquid and solid form and are contained in glass bottles and large bulk drums. Because the building roof is rapidly deteriorating, ceiling tiles are coming down on chemical containers causing spillage and emission of dangerous vapors. No inventory of the laboratory chemicals was made, since the area was considered unsafe and outside the original scope of work. In view of this situation, cost estimates were made based on a visual inspection of the area.

(b) Drum overpacking of all drums containing liquids assumed to be organic, located throughout the site as noted in Table 6. A preliminary inventory conducted by Enviropact identified 101 fifty-five gallon drums needing to be repacked and 30 thirty gallon drums that needed their liquid contents to be transferred to fifty-five gallon drums.

(c) Removal and disposal of water covering the floor of the Dice Building and East Building. It was estimated that approximately 19,000 gallons would require removal and disposal. Samples collected indicated pH range of 6 to 6.5, with high nickel content (>4000 ppm).

(d) Secure and dispose of gas cylinders located in the office and laboratory area. A preliminary inventory provided by RTP, indicated the presence of 22 cylinders; their contents including hydrogen sulfide and chlorine gas.

(e) The immediate transfer and/or disposal of approximately 129,000 gallons of liquids from tanks which were identified by AET as deteriorating to a point of possible leakage. The evaluation of tank conditions was not performed by Enviropact, and we assume no responsibility for the accuracy of this assessment. The tanks must also be triple rinsed before they can be dismantled and disposed of. The rinse water (approximately 25,000 gallons) will need to be disposed of accordingly.

(f) Cover lagoon area with liner in order to eliminate the percolation of rain water through sludge material in the lagoon.

2.3 SAMPLE COLLECTION

Samples collected throughout the site are identified on Figures 5 through 9, depending on the area sampled. Approximately 200 samples were collected across the site for various analyses.

2.3.1 CONTAINERIZED SOLID WASTE SAMPLES

Materials in areas A, C and D, found in either drums or crates, were sampled for metals analysis. These were collected

in plastic bags, using plastic or P.V.C. sampling equipment to remove material from the containers. Most of these materials were stored in lots. The sampling attempted to acquire a representative sample for each lot encountered. Where lot sizes were unclear, Enviropact personnel established physical boundaries for sampling purposes.

Materials in area A were badly weathered. Many drums and crates were collapsed, resulting in materials deposited on the ground. Samples A-1 through A-24e were collected in this area, (Figure 5).

Materials in area C were also badly weathered and discharging their contents directly to the ground. Samples C-15, C-16 and C-20 were collected in this are, (Figure 7).

Materials in area D were located throughout the Dice Building. The samples taken in this area displayed a greater variety in physical appearance (color, consistency, etc.). Many stacks of drums had toppled over, and many more gave the appearance that they could fall at any time. This situation made sampling very difficult and dangerous. Representative samples, by lot, were collected in area D, with some samples apparently representing raw materials (See Table 2). Samples D-1 through D-113 were collected in this area. (Figure 8)

2.3.2 WASTE PILE SAMPLES

Materials in areas B and C appear to have been landfilled from the Li Tungsten operation. These materials appear to differ by color and consistency for each pile. They also appear to be

different from the processed material predominant throughout areas A and D. A composite of each pile was made by collecting multiple surface samples of visually similar material.

Piles in area B were also sampled as previously described. Samples B-1 through B-7 were collected in this area. An area south of these samples, currently used to store old tanks and tank trucks, may also have been subjected to some landfilling. Sample B-10 was collected in this area. (Figure 6)

2.3.3 P.C.B. SAMPLES

Grab samples were collected throughout the site in those areas where P.C.B. contamination was thought to be a concern. All samples were collected in 40 ml. septum vials. Due to the age of the transformers on site, it was anticipated that they would contain P.C.B. Five samples, A-53, A-58, A-64, C-21 and D-99 were collected for P.C.B. analysis (Figures 5, 7 and 8). Additionally, a P.C.B. sample was collected from some open-head, 30 gallon drums located inside the Dice Building and the oil recovery sump to the west of the Dice Building.

2.3.4 VOLATILE ORGANICS SAMPLES

Grab samples were collected throughout the site in those areas where volatile organics contamination was thought to be a concern. All samples were collected in 40 ml. septum vials. A total of 26 samples were collected for VOC across the site. These include samples A-50 through A-63, A-8, B-9, B-10, C-1, C-5, C-11, C-12, C-18, C-19, C-21, D-9 and D-94. (See Figures 5

through 8.)

2.3.5 PRIORITY POLLUTANT SAMPLES

Grab samples were collected from four locations across the site (Figure 9). These sample locations were selected based on their ability to reflect potential contamination resulting from the facility's past activities. All samples were collected in glassware cleaned to E.P.A. specifications.

2.3.6 RADIOCHEMICAL SAMPLES

Three samples were composited from various waste containers in area A and area D to determine the radioactive potential of the wastes on site.

2.3.7 OUTFALL SAMPLES

Samples were collected at the east and west outfalls (004 and 005) entering Glen Cove Creek. Due to the inactivity of the outfalls themselves, sediment samples were collected directly below each outfall. A metal dredge was used to collect the organic samples and a PVC rod was used to collect the metal samples.

2.3.8 MISCELLANEOUS SAMPLES

Additional samples were collected throughout the site in areas of general concern, i.e., lagoons, drainage areas, etc.

3.0 DISCUSSION OF ANALYTICAL RESULTS

3.1 WASTE CHARACTERIZATION

The characterization of solid waste as hazardous was performed in accordance to R.C.R.A. definitions of the term "hazardous waste". According to this definition, any solid waste that is either ignitable, corrosive, reactive or toxic is considered hazardous. Each characteristic is defined in complex and comprehensive terms. Some substances are mentioned by name. Other materials are identified by the industrial process in which they are produced.

The actual rules are complicated and voluminous; in order to make the regulatory criteria specific, so that coverage is broad enough, but no broader than necessary to insure public safety and environmental protection. The present consensus within the regulatory community is that, where the regulators erred, they erred on the side of caution, resolving uncertainties in favor of inclusion rather than exclusion. Since the burden of finding out whether a material is covered by the definition falls solely on the regulated party, uncertainties have to be resolved according to applicable standards.

With regard to the solid material located on site, the determination of its potential hazardous nature was based on the results of the analysis for the 8 R.C.R.A. metals and the Extraction Procedure Toxicity (40CFR 261.24(a)). Toxicity has a special and very precise meaning in the context of characteristic

wastes. The regulations contain a list of fourteen substances which, if present in an extract of the material sampled at threshold concentrations, render the entire waste stream subject to regulation as a hazardous waste. A list of the prominent metals and their thresholds is found below:

TABLE 7

MAXIMUM CONCENTRATION OF METAL CONTAMINANTS
FOR CHARACTERISTIC OF E.P. TOXICITY

Arsenic	5.0 mg/l
Barium	100.0 mg/l
Cadmium	1.0 mg/l
Chromium	5.0 mg/l
Lead	5.0 mg/l
Mercury	0.2 mg/l
Selenium	1.0 mg/l
Silver	5.0 mg/l

The extraction procedure itself is intended to simulate landfill leaching under natural conditions. The analytical method for determining the concentrations of these metals-extraction procedure toxicity testing - is prescribed in the regulations. Other characteristics such as ignitability, corrosivity and reactivity do not apply to the solid material on site.

3.2 ANALYTICAL RESULTS

Final laboratory results for all samples analyzed can be found in Attachment 3. A summary of positive analytical results

can be found in Tables 1 through 4.

3.2.1 CONTAINERIZED SOLID WASTE ANALYSES

Due to the large quantities of containerized solid waste material on site, a major portion of the analytical effort was directed towards the characterization of these materials.

Forty-six samples were analyzed for the eight R.C.R.A. metals: arsenic, barium, cadmium, chromium, lead, mercury, selenium, and silver. Although concentration for these metals varied; barium, lead and chromium were consistently higher than the other metals tested.

Due to the high E.P. Toxicity threshold set for barium, it was dropped from further consideration. An additional 30 samples were analyzed for lead and chromium to provide a 50% testing of all waste sampled. Eight of the samples demonstrating metal concentrations ranging from low to high were analyzed for E.P. toxicity. None of the containerized wastes sampled exceeded the E.P. toxic threshold concentrations set by R.C.R.A.

3.2.2 PILE WASTE ANALYSES

Waste piles from areas B and C were tested for prominent R.C.R.A. metals as previously described for the containerized waste. The lead concentrations in these samples were elevated, while chromium concentrations were lower. The E.P. toxicity analyses supported previous findings by meeting threshold concentrations for E.P. toxicity. However, one sample, C-7, had

an elevated E.P. Toxicity concentration for lead of 2.8 mg/l. Although this value is 56% of the threshold concentration for lead, it would support further E.P.toxicity testing on a lot by lot basis during actual site clean-up.

3.2.3 P.C.B. ANALYSES

The areas around three transformers were checked for P.C.B. contamination. The two transformers located in Area A (Sample 53a and Sample 58) showed no signs of contamination. The transformer stored in Area C (Sample C-21) displayed slight oil leakage to the soil, resulting in a positive P.C.B. of 21.9 ppm. From oils, one water sample and one oil sample were also checked for P.C.B. Sample A-64, the oil recovery sump along the west side of Area A, tested clean for P.C.B., while Sample D-99, collected from approximately 30 open-head, 30 gallon drums, contained P.C.B. at a concentration of 530 ppm.

3.2.4 VOLATILE ORGANIC ANALYSES

The majority of the 26 volatile organic samples analyzed tested clean (<10 ppb). The exceptions were Sample A-55, a small in-ground sump at the northwest corner of the East Building, which had low levels of chlorinated compounds. Sample A-56, water collected in an underground pit, also had low levels of chlorinated compounds. Sample C-12, collected from soils receiving drainage from a drum storage area, showed traces of tetrachloroethane. Overall, the surface soil and water samples collected across the site indicated very little contamination by

volatile organics.

3.2.5 PRIORITY POLLUTANT ANALYSES

The four samples collected for priority pollutant organics tested clean. Three of the four samples tested positive for BIS (2-Ethylhexyl) Phthalate, a common plasticizer often found in environmental samples and usually attributed to cross contamination from sampling equipment or laboratory preparation of samples.

The priority pollutant analysis confirmed the presence of metals previously identified in the processed solid waste. In addition to the R.C.R.A. metals, the priority analyses indicated high levels of copper, nickel and zinc. Although these metals are not used to characterize waste as hazardous they may be important, in determining the final criteria for site decontamination. All cyanide tested clean (<0.25 mg/kg). Total Phenol results were all positive, but in all cases below 0.1 mg/kg.

3.2.6 RADIOCHEMICAL ANALYSES

Three random grab samples were collected to estimate the radioactive potential of the waste material. All samples were analyzed for gross alpha, with results of 64, 114, and 251 Ci/g. The analytical procedure for gross alpha is qualitative and was used in determining health and safety protocol.

3.2.7 OUTFALL ANALYSES

Two sediment samples were collected below the outfalls and analyzed for semivolatiles, nickel, chromium and lead. The analysis of samples collected from the east and west outfalls showed high lead concentrations of 58 ppm and 56 ppm, respectively.

PPb
according to
lab sheet
A. A. Hecht
1-26-89

4.0 COST ESTIMATES

ESTIMATES FOR SOLIDS, LIQUIDS AND ADDITIONAL REMEDIAL

4.1 SOLIDS

Estimated cost for staging, transporting and disposal of solid material identified on site.

Area "A"	1,413 tons	(drums,crates and piles)
Area "B"	487 tons	(piles)
Area "B"	9,000 tons	(filled-in area)
Area "C"	493 tons	(drums and crates)
Area "C"	3,000 tons	(filled-in area)
Area "D"	2,382 tons	(drums,crates and piles)

Grand Total	16,775 tons
-------------	-------------

SCENARIO - A

Based on preliminary laboratory E.P. Toxicity results, it would appear that the solid waste material can be disposed at an appropriate industrial landfill as non-hazardous waste. However, final characterization of all waste before disposal will need to be performed on a lot by lot basis, as non-hazardous material cost can range from \$115/ton to \$200/ton.

Estimated Cost \$1,929,125 to \$3,355,000

SCENARIO - B

Based on final solid waste characterization, 30% of solid waste is found to be hazardous while 70% is non-hazardous. Under this scenario hazardous waste would need to be disposed at a cost that can range from \$225/ton to \$260/ton.

Estimated Cost \$2,482,700 to \$3,656,950

SCENARIO - C

Filled areas are not removed based on approval of local and state agencies, and all remaining solid waste is non-hazardous.

Estimated Cost \$664,125 to \$1,155,000

4.2 LIQUIDS

Estimated cost for staging, transporting and disposal of liquid materials in tanks (Table 5).

The cost estimate is based on inventory of tanks prepared by American Environment Technologies. The basic assumption is that the liquids in the tank are acid or caustic solution with a concentration of 10% by weight and a metal concentration of 5 g/l. Cost does not include disposal of anhydrous ammonia in tank 1302.

Total cost based on transportation/disposal of
311,130 gallons of concentrate liquid material \$218,950
Includes transportation/disposal of approximately
40,000 gallons of rinse water.

4.3 ADDITIONAL REMEDIATION COSTS

In discovering additional remediation needs throughout the project, the following addresses the estimated costs associated with each remedial task. Due to the nature of each task, and the incomplete information available in some cases, we have made assumptions as a basis for the estimates. These assumptions may or may not be correct. Variations from these assumptions will affect the estimates.

4.3.1 LAB PACKS

The laboratory area at the Li Tungsten site has been divided into five areas and three sub-areas which contain laboratory chemicals and bulk chemicals (55 gallon drums). The estimated cost is based on labor, material and laboratory testing required to prepare material for shipment, and/or storage in a safe area. The estimated cost does not include the chemical storage area in the Dice building and does not include the removal of gas bottles

located in the laboratory. Two alternatives are presented for RTP's consideration:

- | | | |
|----|--------------------------|-----------------|
| a) | Ship Ready Lab Packs | |
| | Labor and materials | <u>\$49,185</u> |
| b) | Lab Packs Not Ship Ready | |
| | Labor and materials | <u>\$32,000</u> |

4.3.2 OVERPACKS

Existing 55-gallon drums containing liquid product and/or waste will be overpacked. Cost estimate includes labor, materials and laboratory testing, but not disposal cost, and is based on a minimum of fifty overpacks. Additional overpacks will be charged at \$145/drum. (The expected total quantity is 100.)

Cost Estimate \$8,137.50

4.3.3 REMOVAL OF CONTAMINATED WATER

The Dice building and the East building both contain flooded floor areas. Based on the size of the flooded areas and the depth of the water, it was estimated that approximately 19,000 gallons of contaminated water will need to be collected by vacuum truck. Cost estimates include vacuum truck, extension hoses, demurrage, laboratory testing and disposal cost. Disposal of water in excess of the 19,000 gallons will be charged at \$0.33/gal.

Cost Estimate \$10,175.00

4.3.4 CAPPING OF LAGOONS

Two alternatives are presented for RTP's consideration.

(a) Alternative #1

Cover two small mud ponds and one large lined lagoon with liner (20 mil pvc Ultratech-uv stabilized liner). The life expectancy of this liner is one to two years. Areas demonstrating vegetation would be treated with approved herbicide and prepared for liner installation. If needed, 1/4" plywood could be used to insure that the vegetation does not break through liner. Cost estimates are based on material and labor.

With Plywood	<u>\$60,783</u>
Without Plywood	<u>\$51,783</u>

(b) Alternative #2

This alternative is preferred since it will initiate remediation of the area. The alternative would require moving the soil from the two small sand ponds to the large pond. Soil removal would be terminated based on laboratory results indicating that the soil is no longer contaminated with heavy metals. Once all material is transferred to the large lagoon, it would be covered with the liner. The soil cover is expected to limit any extensive growth of vegetation, which could perforate the liner. Cost estimate includes labor, earth moving equipment and materials.

<u>Cost Estimate</u>	<u>\$46,777.00</u>
----------------------	--------------------

4.3.5 GAS CYLINDER DISPOSAL

In quoting the removal of 22 gas cylinders, the following assumptions were made. The type of gas is either sulfur dioxide, chlorine, anhydrous ammonia, or hydrogen sulfide. The size of the units are 12 standard units, 10 1/2 standard size. The cylinders are not leaking at the time of packaging and are not severely corroded. Price includes labor, transportation, and disposal for 22 cylinders as described:

<u>Cost Estimate</u>	<u>\$18,654.00</u>
----------------------	--------------------

4.3.6 EMERGENCY TANK LIQUID REMOVAL

Another contractor determined that 129,550 gallons of concentrate, and 25,000 gallons of rinse water need to be disposed of immediately. The quotation does not include any removal, transportation or disposal of anhydrous ammonia. The basic assumption is that liquids present are acidic or caustic solutions with a concentration of 10% by weight with a metal concentration of 5 g/l. This does not apply to the following tanks: underground Tank A, underground Tank B, Tank 35, and Tank 36. All oils must be tested for P.C.B. P.C.B. concentrations cannot be higher than 25 ppm.

Task Cost

Transportation/Disposal

129,550 gallons of concentrate	<u>\$84,490.00</u>
--------------------------------	--------------------

25,000 gallons of rinse water	
-------------------------------	--

Costs have been developed individually. Implementation of all remedial actions may reduce some of the labor cost. Cost estimates are good for forty-five days commencing April 21, 1988. Payments will be due net 15 days and one-third of total cost will be required upon job start-up date.

ANALYTICAL RESULTS

FOR

RADIOCHEMISTRY



Enviropact Northeast, Inc.
540 Palmer Road, 2nd Floor
Yonkers, N.Y. 10701

Attn: John Tostanoski

April 1, 1988
Report T-6187
LAB ID #64271
E84060

Page 1 of 1

Samples Received: 3/23/88
Sample Designation: Analysis as Noted
Collected By: Your Rep.

REPORT OF ANALYSIS	LI-RAD 1	LI-RAD 2	LI-RAD 3	UNITS
Gross Alpha	64	114	251	nci/g

Analyses made in accordance with E.P.A., A.S.T.M., Standard Methods or other approved methods.

Respectfully submitted,

Michael T. Osinski
Michael T. Osinski
Laboratory Manager

TABLES

Footnotes for Tables 1-4:

1. Letters in parenthesis under the ANALYTICAL RESULTS column indicate the approximate concentrations at which the substance was found:
 - (a) less than 100 ppm
 - (b) greater than 100 ppm and less than 499 ppm
 - (c) greater than 499 ppm and less than 1000 ppm
 - (d) greater than 1000 ppm
2. Volume estimates are based upon surveyed dimensions or rough volume approximations.

103942

TABLE 2

AREA "D"

TOTAL QUANTITY OF SOLID MATERIAL AND ANALYTICAL RESULTS

<u>AREAS</u>	<u>ESTIMATED CUBIC YARDS</u>	<u>ESTIMATED TONS</u>	<u>ANALYTICAL RESULTS</u>
D-1	3.72	5.6	Ba(c),Cr(b),Pb(b)Cd(a)
D-2,3&4	2.16	3.2	
D-5	9.97	14.9	Ba(d),Cd(a),Cr(b),Pb(b)
D-6	28.05	42.1	
D-7	12.94	19.4	Cr(a),Pb(d),Ba(a)
D-8	16.85	25.3	Ba(c)Cr(b),Pb(b),Cd(a)
D-9	3.23	4.8	
D-10	5.23	7.8	Ba(b),Cd(a),Cr(d),Pb(b)
D-11	2.7	4.0	
D-12*	17.64	26.5	Pb(b),Ag(c)
D-13	19.11	28.7	
D-14(3)*	24.97	37.5	Ba(b),Cd(a),Cr(d),Pb(d)
D-15	10.46	15.7	Ba(a),Cd(a),Cr(b),Pb(b)
D-16	13.20	19.8	
D-17	4.52	6.8	
D-18	6.68	10.0	
D-19	2.65	4.0	pH 5.0 Cd(a)
D-20	5.39	8.1	
D-21	8.89	13.3	
D-22	14.55	21.8	Ag(b),Ba(a),Cr(a),Cd(a),Pb(b)
D-23	3.97	5.9	
D-24	9.16	13.7	Cr(a),Pb(b),Ag(a)
D-25	0.54	0.8	
D-26	5.78	8.7	
D-27	1.03	1.5	
D-28	5.66	8.5	
D-29	6.02	9.0	
D-30	5.78	8.7	
D-31	10.65	16.0	Cr(b),Pb(b)
D-32	7.37	11.0	
D-33			
D-34,35	0.34	0.5	Ba(a),Cd(a),Cr(b),Pb(b)
D-36	7.47	11.2	
D-37	16.03	24.0	Cr(b),Pb(b)
D-38	0.59	0.9	
D-39	16.27	24.4	
D-40	30.11	45.2	

(3) Pile measuring approximately 15' x 15' x 3'

TABLE 2 (continued)

AREA "D" (CONTINUED)

<u>AREAS</u>	<u>ESTIMATED CUBIC YARDS</u>	<u>ESTIMATED TONS</u>	<u>ANALYTICAL RESULTS</u>
D-41	23.96	35.9	
D-42	48.02	72.03	Ba(b), Cd(a), Cr(b), Pb(c)
D-43	22.75	34.13	Pb(a)
D-44	35.18	52.8	Cr(a), Pb(b)
D-45	19.67	29.5	
D-46	23.22	34.8	
D-47	4.8	7.2	
D-48	To be removed by Li Tungsten per Bob		
D-49	" " "	" "	" "
D-50	8.42	12.6	
D-51*	7.1	10.7	Ba(b), Cd(a), Cr(b), Pb(d)
D-52	30.75	45.5	Ba(b), Cd(a), Cr(b), Pb(a)
D-53	23.72	35.6	As(a)
D-54	7.64	11.5	
D-55	29.52	44.3	Ba(a), Pb(a)
D-56	16.81	25.2	Ba(a)
D-57	6.19	9.3	
D-58	5.82	8.7	
D-59	13.06	19.6	Cr(a), Pb(a)
D-60	11.76	17.6	
D-61	23.44	35.2	
D-62	14.11	21.2	pH 6.7 Pb(a)
D-63	35.28	52.9	Cr(b),
D-64	16.22	24.3	Cr(a), Pb(a)
D-65	28.98	43.5	
D-66	Will be removed		Cr(a)
D-67	7.69	11.5	
D-68	21.13	31.7	
D-69	8.0	12.0	
D-70	2.32	3.5	Cr(a)
D-71	46.53	69.8	Ba(a)
D-72	Carbon Black will be removed		
D-73	20.0	30.0	
D-74	5.12	7.7	
D-75	2.94	4.4	
D-76	14.55	21.8	
D-77	6.19	9.3	
D-78	17.19	25.8	Cr(a), Pb(b)
D-79*	14.38	21.6	Cd(b), Pb(b)
D-80	24.5	36.7	Cr(a), Pb(a)

TABLE 2 (continued)

AREA "D" (CONTINUED)

<u>AREAS</u>	<u>ESTIMATED CUBIC YARDS</u>	<u>ESTIMATED TONS</u>	<u>ANALYTICAL RESULTS</u>
D-81	71.21	106.8	
D-82	16.71	25.1	
D-83	Carbon Black will be removed		Ag(a)
D-84	30.62	45.9	Cr(a), Pb(b)
D-85	Misc. boxes with equipment will be removed		
D-86	40.0	60.0	
D-87	18.73	28.1	
D-88	18.32	27.5	Ag(a), Ba(b), Cd(a), Cr(d), Pb(b)
D-89	9.7	14.5	Pb(a)
D-90	36.16	54.2	Cr(a), Pb(a)
D-91	28.73	43.1	Cd(b), Pb(b), Cr(a)
D-92	21.17	31.7	Cr(a), Pb(a)
D-93 (Rep.)	35.28	52.9	Cr(a), Pb(a)
D-94	33.98	50.9	Cr(a), Pb(a)
D-95	5.12	7.7	Cr(a)
D-96	28.31	42.5	
D-97	6.74	10.1	
D-98	11.23	16.8	
D-99	Drums contain oils. Need to be repacked and disposed		
D-100	8.2	12.3	Pb(a)
D-101	3.53	5.3	Cd(a)
D-102	Sodium sulfide will be removed by owner		
D-103	15.09	22.6	
D-104	25.87	38.8	Cr(a), Pb(c)
D-105	29.05	43.6	Cr(a), Pb(d)
D-106	18.05	27.1	Pb(a)
D-107	12.45	18.7	
D-108	3.69	5.5	
D-109	22.0	33.0	Cr(a), Pb(d)
D-110	10.55	15.8	Pb(a),
D-111	21.82	32.7	Cr(a)
D-112	14.82	22.2	Ag(b), Ba(c), Cd(a), Cr(b), Pb(d)
D-113	3.23	4.85	Pb(c), Cr(a)

TABLE 3

AREA "B"

TOTAL QUANTITY OF SOLID MATERIALS AND ANALYTICAL RESULTS

<u>AREAS</u>	<u>CUBIC YARDS</u>	<u>TONS</u>	<u>ANALYTICAL RESULTS</u>
Landfill	6000.00	9000.0	
B-1			Cr(a), Pb(c)
B-2			Cr(a), Pb(a)
B-3	165.0		Pb(a), Pr(a)
B-4			Pb(c), Cr(a)
B-5			Pb(a), Cr(b)
B-6	80.0		Pb(b), Cr(a)
B-7	80.0		Pb(c), Cr(a)
B-9			Pb(a), Cr(a)
B-10			Cr(a), Pb(b)

TABLE 4

AREA "C"

TOTAL QUANTITY OF SOLID MATERIAL AND ANALYTICAL RESULTS

<u>AREAS</u>	<u>ESTIMATED CUBIC YARDS</u>	<u>ESTIMATED TONS</u>	<u>ANALYTICAL RESULTS</u>
C-15	39.85	59.8	Cr(a),Pb(b)
C-16	238.50	357.8	Cr(a),Pb(a)
C-20	50.69	76.0	Pb(a),Cr(a)
Land Fill			
Area	2000.00	3000.0	
C-2			Cr(a),Pb(b)
C-3			CR(a),Pb(b)
C-4			Cr(a),Pb(a)
C-6			Pb(c)
C-7			Pb(a),Cr(a)
C-8			P(b),Cr(a)
C-9			Pb(b),Cr(a)
C-11			Pb(a),Cr(a)
C-12			Pb(a),Cr(a)
C-13			Pb(a),Cr(a)
C-14			Pb(c),Cr(a)
C-15			Cr(a),Pb(b)
C-16			Pb(a),Cr(a)
C-17		Ag<.5	Pb(b),Cr(a)
C-18			Pr(a),Pb(a)
C-19			Pb(d),Cr(a)
C-20			Cr(a),Pb(a)
C-22		(CN <1)	Pb(d),Cr(a)

TABLE 5

TANK QUANTITIES AND CONTENTS

<u>CONTENTS</u>	<u>TANK #'S</u>	<u>GALLONS</u>
NH4WO4	L9-E	unknown
APT Mother Liquid	L-6, L-5	15,000
ACR Leachate Sol.	L-13A, L-13B, 246	27,000
Water	L550, L550-A, 1332, 244	19,500
Spent Hcl. Acid	233, 231, 232, 1213-1. 1213-2, 1334	48,250 min
Aqua NH3	235, 1302	3,700 est
Water & Sheelite	1333	5,500 est
FM Residue	245	15,000
NH3 Solution	1306, 1307, 1308	unknown
ACR Residue	1336	4,500
PD Residue	248	2,500
PD Leachate Sol.	249	23,000
NaOh Solution	242, 35	3,100 est
Stathetic Sheelite	262, 263, 264, 265, 266	280 min
Tungsten Acid	285	unknown
PD Solution & Residue	287, 56, 58	13,000
CaCl2	36	2,000
Cobalt Chloride	M-4	1,800
Sodium Tungstate	M-11, K-1, K-2, K-3, K-4, K-6	46,000
NF Residue	K-5, K-7	6,500
Cobalt Sulfate	C-3, C-4, C-5, C-7, C-10, C-11, C-12, C-13	25,200
Water & Lime Mixer	237	8,500

TANK QUANTITIES AND CONTENTS continued

Miscellaneous Items

Unknown Solid	L611, L-568	3,000
Sol. & precipitation from neutraliz.	1328	dirt..8,000
Unknown	1340	2,200
Residue & Leach.	M-1	500
Unknown	M-2	1,100
Unknown	M-5	1,800
Unknown	K-9	7,000
Unknown	W-2	600
Unknown	W-3	12,000
Unknown	832	2,000
Unknown	C-6	700
Unknown	C-14	3,000

Current Quantities Unknown in the Following

1330 (Lime Silo), L-8, L-9A, L-9B, L-9C, L-11, L-9R2, 32, 33, W-1, W-4, 1*, 2*, 3*, 4*, 5*, 6*, 16*, 18*, 20, 21, 24, 25, 26, 78*, C, D, the Water Reservoir and the Oil Change Pit.

Tanks with Unknown Capacities, Contents & Current Capacities.

9, 17*, 19*, 41, 56, 57, 58, 59, 59A, 79*, 80*, 83, 84, 85, 86, 89A, 120, 121, 255, 268, 269, 270, 274, 286, 1342, 1343, 616, 620, 667*, 1303, 1337, 1338, 1339, P-1, A, B, L-101* & K-8.

* = Unable to open.


TABLE 6

QUANTITIES & LOCATIONS OF DRUMS CONTAINING LIQUIDS

<u>AREA</u>	<u>QUANTITY</u>
A-50	4 DRUMS
A-56	7 DRUMS
A-57	6 DRUMS
A-8	35 DRUMS
A-10	8 DRUMS
A-14	2 DRUMS
A-24	2 DRUMS

INSIDE THE DICE BUILDING

<u>AREA</u>	<u>QUANTITY</u>
111	4 DRUMS
91	3 DRUMS
40	6 DRUMS
47	2 DRUMS
84	1 DRUM
60	3 DRUMS
55	1 DRUM
54	6 DRUMS
Between 32 & 33	11 DRUMS
99	30 30 GAL. DRUMS



TITLE: SITE MAP

SCALE: N/A

DATE: 4/25/88


REVISED: -

DRAWN BY: RTP

PROJECT #4190-01

DRAWING # 1

103951



0 100 200 300
SCALE IN FEET



TITLE: AREA A & D

SCALE: N/A

DATE: 4/25/88


REVISED: -

DRAWN BY: RTP

PROJECT 4190-01

DRAWING 12

103952



TITLE: AREA B

SCALE: N/A

DATE: 4/25/88

REVISED: -

DRAWN BY: RTP


PROJECT 4190-01

DRAWING # 3

103953

REFERENCE NO. 9

103954




- LEGEND**
- V. - VILLAGE
W.D. - WATER DISTRICT
W.S.D. - WATER SUPPLY DISTRICT
- AREA IDENTIFICATION**
1. SPLIT ROCK ASSOCIATION
 2. DEL VRA ASSOCIATION
 3. DEFOREST ASSOCIATION
 4. MAMMASSET - LAKEVILLE W.D.
 5. PLANDOME V.
 6. GREAT NECK W.D.
 7. GLENWOOD W.D.
 8. GARDEN CITY SOUTH W.D.
 9. NORTHEAST FARMINGDALE W.S.D.
 10. MILL NECK ESTATES
 11. MILLISTON PARK V.
 12. EAST WILLISTON V.
 13. HEMPSTEAD LAKE STATE PARK - SERVED BY LONG ISLAND W. AND ROCKVILLE CENTRE V.
 14. OYSTER BAY W.D.
 15. PLANTING FIELDS ASSOCIATION - SERVED BY PRIVATE WELLS
 16. VALLEY STREAM STATE PARK - SERVED BY LONG ISLAND W. AND JAMAICA WATER SUPPLY CO.
- NOTE: BETHPAGE STATE PARK - SERVED BY BETHPAGE W.D. AND PLAINFIELD W.D.

NOTE:
INFORMATION SHOWN ON THIS MAP HAS BEEN
OBTAINED FROM THE OFFICE OF THE NASSAU
COUNTY DEPARTMENTS OF ASSESSMENT AND HEALTH

0.5" = 6400 FT.

WATER SUPPLY AND WATER DISTRICTS



DATE - OCT 1964
PLATE 8

Table 5

WATER DISTRICTS AND WATER SUPPLY

THE FOLLOWING AREA AND POPULATION INFORMATION FOR WATER SERVICES IN NASSAU COUNTY IS UTILIZED IN CONJUNCTION WITH PLATE 5


		Population		
	Type of Service	1980 U.S. Census	NCPC Estimate	Area (Acres)
TOWN OF HEMPSTEAD				
Bethpage***	W.D.		3,100	296
Bowling Green Estates	W.D.		9,700	887
East Meadow	W.D.		42,150	3,580
Franklin Square	W.D.		16,800	1,039
Freeport	V.	38,272		3,508
Garden City	V.	22,927		3,413
Garden City South	W.D.		1,050	87
Hempstead	V.	40,404		2,327
Hicksville***	W.D.		5,400	497
Jamaica Water Supply*	PVT.		73,650	5,166
Levittown	W.D.		41,950	3,112
Lido-Point Lookout	W.D.		4,500	1,476
Long Beach	CITY	34,073		1,590
Long Island Water Corp.	PVT.		238,950	27,054
New York Water Service Corp.	PVT.		126,650	12,496
Mineola*	V.	52		11
Rockville Centre	V.	25,405		2,196
Roosevelt Field	W.D.		100	858
Uniondale	W.D.		23,100	2,005
West Hempstead-Hempstead Gardens	W.D.		23,000	1,556
Mitchel Field Water Supply Area	(PROPOSED)		1,250	1,970
TOWN OF NORTH HEMPSTEAD				
Albertson Square	W.D.		11,650	1,453
Carle Place	W.D.		9,300	987
Citizens Water Supply Co.	PVT.		22,500	3,922
East Williston	V.	2,708		369
Garden City	V.	0		1
Garden City Park	W.D.		19,900	2,022
Glenwood	W.D.		350	282
Great Neck	W.D.		2,450	272
Jamaica Water Supply*	PVT.		18,150	1,140
Manhasset-Lakeville	W.D.		32,600	6,099
Mineola*	V.	20,705		1,186
Old Westbury***	V.	2,175		3,328
Plandome	V.	1,503		315
Port Washington	W.D.		27,150	4,220
Roslyn	W.D.		16,700	3,463
Sands Point	V.	2,742		2,743
Westbury	W.D.		19,750	2,151
Williston Park	V.	8,216		390
TOWN OF OYSTER BAY				
Bayville	V.	7,034		924
Bethpage**	W.D.		24,850	3,537
Farmingdale	V.	7,946		696
Glen Cove	CITY	24,618		4,336
Glenwood-Glenhead	W.D.		6,650	1,878
Hicksville**	W.D.		42,600	4,470
Jericho	W.D.		55,300	24,034
Locust Valley	W.D.		7,050	5,443
Massapequa	W.D.		44,950	4,028
New York Water Service Corp.*	PVT.		17,600	2,229
Northeast Farmingdale	W.S.D.		400	59
Old Westbury*	V.	1,102		1,819
Oyster Bay	W.D.		6,300	2,358
Plainview	W.D.		32,700	5,190
Sea Cliff	V.	5,364		752
South Farmingdale	W.D.		43,300	3,817
DeForest Drive	P.W.A.		30	12
Mill Neck Estates	P.W.A.		250	60
SEL VRA	P.W.A.		80	60
Split Rock	P.W.A.		70	20

* Part in Town of North Hempstead
 ** Part in Town of Hempstead;
 *** Part in Town of Oyster Bay
 W.D. - Water District

W.S.D. - Water Supply District
 V. - Village
 PVT. - Private Company
 P.W.A. - Private Water Association

Area Sources: Long Island Regional Planning Board, Existing Land Use, 1968;
 Nassau County Planning Commission planimeter estimates

Population Sources: 1980 U.S. Census and Nassau County Planning Commission estimates based on 1980 U. S. Census



New York State Atlas of Community Water System Sources 1982

**NEW YORK STATE DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION**

FOREWARD

SOURCE LOCATIONS

The county maps in this atlas show the locations of surface water intakes and groundwater sources for community water systems in New York State. A community water system is defined in Part 5 of the New York State Sanitary Code as a public water system which serves at least five service connections used by year round residents or regularly serves at least 25 year round residents. Many different types of water systems are therefore included. Community water systems which purchase 100 percent of their water and have no sources of their own are not shown.

Each county map is accompanied by a list of the county's community water systems, population served, and source names. Systems are separated into MUNICIPAL COMMUNITY (program code 100) and NON-MUNICIPAL COMMUNITY (all other program codes) and listed alphabetically within each. MUNICIPAL COMMUNITY water systems are operated by a city, town, village, county or water authority or the water system may be a water district or privately owned. NON-MUNICIPAL COMMUNITY systems are primarily mobile home parks but also include apartments/condominiums, resident health care facilities, resident institutions, and federal facilities.

EXPLANATION OF SYMBOLS

Surface water intakes are designated on the county maps by a triangle (▲) accompanied by the corresponding water supply number.

Groundwater sources are designated by a dot (•) followed by the supply number. Multiple wells separated by less than 1000' and supplying the same water system are shown with one dot. Springs and infiltration galleries are shown as groundwater sources unless the local health unit has designated it a surface source. Therefore, springs and infiltration galleries are listed as wells (springs) or wells (infiltration galleries).

If a Community Water System has source(s) located outside the county, these sources are shown in the county list and show in parentheses the system number, county and page number. Conversely, when a county contains source(s) which supply community water systems located outside the county, the name of the system is also shown in that county's list of sources.

ACKNOWLEDGEMENT

Data compiled in this Atlas is based on location of community water system sources from visits, in 1979, to every county health unit in the State by technicians working for the Bureau of Public Water Supply Protection. This data was updated in 1982 through use of the Department of Health's SAFWATER computer inventory and through limited field review. The Bureau of Public Water Supply Protection wishes to acknowledge the following organizations who have made the Atlas possible:

To the United States Environmental Protection Agency for funding this Atlas as a part of the Underground Injection Control Program.

To the Cartography Section of the New York State Department of Transportation for providing the talent, time and effort in performing the necessary cartographic work to produce this Atlas.

To the engineers and technicians of the Bureau of Public Water Supply Protection of the New York State Department of Health for the painstaking work of gathering the basic data and cross-checking it, and for leading this project through to completion.

New York State Atlas of Community Water System Sources 1982

NEW YORK STATE
DEPARTMENT OF HEALTH




TABLE OF CONTENTS

FORWARD		PAGE 1					
COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE	COUNTY	PAGE
ALBANY	56	FRANKLIN	42	ONEIDA	32	SCHOHARIE	60
ALLEGANY	14	FULTON	58	ONONDAGA	28	SCHUYLER	18
BRONX	76	GENESEE	8	ONTARIO	12	SENECA	24
BROOME	20	GREENE	64	ORANGE	72	STEUBEN	16
CATTARAUGUS	4	HAMILTON	48	ORLEANS	8	SUFFOLK	78
CAYUGA	24	HERKIMER	34	OSWEGO	30	SULLIVAN	70
CHAUTAUQUA	2	JEFFERSON	38	OTSEGO	60	TIOGA	20
CHEMUNG	16	KINGS	76	PUTNAM	66	TOMPKINS	18
CHENANGO	22	LEWIS	36	QUEENS	76	ULSTER	68
CLINTON	44	LIVINGSTON	10	RENSSELAER	56	WARREN	50
COLUMBIA	64	MADISON	28	RICHMOND	76	WASHINGTON	52
CORTLAND	22	MONROE	8	ROCKLAND	74	WAYNE	26
DELAWARE	62	MONTGOMERY	58	ST. LAWRENCE	40	WESTCHESTER	74
DUTCHESS	66	NASSAU	76	SARATOGA	54	WYOMING	
ERIE	6	NEW YORK	76	SCHENECTADY	56	YATES	
ESSEX	46	NIAGARA	6				

LEGEND

BOUNDARIES AND PLACES

International	-----
State	-----
County	-----
Town	-----
Indian Reservation	-----
City	-----
Unincorporated Place	-----
Built-up Area (Over 25,000 population including any contiguous city or village)	-----
Village	-----
Federal Reservation	-----

CLASSIFICATION OF POPULATED PLACES


100,000 or more	YONKERS
50,000 to 100,000	Levittown
12,500 to 50,000	Poughkeepsie
2,500 to 12,500	Hampton Bays
250 to 2,500	Boiceville
250 or less	Corbin

TRANSPORTATION

Highways	
Divided Highways	
Full Control of Access	
Partial or No Control of Access	
Undivided Highway	
Interchange	
Touring Route (State, U.S., Interstate) or State Parkway	
Touring Route Markers	
State, U.S., Interstate	
Railroads	
Operating Line	
Operator	
Owner (If Other than Operator)	
Company Having Trackage Rights	
Airports (Open to the Public, Military)	
Runway under 4000'	
Runway over 4000'	
Rest Areas	
Food, Gas, Rest Rooms	
Gas, Rest Rooms	
Rest Rooms	
Parking Only	

RECREATION FACILITIES

State or National Recreation Area	
State Campground	
State Boat Launching Site	
State Canal Park	
State Fish Hatchery	
Other State Recreation Site	



NASSAU COUNTY

NEW YORK CITY WATER SUPPLY

9

ID NO COMMUNITY WATER SYSTEM POPULATION SOURCE

Municipal Community

1	Albertson Water District.	13500.	Wells
2	Bayville Village.	7500.	Wells
3	Bethpage Water District.	32000.	Wells
4	Bowling Green Water District.	12000.	Wells
5	Carle Place Water District.	11000.	Wells
6	Citizens Water Supply Company.	30000.	Wells
7	Deforest Drive Association.	25.	Wells
8	East Meadow Water District.	52000.	Wells
9	Farmingdale Village.	7946.	Wells
10	Franklin Square Water District.	20000.	Wells
11	Freeport Village.	38272.	Wells
12	Garden City Park Water District.	22596.	Wells
13	Garden City Village.	22927.	Wells
14	Glen Cove City.	24618.	Wells
15	Hempstead Village.	40404.	Wells
16	Hicksville Water District.	58000.	Wells
17	Jamaica Water Supply Company.	128448.	Wells
18	Jericho Water District.	64000.	Wells
19	Levittown Water District.	50000.	Wells
20	Lido-Point Lookout Water District.	10000.	Wells
21	Locust Valley Water District.	8500.	Wells
22	Long Beach City.	34073.	Wells
23	Long Island Water Corporation.	258936.	Wells
24	Manhasset-Lakeville Water District.	44730.	Wells
25	Massapequa Water District.	52000.	Wells
26	Mill Neck Estates Water Supply.	240.	Wells
27	Mineola Village.	20600.	Wells
28	New York Water Service.	172180.	Wells
29	Old Westbury Village.	3100.	Wells
30	Oyster Bay Water District.	10225.	Wells
31	Plainview Water District.	40000.	Wells
32	Plandome Village.	2616.	Wells
33	Port Washington Water District.	35000.	Wells
34	Rockville Centre Village.	25405.	Wells
35	Roosevelt Field Water District.	1640.	Wells
36	Roslyn Water District.	27500.	Wells
37	Sands Point Village.	3002.	Wells
38	Sea Cliff Water Company.	17850.	Wells
39	Sel-Bra Acres Water Supply.	80.	Wells
40	South Farmingdale Water District.	49900.	Wells
41	Split Rock Water Supply.	25.	Wells
42	Uniondale Water District.	25000.	Wells
43	West Hempstead-Hempstead Garden Water District.	32000.	Wells
44	Westbury Water District.	20050.	Wells
45	Williston Park Village.	8216.	Wells

Non-Municipal Community

46	Community Hospital at Glen Cove.	1350.	Wells
47	Planting Fields Arboretum.	90.	Wells
48	Stuart, Walker, Zimmer Water Supply.	41.	Wells

The majority of New York City residents receive their drinking water from the New York City Aqueduct System. Only a portion of the borough of Queens is supplied by a separate ground-water system, the Jamaica Water Supply.

The New York City Aqueduct System consists of the Croton, Delaware, and Catskill branches. It is supplied by reservoirs and lakes in Westchester, Putnam, Ulster, Schoharie, Delaware, and Sullivan Counties. The reservoirs and lakes supplying the respective aqueduct branches are designated in those counties.

CROTON SYSTEM - The Croton supply is the oldest system which has a safe yield of about 240 MGD*. The Croton System embodies 12 reservoirs and 4 controlled lakes, situated in Westchester and Putnam Counties, which impound about 95 billion gallons of water from 375 square miles of the Croton River drainage area. The principal structures in the present Croton System are the New Croton Dam and the New Croton Aqueduct which supplemented the Old Croton Aqueduct now out of service. Croton water is delivered via the New Croton Aqueduct to the Jerome Park Reservoir in the Bronx and then via aqueduct and conduits to the Central Park Reservoir in Manhattan. The delivery capacity of the Aqueduct from the New Croton Reservoir to the Jerome Park Reservoir is 275 MGD.

CATSKILL SYSTEM - The Catskill supply is the second major system which has a safe yield of about 470 MGD. Its principal structures are the Schoharie, Ashokan, Kensico, and Hill View Reservoirs.

The Ashokan Reservoir impounds 128 billion gallons of available storage, at Elevation 590 in the West Basin and at Elevation 587 in the East Basin, from 257 square miles of drainage area in the Catskill Mountains west of Kingston. The Ashokan Reservoir feeds directly into the Catskill Aqueduct.

The Schoharie Reservoir, placed in service in 1924, impounds 19.6 billion gallons of available storage, at Elevation 1130, from 314 square miles of drainage area.

The Catskill Aqueduct is 92 miles long overall, extending 75 miles from the Ashokan Reservoir to the upstream influent chamber of the Kensico Reservoir, with a 2-mile bypass, then continuing 15 miles from the Kensico Reservoir effluent chamber to the Hill View Distributing Reservoir in Yonkers.

The Kensico Reservoir was originally constructed as an equalizing basin on the Catskill Aqueduct. The reservoir, having a safe yield of 5 MGD from its own drainage area, is formed by the Kensico Dam.

DELAWARE SYSTEM - The Delaware supply is the latest system which has a safe yield of about 580 MGD. The supply from the Delaware watershed, which is stored in the Neversink, Pepacton, and Cannonsville Reservoirs, has a safe yield of about 480 MGD. The Rondout Reservoir, serving as a collecting reservoir for these three reservoirs, has a safe yield of about 100 MGD from its own drainage area of 95 square miles which is part of the Hudson watershed. This reservoir impounds 50 billion gallons of available storage at the flow line, Elevation 840.

The Delaware Aqueduct is a pressure tunnel deep in bed rock for its entire length of 85 miles.

JAMAICA WATER SUPPLY - The Jamaica-Queens Water Company serves the Jamaica section of the borough of Queens. This system utilizes 76 wells located in 46 separate well fields. A map depicting the Jamaica-Queens service area is included on Page 77

* Millions of Gallons per Day

REFERENCE NO. 10

103962

MONTHLY FLUCTUATIONS IN THE QUALITY OF GROUND WATER NEAR THE
WATER TABLE IN NASSAU AND SUFFOLK COUNTIES.
LONG ISLAND, NEW YORK

by Brian G. Katz, Stephen E. Ragone, and Juli B. Lindner

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations 78-41

Prepared in cooperation with the

Nassau County Department of Public Works
Suffolk County Department of Environmental Control
Suffolk County Water Authority

PROPERTY OF U.S. GEOLOGICAL SURVEY
FEDERAL BUILDING, HUDON, SD 57302



Syosset, New York
1978

103963

CONTENTS

	Page
Conversion factors and abbreviations.....	v
Abstract.....	1
Introduction.....	3
Purpose and scope of study.....	3
Previous studies.....	3
Method of study.....	4
Field sampling.....	4
Data treatment.....	4
Hydrogeology.....	9
Monthly fluctuations of selected physical and chemical characteristics of ground water.....	11
Temperature.....	11
Chloride.....	11
Nitrate.....	23
Sulfate.....	29
Summary and conclusions.....	35
Selected references.....	36

ILLUSTRATIONS

Figure 1. Map showing location and major geographic features of Long Island.....	2
2. Map showing location of wells in: (A) sewerd and unsewerd areas of Nassau County.....	6
(B) a rural area of Suffolk County.....	7
3. Schematic representation of aquifers on Long Island.....	9
4. Map showing major physiographic features of upper glacial aquifer on Long Island.....	10
Figures 5-10. Graphs showing:	
5. Monthly fluctuations of water temperature at selected wells where depth to water was less than 3 meters.....	13
6. Monthly air temperatures recorded at Mineola, (Nassau County) and Riverhead (Suffolk County), August 1975 to July 1976.....	14
7. Monthly fluctuations of water temperature at selected wells where depth to water was greater than 3 meters.....	15

ILLUSTRATIONS (Continued)

	Page
8. Monthly fluctuations of chloride concentration in water:	
A. From 14 selected wells that show large fluctuations over period of record.....	17
B. From 16 selected wells that show little or no monthly fluctuation over period of record.....	20
9. Monthly fluctuations of nitrate (as N) concentrations in water:	
A. From 10 selected wells that show large fluctuations over period of record.....	25
B. From 20 selected wells that show little or no monthly fluctuations over period of record.....	27
10. Monthly fluctuations of sulfate concentrations in water:	
A. From 9 selected wells that show large fluctuations over period of record.....	30
B. From 21 selected wells that show little or no monthly fluctuation over period of record.....	32

TABLES

Table 1. Sampling depths at wells monitored during study, August 1975 to July 1976, Nassau and Suffolk Counties.....	5
2. Accuracy and precision of analyses for selected ground-water constituents.....	8
3. Depth to water and concentration of selected constituents of water from selected wells in Nassau and Suffolk Counties, August 1975 to July 1976.....	12
4. Chemical quality of precipitation collected at Mineola, N.Y. and Upton, N.Y., August 1975 to July 1976.....	22

CONVERSION FACTORS AND ABBREVIATIONS

Factors for converting U.S. Customary units to metric units are shown to three or four significant figures. However, in the text the metric equivalents are shown only to the number of significant figures consistent with the values for the English units.

<u>U.S. Customary</u>	<u>Multiply by</u>	<u>Metric</u>
inch (in.)	2.54	centimeters (cm)
foot (ft)	.3048	meter (m)
mile (mi)	1.609	kilometers (km)
gallon (gal)	3.785	liters (L)
gallons per minute (gal/min)	.06309	liters per second (L/s)
million gallons (Mgal)	3.785	million liters (mil L)
million gallons per day (Mgal/d)	.004381	cubic meters per second (m ³ /s)
		meters per day (m/d)
		liters per second per meter [(L/s)/m]
pound (lb)	.4536	kilogram (kg)
acre	.405	square hectometer (hm ²)

MONTHLY FLUCTUATIONS IN THE QUALITY OF WATER NEAR THE
WATER TABLE IN NASSAU AND SUFFOLK COUNTIES,
LONG ISLAND, NEW YORK

By

Brian G. Katz, Stephen E. Ragone,
and Juli B. Lindner

ABSTRACT

Water samples from wells in a sewered and an unsewered suburban area and an unsewered rural area on Long Island, N.Y., were collected and analyzed monthly from August 1975 to July 1976 to determine the concentrations of chloride, sulfate, and nitrate in ground water near the water table. Short-term and seasonal fluctuations in concentrations of these substances were evaluated to determine their relation to non-point discharges.

Major factors that may cause concentrations of these substances to fluctuate at any particular site are precipitation, lawn fertilizer, dissolved salts in storm runoff, and effluent from septic tanks and cesspools. Chloride concentrations during the study fluctuated by as little as 2 milligrams per liter (mg/L) at some sites and as much as 300 mg/L at others. Nitrate and sulfate concentrations showed essentially no change at some sites but fluctuated by as much as 8 and 40 mg/L, respectively, at others. Short-term fluctuations in the concentrations of these substances in ground water seem to have no consistent correlation with type of land use (suburban or agricultural) or precipitation but seem to be related to seasonal variations in input from specific nonpoint sources.




Figure 1.--Location and major geographic features of Long Island, New York.

INTRODUCTION

Ground water is the sole source of freshwater for more than 2.7 million residents of Nassau and Suffolk Counties, Long Island, New York (fig. 1). Under natural conditions, the ground-water reservoir is recharged only by precipitation. Population growth and urbanization on Long Island have caused a steady increase in the demand for fresh ground water and have affected its quality through the discharge of wastes and other contaminating products to the ground-water reservoir. A significant amount of the changes in water quality are attributed to the increased discharge of dissolved chloride, nitrate, and sulfate to the aquifer from nonpoint sources such as wastewater from cesspools and septic tanks, salts for road deicing, and fertilizers for lawns and agriculture. Precipitation and storm-water runoff are the principal agents in moving these substances through the ground to the water table.

In general, the upper glacial aquifer is the water-table aquifer in most of Long Island. As the uppermost aquifer on the island, it is the most susceptible to contamination.

Purpose and Scope of Study

To date, information on short-term fluctuations in quality of shallow ground water in Nassau and Suffolk Counties is incomplete. To obtain data on short-term fluctuations in water quality in these counties and to correlate them with their probable main controlling factors, the U.S. Geological Survey collected water samples monthly from August 1975 to July 1976 from 30 wells screened in the upper glacial aquifer. The data obtained from these samples are described, summarized, and interpreted in the sections that follow. Air and ground-water temperatures during the sampling period are correlated to determine the effect of seasonal changes in the temperature of precipitation entering the aquifer. Chloride, nitrate, and sulfate were selected for analysis in this report because they are the major inorganic ions in ground water and can be indicative of ground-water contamination.

Previous Studies

Short-term fluctuations and seasonal variations in ground-water quality have recently received an increasing amount of attention in the literature. Pluhowski and Kantrowitz (1964) reported on factors affecting monthly ground-water temperatures over a 2-year period. Pettyjohn (1971, 1975, 1976) reported that nitrate and chloride concentrations in ground water increase substantially after periods of precipitation. Walker (1973, 1973a) reported that nitrate in soil moves downward to shallow aquifers during recharge periods in the late fall and early spring. Toler and Pollock (1974) stated that deicing salt that has accumulated in the unsaturated zone is eventually flushed from the soil to the water table by spring recharge. Schmidt (1972, 1977) described short-term variations and seasonal trends of nitrate and chloride

in ground water and discussed factors that possibly control these variations. Piskin (1973) discussed factors that affect seasonal variations of nitrate in ground water.

Method of Study

Ground-water near the water table was monitored at wells along three north-south and two east-west trending lines in a sewerred and an unsewerred area in Nassau County (fig. 2A) and a rural area in Suffolk County (fig. 2B). These wells range in diameter from 3.2 cm to 15 cm, and the screened interval is generally 0.9 m in the small-diameter wells and 3.0 m in the large-diameter wells. The range in depth to water over the period of sampling, and the average depth of the top of the screens below the water table, are presented in table 1.

Field Sampling

At 24 of the shallow wells in this study (where depth to water was less than 8 m from land surface), a rubber hose was inserted down the casing to below water level. Before water samples were taken by centrifugal pump, three times the volume of water in the well casing was removed to insure a representative ground-water sample. Specific conductance and pH were measured at discharge; dissolved oxygen and temperature were measured in the well.

At the six deeper wells (where depth to water was greater than 8 m from land surface), water samples were taken by submersible pump lowered down the casing to between 3 and 6 m below water level. Again, three times the volume of water in the well casing was cleared before the samples were taken. Specific conductance, pH, and temperature were measured at discharge.

Data Treatment

Water-quality data from the 30 wells sampled on a monthly basis were entered in the U.S. Geological Survey's computer in Reston, Va. The data were retrieved as tables, and analyses in which cation anion balances differed by 20 percent or more were deleted. Chloride, nitrate, and sulfate were selected for analysis because they are the major inorganic ions in ground water.

Analytical accuracy and precision for the principal anionic constituents of water--chloride, nitrate, and sulfate (Cl^- , NO_3^- , and SO_4^{2-})--are presented in table 2 (L. C. Friedman, U.S. Geol. Survey, written commun., 1976). These analyses of standard reference samples were made by the U.S. Geological Survey Laboratory in Albany, N.Y. The standard-deviation values (table 2) were used to determine whether fluctuations above analytical noise were observed in the water-quality data.

Table 1.--Sampling depths at wells monitored during study, August 1975 to July 1976, Nassau and Suffolk Counties, New York

[All depths are in meters]

Well number	Depth to water ^{1/}	Average depth to top of screen ^{2/}
SEWERED AREA, NASSAU COUNTY		
N1129	7.1 - 7.6	5.2
N1143	5.9 - 6.4	14.7
N1164	5.5 - 6.3	5.3
N1165	5.1 - 5.9	6.2
N1167	4.1 - 4.7	2.1
N1168	2.6 - 3.1	4.7
N8235	4.3 - 5.0	10.4
N8598	6.7 - 7.4	5.8
UNSEWERED AREA, NASSAU COUNTY		
N1160	7.1 - 9.6	0.15
N1176	34.4 - 35.0	24.2
N1183	4.1 - 4.9	4.7
N1194	24.0 - 24.7	4.6
N1201	4.4 - 5.1	3.0
N1250	3.0 - 4.4	5.6
N1251	2.4 - 3.1	2.1
N1252	1.2 - 2.2	4.7
N1253	3.6 - 5.1	3.7
N1254	2.6 - 3.7	5.0
N7397	23.8 - 24.9	4.9
N8669	2.3 - 3.8	7.0
N8789	3.0 - 4.0	4.7
N8888	22.6 - 26.6	7.8
S29778	34.5 - 35.1	13.4
RURAL AREA, SUFFOLK COUNTY		
S46913	1.2 - 1.5	0.9
S46914	1.8 - 2.3	0.3
S47226	1.0 - 1.5	3.3
S47227	0.9 - 1.6	25.2
S48946	2.1 - 3.1	7.0
S51583	6.1 - 6.9	5.2
S51592	3.4 - 4.0	5.5

^{1/} In meters below land surface.

^{2/} In meters below water table.




Figure 2B.--Location of wells in a rural area of Suffolk County.

103973

The wells were selected, in part, according to location. The three types of areas represented include a suburban sewered area and a suburban unsewered area (fig. 2A) and a rural unsewered area (fig. 2B). Nonpoint sources from natural and (or) urbanizing factors, specifically sewage, fertilizer, road salt, and precipitation, were evaluated as to their effect on water quality in each of the three areas.

The sewered part of Nassau County includes Sewage Disposal Districts 1 and 2, which cover an area of about 207 km² (fig. 2A). The unsewered section of Nassau County contains Sewage Disposal Districts 3 and 4 and covers an area of about 544 km². Domestic wastes in this area are currently (1976) disposed of by shallow septic-tank systems as in the rural area, in eastern Suffolk County, which is unsewered and predominantly agricultural.

Table 2.--Accuracy and precision of analyses for
selected ground-water constituents

Constituent	Mean value of standard reference sample (mg/L)	Standard deviation (mg/L)	Percent standard deviation
Chloride (Cl)	1.84	± 0.34	± 18.5
	8.17	.61	7.5
	74.0	1.8	2.4
	124	5	4
	179	3	1.6
Nitrate (NO ₂ +NO ₃ -N)	0.097	± 0.013	± 13.4
	.49	.04	8.2
	1.19	.03	2.5
	2.94	.08	2.7
	12.5	.6	4.8
Sulfate (SO ₄)	16.3	± 1.2	± 7.4
	22.0	1.8	8.2
	67.8	1.3	1.9
	98.1	1.3	1.3
	105	10	9.5

All analyses performed by U.S. Geological Survey Laboratory in Albany, N.Y.

HYDROGEOLOGY

The hydrogeology of the water-table aquifer is described only generally in this report. More detailed descriptions are given in reports by McClymonds and Franke (1972) and Franke and Cohen (1972). Figure 3 depicts the hydrogeologic system of Long Island and the position of the upper glacial aquifer.

The upper glacial (water-table) aquifer is composed of Pleistocene-age deposits (fig. 3). These consist of (1) till deposits, which are composed of clay, sand, gravel, and boulders and occur in the northern half of the island in moraines; (2) outwash deposits, which consist of quartzose sand and gravel and occur between and south of morainal deposits (fig. 4), and (3) glacio-lacustrine deposits, which consist of silt and clay and are scattered but found mostly in eastern Long Island (McClymonds and Franke, 1972).




Figure 3.--Schematic representation of aquifers on Long Island (vertical scale greatly exaggerated).

The water-bearing properties of these deposits range from poorly permeable (till) to highly permeable (outwash deposits). Specific capacities of wells tapping these deposits range from very low (almost no yield) in the till to more than 41 (L/s)/m in the outwash (McClymonds and Franke, 1972). Hydraulic conductivities range from 41 to 82 m/d (McClymonds and Franke, 1972). In the northern half of Long Island (fig. 4), depth to water may be as much as 36 m in these poorly permeable deposits, but in the southern half (outwash deposits), depth to water can range from less than 1 m to about 9 m.

Recharge to the upper glacial aquifer results mainly from infiltration of precipitation, infiltration of storm runoff, injection of water used for industrial purposes, and discharge of domestic and industrial wastewater from cesspools and septic-tank systems (Franke and Cohen, 1972). Depending upon factors such as lithology and soil moisture, the time required for water to move through the unsaturated zone to the water table ranges from a few hours (Seaburn and Aronson, 1974) to an estimated maximum of 16 months (Isbister, 1966, p. 49). Consequently, short-term variations in water quality due to cyclic variations in input rate, and concentration of typical substances, may be difficult to predict.

In general, north of the regional ground-water divide (fig. 1), ground-water movement is toward Long Island Sound. South of this divide, regional ground-water movement is generally toward the south shore of Long Island (Franke and Cohen, 1972).




Figure 4.--Major physiographic features of upper glacial aquifer on Long Island.

SUMMARY AND CONCLUSIONS

Concentrations of chloride, nitrate and sulfate in shallow ground water were monitored for 1 year in areas receiving these dissolved constituents from nonpoint sources. Samples were collected monthly in sewered and unsewered suburban areas and in a rural unsewered area. During the period of sampling, maximum fluctuations of chloride concentrations in any particular well ranged from 2 to 300 mg/L; nitrate, from 0.2 to 10 mg/L; and sulfate, from 1 to 40 mg/L. Factors giving rise to these fluctuations include variations in (1) quality of precipitation, (2) application rates of fertilizers, (3) concentration of dissolved constituents in storm runoff, and (4) quality of sewage discharged to the ground.

The monthly and seasonal fluctuation of chloride, nitrate, and sulfate concentrations in ground water seems to correlate with temporal variations in discharge from specific nonpoint sources such as fertilizers, sewage, and storm runoff. No consistent correlation was noted between monthly variations of these substances in ground water and seasonal fluctuations in temperature or of the concentration of these substances in precipitation.

When long-term trends in ground-water quality are derived from scant data, it is of utmost importance to observe the magnitude of the short-term variations that may result from nonpoint sources. The magnitude of these short-term fluctuations could be larger than the actual long-term change in concentration, and this would lead to an incorrect assessment of possible trends toward an improvement or degradation in water quality.

SELECTED REFERENCES

- Baier, J. H., and Rykbost, K. A., 1976, The contribution of fertilizer to the ground water of Long Island: *Ground Water*, v. 14, no. 6, p. 439-447.
- Cohen, Philip, Franke, O. L., and Foxworthy, B. L., 1968, An atlas of Long Island's water resources: *New York State Water Resources Commission Bulletin* 62, 117 p.
- DeLuca, F. A., Hoffman, J. C., and Lubke, E. R., 1965, Chloride concentration and temperature of the waters of Nassau County, Long Island, New York: *New York State Water Resources Commission Bulletin* 55, 35 p.
- Franke, O. L., and Cohen, Philip, 1972, Regional rates of ground-water movement on Long Island, New York, in *U.S. Geological Survey Professional Paper* 800-C, p. C271-C277.
- Hoffman, J. F. and Spiegel, S. J., 1958, Chloride concentration and temperature of water from wells in Suffolk County, Long Island, New York, 1928-53: *New York State Water Power and Control Commission Bulletin* GW-38, 55 p.
- Isbister, John, 1966, Geology and hydrology of northeastern Nassau County, Long Island, New York: *U.S. Geological Survey Water-Supply Paper* 1825, 89 p.
- McClymonds, N. E., and Franke, O. L., 1972, Water-transmitting properties of aquifers on Long Island, New York: *U.S. Geological Survey Professional Paper* 627-E, 24 p.
- Nassau-Suffolk Regional Planning Board, 1976, Population estimates and projections, 1975 to 1995; interim report series 1: Hauppauge, N.Y., 58 p.
- Nassau-Suffolk Research Task Group, 1969, The Long Island water pollution study: *New York State Department of Health*, 395 p.
- Pearson, F. J., Jr., and Fisher, D. W., 1971, Chemical composition of atmospheric precipitation in the northeastern United States: *U.S. Geological Survey Water-Supply Paper* 1535-P, 23 p.
- Perlmutter, N. M., and Guerrera, A. A., 1970, Detergents and associated contaminants in ground water at three public-supply well fields in southwestern Suffolk County, Long Island, New York: *U.S. Geological Survey Water-Supply Paper* 2001-B, 22 p.

- Pettyjohn, W. A., 1971, Water pollution by oil field brines and related industrial wastes in Ohio: Ohio Journal of Science, v. 71, no. 5, p. 257-269.
- _____, 1975, Chloride contamination in Alum Creek, central Ohio: Ground Water, v. 13, no. 4, p. 332-339.
- _____, 1976, Monitoring cyclic fluctuations in ground-water quality: Ground Water, v. 14, no. 6, p. 472-480.
- Piskin, Rauf, 1973, Evaluation of nitrate content of ground water in Hall County, Nebraska: Ground Water, v. 11, no. 6., p. 4-13.
- Pluhowski, E. J., and Kantrowitz, I. H., 1964, Hydrology of the Babylon-Islip Area, Suffolk County, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1768, 119 p.
- Schmidt, K. D., 1972, Nitrate in ground water of the Fresno-Cloris metropolitan area, California: Ground water, v. 10, no. 1, p. 50-64.
- _____, 1977, Water-quality variations for pumping wells: Ground Water, v. 15, no. 2, p. 130-137.
- Saffigna, P. G. and Keeney, D. R., 1977, Nitrate and chloride in ground water under irrigated agriculture in central Wisconsin: Ground Water, v. 15, no. 2, p. 170-177.
- Seaburn, G. E. and Aronson, D. A., 1974, Influence of recharge basins on the hydrology of Nassau and Suffolk Counties, Long Island, N.Y: U.S. Geological Survey Water-Supply Paper 2031, 66 p.
- Stevens, H. H., Jr., Ficke, J. F., and Smoot, G. F., 1975, Water temperature, influential factors, field measurement, and data presentation: U.S. Geol. Survey Techniques of Water-Resources Investigations, Book 1, Chap. D1, 65 p.
- Sumi, L., Corkery, A., and Monkman, J. L., 1959, Calcium sulfate content of urban air: Baltimore, Md., American Geophysical Union, Geophysics Monograph 3, p. 69-80.
- Toler, L. G., and Pollock, S. J., 1974, Retention of chloride in the unsaturated zone: U.S. Geological Survey Journal of Research, v. 2, no. 1, p. 119-123.

U.S. Environmental Protection Agency, 1975, National interim primary drinking water regulations: Federal Register, v. 40, no. 248, p. 59566-59574.

U.S. Geological Survey, 1976, Water resources data for New York, Water year 1975: U.S. Geological Survey Water-Data Report NY-75-1, 735 p.

Walker, W. H., 1973, Ground-water nitrate pollution in rural areas: Ground Water, v. 11, no. 5, p. 19-22.

_____, 1973a, Where have all the toxic chemicals gone?: Ground Water, v. 11, no. 2, p. 11-20.

REFERENCE NO. 11

103981

United States
Department of
Agriculture

in cooperation with
Cornell University Agricultural
Experiment Station

Soil Survey of Nassau County New York

Soil
Conservation
Service



In winter the average temperature is 33 degrees F, the average daily minimum temperature is 27 degrees. The lowest temperature on record, which occurred at Mineola on January 27, 1976, is -1 degree. In summer the average temperature is 72 degrees, and the average daily maximum temperature is 81 degrees. The highest recorded temperature, which occurred at Mineola on July 3, 1966, is 103 degrees.

Growing degree days are shown in table 1. They are equivalent to "heat units." During the month, growing degree days accumulate by the amount that the average temperature each day exceeds a base temperature (40 degrees F). The normal monthly accumulation is used to schedule single or successive plantings of a crop between the last freeze in spring and the first freeze in fall.

The total annual precipitation is 42 inches. Of this, 21 inches, or 50 percent, usually falls in April through September. The growing season for most crops falls within this period. In 2 years out of 10, the rainfall in April through September is less than 16 inches. The heaviest 1-day rainfall during the period of record was 8.2 inches at Mineola on August 12, 1955. Thunderstorms occur on about 22 days each year, and most occur in summer.

The average seasonal snowfall is 27 inches. The greatest snow depth at any one time during the period of record was 29 inches. On the average, 15 days of the year have at least 1 inch of snow on the ground. The number of such days varies greatly from year to year. The average relative humidity in midafternoon is about 55 percent. Humidity is higher at night, and the average at dawn is about 70 percent. The sun shines 65 percent of the time possible in summer and 50 percent in winter. The prevailing wind is from the west-northwest. Average windspeed is highest, 14 miles per hour, in spring.

Physiography and Geology

Bernard S. Ellis, geologist, Soil Conservation Service, assisted with this section.

Nassau County is part of the Coastal Plain physiographic province. The county is characterized by undulating or rolling landscapes in the northern part and a flat plain with a gently southward tilt in the southern part. A lobe of rolling topography protrudes farther to the south along the eastern edge of the county. Extensive tidal areas and marshes are just south of the plain, and a barrier beach and dunes form the southern outline of the county.

Elevation in the county ranges from sea level to about 340 feet above sea level near the eastern edge of the county, just south of NY Route 25. The landforms at the higher elevations were deposited as a terminal moraine. These areas have irregular topography that is crossed by deep glacial drainage channels near the north shore. These channels empty into deep bays on the north shore. The steepest relief is along drainage channels or

on the side slopes adjacent to the bays. An outwash plain, which is to the south of the terminal moraine, has a maximum elevation of about 180 feet just northeast of Hicksville and slopes gradually to the south some 8 to 10 miles, finally reaching tidal areas at sea level.

Nassau County is underlain by bedrock, but most of it is at a depth of several hundred feet. The closest surficial bedrock is to the west in the boroughs of Bronx and Queens in New York City and areas to the northwest in Westchester County, near Long Island Sound. From these areas of surface exposure, the rock surface dips to the southeast to form a solid basement below Nassau County. Most of the bedrock consists of Cretaceous sedimentary layers (3). Some of the older rocks in the area are the 200-million-year-old Triassic red beds and lava flows off New Jersey and Connecticut and the Cambrian metamorphic rocks in the New York City area that are 450 million years old.

During the Late Cretaceous Period the sediments from the eroding Appalachian Highlands were carried by streams and rivers to low-lying coastal areas. The sand, silt, and clay of the Raritan and Magothy formations, which form the foundation of Long Island, were deposited as deltas in areas of shallow water. The Raritan formation is below sea level, and the Magothy formation is at the surface of several sites along the north shore.

During the Tertiary Period the area of Long Island was uplifted above sea level and the Cretaceous sediments were eroded and dissected by streams and rivers. The valley now occupied by Long Island Sound was cut by a major river, and smaller tributary streams formed valleys which are now the north shore bays.

During the Pleistocene Epoch of the Quaternary Period, several major glacial advances into the northern United States occurred. This epoch is divided into four major glacial stages. From oldest to youngest, they are: Nebraskan, Kansan, Illinoian, and Wisconsin. During the Illinoian advance, the ice sheet reached a position just north of the Long Island area. Outwash sand and gravel, of the Jameco gravel formation, was deposited by meltwater streams. Following the Illinoian stage, sea level rose close to its present level and a clay (Gardiners clay) containing marine fossils was deposited in the shallow coastal waters surrounding Long Island.

During the Wisconsin glacial advance, the ice reached a position represented on most of Long Island by the Ronkonkoma terminal moraine. In the latter part of this stage, the ice sheet receded from a point east of Lake Success and established a new position along the north shore marked by the Harbor Hill terminal moraine. West of Lake Success this lobe of ice overrode the Ronkonkoma moraine and pushed as far south as Staten Island. This caused the terminal moraine deposits in Nassau County to form a wide band of irregular topography occupying the northern half of the county, while in adjacent Suffolk County the terminal moraine

Deposits were far enough apart to be two distinct landforms separated by a flat plain. During the Wisconsin advance, sea level dropped about 350 feet below its current elevation to expose a broad, flat coastal plain.

As the climate again warmed about 11,000 years ago, the Wisconsin period ended and the Holocene, or present, period began. The ice sheet receded to its present polar limits, and sea level rose to its present level. Currents and wave action modified the outwash plain to create the present-day shoreline.

Drainage

A few perennial streams drain the county. The longer streams carry runoff water to the estuaries of the south shore. From west to east, they are Valley Stream, Mill River, East Meadow Brook, Bellmore Creek, and Massapequa Creek. A few shorter creeks, such as Hook, Motts, Powell, and Seaford Creeks, also drain toward the south shore.

Most of the drainage to the north shore is intermittent. Glen Cove Creek and Mill Neck Creek are the longest creeks that drain toward the north shore; other shorter, mostly intermittent creeks drain into the bays of the north shore. A sizable portion of the runoff that originates between NY Routes 25 and 25A enters the ground water by collecting in natural closed depressions or landlocked ponds.

Much of the runoff on paved surfaces in recently developed areas is recharged into the ground water system by routing it into dug pits or recharge basins.

Water Supply

The primary water supply in the county is underground aquifers. This source is in a saturated wedge-shaped mass of unconsolidated deposits that overlie nearly impermeable consolidated bedrock. There are two major types of aquifers: a confined aquifer with ground water under artesian pressure and an unconfined aquifer in a water table (4).

The contour of the surface of the water table of Nassau County is roughly the same as that of the landscape topography. The water table is closest to the surface at the terminal moraine and is deeper toward the coasts. The artesian pressure surfaces generally are a few feet lower than the water table near the middle of the island, and they are a few feet higher than the water table near the coasts.

The aquifer system is in recognizable separate units. The upper glacial, or water table, aquifer is at the least depth and is made up primarily of sand and gravel deposits from the most recent glacial period. Deeper in the unconsolidated deposits are layers of good water-bearing strata. These are the Jameco, Magothy, and Lloyd aquifers. The Lloyd is the deepest and rests on bedrock.

Initially most wells were drilled into the shallower strata. As the population increased and supplying water became a municipal effort, wells were drilled into deeper strata and the shallower aquifers became more polluted as the amount of cesspool discharge reaching those aquifers increased.

Since much of the county borders saltwater, the encroachment of salt into the freshwater layers is a hazard. This intrusion results because the fresh ground water, salty ground water, and salty sea water are interconnected. Generally, if the freshwater reservoir is pumped out at rates that exceed natural recharge from surface precipitation, saltwater will occupy the void.

Effects of Man and Urbanization

The landscape of Nassau County has changed drastically over the past 50 years. Extensive housing developments, shopping centers, industrial complexes, and business corridors now dominate areas where vast acreages of potatoes and other crops were once grown for markets in New York City. The large areas of well drained, nearly level soils have provided suitable sites for development. Rapid urbanization has created an ever-increasing demand for public services, waste-disposal facilities, and recreation areas.

The main relatively undisturbed open areas are in the southern part of the county. Most are in golf courses, municipal parks, greenbelts bordering parkways, scattered wildlife preserves along drainageways, tidal marshes, and barrier beaches. The soils immediately along the slope that are sites for houses, marinas, and park facilities, such as at Wantagh Cow Meadow, Oceanside, Baldwin Harbor, and Bay Park, largely consist of dredgings from the bays and the ocean. These areas are mostly sandy soils that are variable in drainage due to the shallow depth of the water table. Many of these areas, including residences and small parks, experience inundation during abnormal high spring tides and winter storms. Soils in small parks, picnic areas, and athletic fields have often become compacted through intensive use, making planting and maintenance of grasses and shrubs difficult. Many areas within the larger parks, including Eisenhower Park, Bethpage State Park, and Restoration Village, the upper reaches of Valley Stream Park, and Hempstead Lake State Park, have retained much of their native quality, partly because of soil management to control erosion.

Some areas in the northern part of the county are still open and undisturbed. These areas are in a few vegetable and horse farms, areas of abandoned farms, large estates, partially wooded areas, preserve properties, and low-density or cluster subdivisions. The undulating to steep rolling glacial tills common to the north-central part of the county are variable in drainage, depending upon whether they are at the top of ridges or in low-lying pockets, and many of these soils have a

SOIL LEGEND

Publication symbols consist of letters or a combination of letters and a number (e.g., A1, M8B, or R1D). The first letter, always a capital, is the initial letter of the soil name. The second letter is lower case and separates map units, except those that are slope phases, having names that begin with the same letter. The third letter, always a capital, A, B, C, or D, indicates the slope. Symbols without a slope letter are for nearly level soils, soils named for higher categories, or for miscellaneous areas.

SYMBOL	NAME
A1	Allan loamy sand
B1	Beches
B1d	Berryland mucky loamy sand
Du	Duoland Udipsamments complex
EnA	Enfield silt loam, 0 to 3 percent slopes
EnB	Enfield silt loam, 3 to 8 percent slopes
Fr	Frederick muck
He	Hempstead silt loam
Ip	Ipswich mucky peat
Ma	Marathon muck
Mc	Malheur mucky peat
M1A	Montauk fine sandy loam, 0 to 3 percent slopes
M1B	Montauk fine sandy loam, 3 to 8 percent slopes
M1C	Montauk fine sandy loam, 8 to 15 percent slopes
M1D	Montauk fine sandy loam, 15 to 25 percent slopes
M1A	Montauk silt loam, 0 to 3 percent slopes
M1B	Montauk silt loam, 3 to 8 percent slopes
Pa	Pawcatuck mucky peat
Pg	Pits, ground water recharge
Ph	Pits, sand and gravel
P1B	Plymouth loamy sand, 3 to 8 percent slopes
P1C	Plymouth loamy sand, 8 to 15 percent slopes
P1D	Plymouth Riverhead complex, 15 to 35 percent slopes
R1A	Riverhead sandy loam, 0 to 3 percent slopes
R1B	Riverhead sandy loam, 3 to 8 percent slopes
R1C	Riverhead sandy loam, 8 to 15 percent slopes
R1D	Riverhead sandy loam, 15 to 25 percent slopes
Sc	Scioto silt loam
SdA	Scioto silt loam, till substratum, 0 to 3 percent slopes
SdR	Scioto silt loam, till substratum, 3 to 8 percent slopes
Su	Sudbury sandy loam
Ua	Udipsamments, rarely flooded
U1A	Udipsamments, nearly level
U1B	Udipsamments, steep
Ue	Udipsamments, wet substratum
Uf	Udipsamments, refuse substratum
Ug	Urban land
Uh	Urban land Hempstead complex
Um	Urban land Mineola complex
UnB	Urban land Montauk complex, 3 to 8 percent slopes
UnC	Urban land Montauk complex, 8 to 15 percent slopes
UpA	Urban land Plymouth complex, 0 to 3 percent slopes
UpB	Urban land Plymouth complex, 3 to 8 percent slopes
UpC	Urban land Plymouth complex, 8 to 15 percent slopes
UpD	Urban land Plymouth complex, 15 to 25 percent slopes
UrA	Urban land Riverhead complex, 0 to 3 percent slopes
UrB	Urban land Riverhead complex, 3 to 8 percent slopes
UrC	Urban land Riverhead complex, 8 to 15 percent slopes
Us	Urban land Sudbury complex
Uu	Urban land Udipsamments complex
Uw	Urban land Udipsamments, wet substratum complex
We	Wellington silt loam
Wd	Walpole sandy loam

CONVENTIONAL AND SPECIAL
SYMBOLS LEGEND

CULTURAL FEATURES

BOUNDARIES

National, state or province

County or parish

Minor civil division

Reservation (national forest or park,
state forest or park,
and large airport)

Land grant

Limit of soil survey (label)

Field sheet matchline & headline

ALLIANCE BOUNDARY (label)

Small airport, airfield, park, oilfield,
cemetery, or flood pond

STATE COORDINATE TICK

LAND DIVISION CORNERS
(sections and land grants)

ROADS

Divided (median shown
if scale permits)

Other roads

Trail

ROAD EMBLEM & DESIGNATIONS

Interstate

Federal

State

County, farm or ranch

RAILROAD

POWER TRANSMISSION LINE
(normally not shown)PIPE LINE
(normally not shown)FENCE
(normally not shown)

LEVEES

Without road

With road

With railroad

DAMS

Large (to scale)

Medium or small

PITS

Gravel pit

Mine or quarry

MISCELLANEOUS CULTURAL FEATURES

Farmstead, house
(omit in urban areas)

Church

School

Indian mound (label)

Isolated object (label)

Tank (label)

Wells, oil or gas

Windmill

Kitchen midden

WATER FEATURES

DRAINAGE

Perennial, double line

Perennial, single line

Intermittent

Drainage end

Canals or ditches

Double line (label)

Drainage and/or irrigation

LAKES, PONDS AND RESERVOIRS

Perennial

Intermittent

MISCELLANEOUS WATER FEATURES

Marsh or swamp

Spring

Well, artesian

Well, irrigation

Wet spot

SPECIAL SYMBOLS FOR
SOIL SURVEY

SOIL DELINEATIONS AND SYMBOLS

ESCARPMENTS

Bedrock
(points down slope)Other than bedrock
(points down slope)

SHORT STEEP SLOPE

GULLY

DEPRESSION OR HUNK

SOIL SAMPLE SITE
(normally not shown)

MISCELLANEOUS

Blowout

Clay spot

Gravelly spot

Gumbo, slick or wabby spot (soils)

Dumps and other similar
non soil areas

Prominent hill or peak

Rock outcrop
(includes sandstone and shale)

Saline spot


Sandy spot

Severely eroded spot

Slide or slip (lips point up slope)

Stony spot, very stony spot

Groundwater recharge pit
less than 2 ac.Area of Histosol
1/4 to 2 acres



TITLE: AREA C

SCALE: N/A

DATE: 4/25/88

REVISED:

DRAWN BY: RTP

PROJECT 4190-01

DRAWING # 4


103986



REFERENCE NO. 12

103987

Hydrogeology and Ground-Water Quality of the Northern Part of the Town of Oyster Bay, Nassau County, New York, in 1980



U.S. GEOLOGICAL SURVEY
Water-Resources Investigations
Report 85-4051

Prepared in cooperation with
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS




HYDROGEOLOGY AND GROUND-WATER QUALITY OF THE
NORTHERN PART OF THE TOWN OF OYSTER BAY,
NASSAU COUNTY, NEW YORK, IN 1980

By Chabot Kilburn and Richard K. Krulikas

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations
Report 85-4051

Prepared in cooperation with the
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS



Syosset, New York

1987

103989

HYDROGEOLOGY

The ground-water reservoir underlying the northern part of the Town of Oyster Bay consists of unconsolidated glacial deposits of Pleistocene age and coastal-plain deposits of continental and marine origin of Late Cretaceous age. These unconsolidated deposits consist of gravel, sand, silt, and clay and are underlain by bedrock of early Paleozoic and (or) Precambrian age. The bedrock, which is relatively impermeable, forms the base of the ground-water reservoir.

The thickness, character, and water-bearing properties of the aquifer and the relationships between hydrogeologic and geologic units underlying the study area are depicted in table 1. The correlations should be considered direct relationships as implied in the tables. The upper and lower boundaries of the hydrogeologic units are determined mainly from gross lithologic differences between units rather than the age of the deposits, which forms the basis for geologic correlations. For example, the upper and lower limits of the confining units (Port Washington confining unit and Raritan clay) are placed at intervals where the lithologic sequence changes from predominantly clay to sand or sand and gravel, and these positions may have no time-stratigraphic significance. For this reason, and because differentiation between sediments of Pleistocene and Cretaceous age is difficult and uncertain, it is possible that some deposits of Pleistocene age have been included in the upper part of the Magothy aquifer, which, by present definition, is approximately equivalent to the Magothy Formation-Matawan Group, undifferentiated, of Late Cretaceous age. The three hydrogeologic sections (pl. 1B) show the inferred extent, lateral and vertical relationships, and the variations in depth, thickness, lithology, and structure of these units.

Description of Hydrogeologic Units

Bedrock

Bedrock of early Paleozoic and (or) Precambrian age underlies all of western Long Island (Fisher and others, 1962). The bedrock generally consists of metamorphic and igneous crystalline rocks--schist, gneiss, and granite--and lies at depths ranging from about 350 ft below sea level along the north shore to about 950 ft below sea level in the southeast part of the study area (pl. 2A, and hydrogeologic sections, pl. 1B).

Bedrock is generally regarded as the base of the ground-water reservoir on Long Island because of its density and low permeability. No wells in the Town of Oyster Bay are known to obtain water from bedrock.

Lloyd Aquifer

The Lloyd aquifer is the equivalent of the Lloyd Sand Member of the Raritan Formation of Late Cretaceous age (Cohen and others, 1968, p. 18). It consists of discontinuous layers of gravel, sand, sandy clay, silt, and clay, and lies roughly parallel to the bedrock surface at depths ranging from about

200 ft below sea level along the north shore to about 700 ft below sea level in the southeast part of the study area (pl. 2B). Its thickness ranges from 0 to 250 ft from northwest to southeast, respectively.

The Lloyd aquifer is a major aquifer in the Town of Oyster Bay. It is probably hydraulically continuous with the adjacent Port Washington aquifer and upper glacial aquifer in the northern part of the study area. Water in the Lloyd aquifer is confined under artesian pressure beneath the Raritan clay.

Well yields during test pumping of large-capacity public-supply wells screened in the Lloyd aquifer have ranged from 500 gal/min to as much as 1600 gal/min.

Raritan Clay

The Raritan clay is a distinct hydrogeologic unit that extends throughout much of the Town of Oyster Bay (pl. 3A). In this area, the Raritan clay may be equivalent to the unnamed clay member of the Raritan Formation of Late Cretaceous age. The Raritan clay consists mainly of light to dark gray, red, white, or yellow clay and variable amounts of silt, and clayey silty fine sand. Sandy beds of varying thickness are common. The top of the Raritan clay is roughly parallel to that of the underlying Lloyd sand member. The upper-surface altitude of the Raritan clay ranges from 150 ft below sea level along the north shore to about 550 ft below sea level in the southeastern part of the study area. Its thickness ranges from 0 to 200 ft from northwest to southeast, respectively.

The Raritan clay is a significant hydrogeologic unit because it confines water in the underlying Lloyd aquifer. Although its hydraulic conductivity is very low, it does not entirely prevent movement of water between the Magothy and Lloyd aquifers. Some public-supply and other wells obtain part of their water supply from the sandy zones in the upper part of the Raritan clay.

Magothy Aquifer

The Magothy aquifer is the equivalent of the Matawan Group-Magothy Formation undifferentiated of upper Cretaceous age. Deposits in this unit consist of beds and lenses of light-gray, fine to coarse sand with some interstitial clay. Detailed lithologic descriptions are given in Soren (1978); Ku and others (1975); and Jensen and Soren (1974).

The top of the Magothy aquifer is not planar, unlike the surfaces of the underlying units. The Magothy surface was deeply eroded during Tertiary time and probably was considerably eroded in Pleistocene time. The upper surface altitude of the Magothy ranges from as high as 200 ft above sea level in the center of the study area to 200 ft below sea level along the northeast edge of the study area (pl. 3B). Its thickness ranges from 0 to 650 ft from northwest to southeast, respectively.

The Magothy aquifer is the principal aquifer underlying Long Island and is the island's main source of water for public supply. The sand beds within the aquifer are moderately to highly permeable. The reported yields during

pumping tests of several public-supply wells screened in the Magothy aquifer in the Town of Oyster Bay ranged from 300 gal/min to as much as 1,500 gal/min. The average yield was about 1,000 gal/min.

The large amount of clay in the upper half of the aquifer causes the water to become increasingly confined with depth. Along the north shore, the Magothy aquifer is probably in hydraulic continuity with the adjacent Port Washington aquifer. The Magothy also has a generally high degree of hydraulic continuity with the overlying upper glacial aquifer, but the degree of continuity may vary considerably from place to place.

Port Washington Aquifer

Two previously unrecognized hydrogeologic units in the northern part of the Town of Oyster Bay are defined as the Port Washington aquifer and Port Washington confining unit. The units were first recognized in the northern part of the Town of North Hempstead (Kilburn, 1979). The inferred limits of the units are shown in plates 4A and 4B, and their relationships to the other hydrologic units are shown on the hydrogeologic sections on plate 1B.

The Port Washington aquifer is a sequence of deposits of Pleistocene and (or) Late Cretaceous age that underlie the north-shore area of the Town of Oyster Bay. The deposits form a distinct hydrogeologic unit that rests upon bedrock and is overlain by a thick sequence of confining clay. The south edge of the deposits overlap and abut the adjacent Cretaceous units. The sediments of the Port Washington aquifer form part of the valley fill in the channels cut into the Cretaceous deposits. These deposits consist largely of sand or sand and gravel and varying amounts of interbedded clay, silt, and sandy clay.

The altitude of the top of the Port Washington aquifer ranges from 150 ft below sea level along the north shore to 450 ft below sea level along the south shore (pl. 4A). Its thickness ranges from 0 to more than 150 ft in the central parts of the study area.

The Port Washington aquifer is moderately to highly permeable and is a major aquifer in the northern parts of the Town of Oyster Bay. The reported yields during pumping tests of public-supply wells screened in the aquifer range from 300 gal/min to 1,200 gal/min. Water in the aquifer is confined beneath the Port Washington confining unit. The hydrogeologic relationships between the Port Washington aquifer and the abutting Lloyd, Magothy, and upper glacial aquifers, as shown in the hydrogeologic sections on plate 1B, suggest that these deposits could be in lateral hydraulic continuity. Potentiometric studies of the head in the Lloyd aquifer made by Swarzenski (1963), Kimmel (1973), and Kilburn (1979) tend to verify a lateral hydraulic continuity between the Port Washington and Lloyd aquifers.

Port Washington Confining Unit

The Port Washington confining unit is a sequence of deposits of Pleistocene or Late Cretaceous to Holocene(?) age that locally underlies the north shore. The unit consists mainly of clay and silt, with scattered lenses

of sand or sand and gravel. (See Kilburn, 1979, for a more detailed description.) The deposits that form the Port Washington confining unit overlie the Port Washington aquifer or overlap the adjacent Cretaceous units and may form part of the valley fill that occupies channels cut into the other Cretaceous deposits. The unit may locally include or consist of erosional remnants of the clay member of the Raritan Formation.

The altitude of the top of the Port Washington confining unit ranges from 100 ft above sea level in the central part of the study area to 300 ft below sea level along the northeastern part (pl. 4B). Its thickness ranges from 0 to more than 150 ft in the central part of the study area.

Upper Glacial Aquifer

The upper glacial aquifer consists of deposits of late Pleistocene and Holocene age that overlie the Magothy aquifer and the Port Washington confining unit and locally abut against or overlie the Port Washington aquifer. The extent and relationships of these deposits to the adjacent hydrogeologic units are shown on plate 1B.

The upper deposits consist mainly of stratified beds of fine to coarse sand and of sand and gravel but also contain thin beds of silt and clay interbedded with coarse-grained material. The outwash that constitutes the bulk of the upper Pleistocene deposits is yellow and brown or, in some places, gray. (See Perlmutter, 1949, and Kilburn, 1979, for further descriptions.)

The upper glacial aquifer, which contains the water table in most of the area, transmits all recharge to the underlying aquifers. Precipitation filtering downward to the water table is the principal source of ground-water recharge. In the past, the upper glacial aquifer was tapped as a water supply by many public-supply wells. Because it has become contaminated by cesspool effluents, fertilizers, and other substances, however, its use for public supply has decreased. Wells tapping the aquifer are now used mainly to supply water for domestic use, irrigation, and commercial and industrial purposes.

The sand and gravel deposits in the upper glacial aquifer are highly permeable and yield large amounts of water to properly constructed wells. The yields of large-capacity public-supply wells screened in the aquifer have been reported to range from 400 gal/min to 1,400 gal/min.

The recent deposits of Holocene age along beaches, streams, swamps, and the bottoms of bays and lakes have not been differentiated from the upper glacial aquifer because they are too thin.

Correlation of Units

The differentiation between deposits of Pleistocene and Cretaceous age throughout most of the northern part of the Town of Oyster Bay is uncertain. On Long Island, the contact between Pleistocene and Cretaceous deposits is an erosional unconformity that is commonly marked by an abrupt lithologic and

Water Movement

The lateral direction of ground-water flow can be estimated from water-table and potentiometric-surface maps. Ground water moves in the direction of decreasing head and perpendicular to the potentiometric contours. A vertical component of ground-water flow may also develop where differences in hydrostatic head are present with depth in an aquifer or between aquifers.

Upper Glacial Aquifer

The regional and local directions of lateral ground-water movement near the water table in the northern part of the Town of Oyster Bay are controlled from the regional and local ground-water divides (pl. 6A). Other smaller, local ground-water divides (not shown) are present on Mill Neck, Centre Island, and Cove Neck.

The lateral direction of ground-water movement near the water table is indicated on plate 6A by arrows. Water on the south side of the regional divide moves southward to discharge areas along the south shore; water north of the regional divide moves in two directions. Ground water east of the principal local divide shown on plate 6A moves toward discharge areas along or underlying Long Island Sound, Mill Neck Creek, Oyster Bay Harbor, or Cold Spring Harbor, and ground water west of the principal local divide moves westward to discharge areas along Glen Cove Creek or into Hempstead Harbor. Some water along the divides moves directly downward until it meets a zone of low permeability (for example, a clay bed or the top of the Port Washington confining unit or the Raritan confining unit), where it is diverted laterally.

Hydrostatic head differences between the water table (pl. 6A) and the potentiometric surface in the lower part of the Magothy aquifer (pl. 5A) during March and April 1980 ranged from less than 1 ft to more than 20 ft throughout most of the area except near the shore. The head differences were such that recharge from the water table could move downward into the Magothy aquifer over most of the area. Cones of depression due to local ground-water pumpage are not shown on plate 6A because the observation wells in the area are spaced too broadly to provide adequate definition.

Magothy Aquifer

The directions of lateral and vertical ground-water movement in the Magothy aquifer are controlled by the position of the regional and local potentiometric divides and by the hydraulic gradients. (See pl. 5A.) Some of the ground water along the divides moves downward to the bottom of the aquifer, where it then moves laterally toward areas of natural discharge or active pumping wells.

The areas of natural discharge from the Magothy aquifer can be inferred from plates 5A and 6A. Discharge occurs wherever the hydrostatic head in the Magothy is greater than that in the adjacent or overlying units. Water discharges from the Magothy aquifer into the upper glacial aquifer in areas adjacent to Hempstead Harbor and Oyster Bay Harbor, and into the Port Washington confining unit elsewhere.

Hydrostatic heads in the Magothy aquifer in 1980 exceeded those in the Lloyd aquifer by as much as 50 ft throughout a large part of the area. This is largely to the low permeability of the Raritan confining unit, which confines water in the Lloyd aquifer but does not prevent water from the areas of higher head in the Magothy from moving in the direction of decreasing head and perpendicular to the potentiometric contours.

Lloyd Aquifer

The Lloyd aquifer is recharged by water moving downward from the Magothy and upper glacial aquifers through the Raritan clay and Port Washington confining unit in response to the higher hydrostatic heads in the upper aquifers. The confining units impede but do not prevent this downward movement. The principal areas of recharge of the Lloyd aquifer are those underlying and adjacent to the regional and local potentiometric divides, where flow is predominantly downward (pl. 5B).

Areas of natural discharge of water from the Lloyd aquifer can be inferred from a comparison of heads in the Lloyd (pl. 5B), the Magothy (pl. 5A), and the water table (pl. 6A). Natural discharge from the Lloyd may occur in areas where the head in the Lloyd exceeds heads in overlying or adjacent units. These comparisons indicate that water from the Lloyd aquifer can move laterally and upward through the Port Washington aquifer (where present) and into the upper glacial aquifer, and thence into Hempstead Harbor (section C-C', pl. 1B). Other areas of discharge are along and beneath Long Island Sound (section A-A', pl. 1B). Some discharge may also occur in the Oyster Bay Harbor area (section C-C', pl. 1B) by movement of water upward through the Port Washington aquifer and Port Washington confining unit into the upper glacial aquifer and then into the harbor.

GROUND-WATER QUALITY

Data on ground-water quality in the northern part of the Town of Oyster Bay during 1950-79 are available mainly from analyses made by the Nassau County Department of Health. These analyses, together with those made by the U.S. Geological Survey, represent 155 wells. The number of samples per well during this period ranged from 1 to 37. The frequency of sampling varied, as did the constituents for which analyses were made. It was beyond the scope of this study to make a detailed study of water quality or to review the 2,168 analyses for obvious errors. It was assumed that the number of analyses in error was small enough to not significantly affect general interpretations of water quality that could be made from the analyses.

General Water Quality

Table 3 (p. 22) lists the median and range of the principal constituents and summarizes the general water quality of the three aquifers during 1950-79; Table 4 summarizes the ground-water quality in the northern part of the Town of Oyster Bay in 1979. The analyses are arranged by aquifer to facilitate comparison and to demonstrate changes with depth.

Table 4.--Chemical analyses of ground water from wells in northern part of Town of Oyster Bay, L.I.

[Concentrations in milligrams per liter unless otherwise indicated. Analyses by Nassau County Department of Health except as indicated. Dashes indicate no measurement recorded.]

Well data				Constituents					
Well number ¹	Date of sample	Depth of well (ft)	Use of well ³	Specific conductance (umho)	pH	Hardness (as CaCO ₃)	Calcium dissolved (as Ca)	Magnesium dissolved (as Mg)	Sodium dissolved (as Na)
Upper Glacial aquifer									
N1194A ²	6- 7-79	100	Obs.	360	5.7	90	26	6.1	40
N1209A	8-21-79	64	Obs.	--	5.9	72	18	.5	33
N2072 ²	9- 9-75	159	P.S.	25	5.2	8	2.0	.8	2.9
N3892	6-28-77	251	P.S.	170	6.4	42	9.6	.4	10
N5792	12-27-76	300	P.S.	50	6.4	56	14	.4	10
N7034	9-19-79	232	Irr.	--	6.3	80	18	.7	11
N7643	4- 5-78	218	P.S.	320	5.7	64	11	.7	50
N7665	4-10-79	375	P.S.	--	6.3	60	14	.5	12
N8183	1- 2-79	230	P.S.	150	6.3	47	11	.4	10
Magothy aquifer									
N3475	10-12-77	487	P.S.	65	6.4	15	2.8	0.2	5.1
N4097	3-26-79	470	P.S.	95	5.3	20	5.2	.1	7.4
N4400	1- 2-79	302	P.S.	88	7.0	25	5.2	.2	6.0
N5762	6-28-77	283	P.S.	140	6.6	38	8.8	.3	7.0
N6093	1-23-79	612	P.S.	40	5.6	8	1.6	.1	3.0
N6768	3-13-78	208	Inst.	--	6.3	54	12	.5	6.0
N7030	1-23-79	531	P.S.	140	6.3	44	11	.3	10
N7772	2-16-79	568	P.S.	70	6.4	20	5.6	.1	5.0
N8355	8- 9-78	595	P.S.	--	6.2	30	5.6	.3	6.0
N8713	7-31-78	377	P.S.	70	6.5	16	4.0	.1	4.0
Lloyd aquifer									
N 118	7-11-79	477	P.S.	65	6.9	18	4.0	0.2	4.9
N2920	9-12-77	--	P.S.	75	6.9	22	4.8	.2	10
N5201	7-31-78	509	P.S.	55	6.6	12	3.2	.1	.0
N7614	2-26-79	393	Ind.	--	6.6	14	2.4	.2	4.0
N7857	8-10-79	614	P.S.	41	6.1	14	4.0	.1	--
N8776	8-28-79	459	P.S.	46	6.5	10	2.4	.1	3.8

¹Well locations are shown in plate 1.

²Analyses by U.S. Geological Survey.

CL-4091
DIPKING
WELL

Constituents (Continued)

Well number ¹	Carbonate (as CO ₃)	Alkalinity total (as CaCO ₃)	Sulfate dissolved (as SO ₄)	Chloride dissolved (as Cl)	Silica dissolved (as SiO ₂)	Solids residue at 180°C	Solids (sum of dissolved constit- uents	Nitrogen Nitrate, dissolved (as N)	Iron total (µg/L as Fe)
Upper Glacial aquifer									
N1194A ²	0	25	29	82	13	--	214	2.3	810
N1209A	28	14	35	44	--	267	--	12	1,580
N2072 ²	0	4	.4	3.0	6.8	--	22	.71	60
N3892	14	16	11	17	--	155	--	3.2	230
N5792	20	20	9.0	13	--	153	--	4.4	60
N7034	28	14	36	23	--	209	--	8.7	200
N7643	17	10	54	41	--	302	--	19	0
N7665	20	14	32	11	--	190	--	4.4	110
N8183	17	20	7.0	14	--	113	--	6.4	0
Magothy aquifer									
N3475	4	12	0.0	6.5	--	33	--	2.0	100
N4097	8	4	.0	11	--	28	--	6.3	0
N4400	8	24	4.0	5.0	--	75	--	2.1	150
N5762	13	20	12	9.2	--	102	--	2.8	280
N6093	2	2	.0	4.0	--	53	--	1.3	60
N6768	18	14	33	7.8	--	116	--	2.9	260
N7030	17	10	18	10	--	102	--	4.5	190
N7772	8	12	.0	7.4	--	56	--	1.9	0
N8355	8	24	.0	10	--	67	--	3.5	0
N8713	6	9	.0	5.6	--	66	--	1.7	0
Lloyd aquifer									
N 118	6	17	3.0	5.0	--	56	--	2.0	50
N2920	7	16	.0	4.8	--	71	--	.73	130
N5201	5	13	.0	4.6	--	58	--	.02	100
N7614	4	12	.0	5.0	--	53	--	1.0	210
N7857	6	15	.0	8.0	--	76	--	.00	--
N8776	4	12	.0	2.5	--	33	--	.00	0

³ Obs.. observation well; P.S., public supply well; Irr., irrigation well;
Inst., institutional well; Ind., industrial well.

Table A.--Wells in northern part of Town of Oyster Bay that are closed or restricted because of contamination by (ates or volatile organic chemicals.

(Locations of wells are shown in pl. 1 and pl. 6B; dashes indicate data unavailable).

Well number	Well owner or user ¹	Screened interval or depth (feet below land surface)	Aquifer	Date		Contaminants
				Closed or abandoned	Restricted or reopened	
N 149	Hicksville W.D.	153	Upper Glacial	1967	--	Nitrate
150	Hicksville W.D.	148	Upper Glacial	1953	--	Nitrate
2072	Hicksville W.D.	138-159	Upper Glacial	1967	--	Nitrate
--- 2316	Pall Corp.	170	Upper Glacial	--	07/13/77	1,1,2 Trichloroethylene
--- 3466	City of Glen Cove	148-173	Upper Glacial	06/23/77	--	1,1,2 Trichloroethylene
--- N 3892	City of Glen Cove	139-172	--	--	--	--
		225-246	Upper Glacial	07/07/77	--	Tetrachloroethylene
3953	Hicksville W.D.	169-213	--	--	--	--
		371-419	Magothy	--	07/06/79	Nitrate
4097	Plainview W.D.	413-463	Magothy	12/28/76	06/13/77	1,1,2 Trichloroethylene, 1,1,1 Trichloroethane
4246	Jericho W.D.	403-453	Magothy	05/06/77	--	1,1,1 Trichloroethane
--- 5261	City of Glen Cove	131-170	--	--	--	--
		185-195	Port Washington	--	--	--
		220-230	confining unit	08/14/78	--	Tetrachloroethylene
N 6191	Hicksville W.D.	489-550	Magothy	--	1973	Nitrate
6531	Riverside Plastics	114-119	Upper Glacial	--	09/06/78	1,1,1 Trichloroethane Trichloroethylene
--- 6579	Glen Components	130-146	Upper Glacial	--	08/10/77	Trichloroethylene
--- 7427	Photocircuits	120-161	Upper Glacial	--	07/25/77	Trichloroethylene
7643	Village of Bayville	159-218	Upper Glacial	--	1967	Nitrate
--- N 7664	Engineer's Country Club	58-79	Upper Glacial	--	06/06/78	Tetrachloroethylene
--- 8326	City of Glen Cove	120-165	Upper Glacial	06/13/77	--	1,1,2 Trichloroethylene Tetrachloroethylene
--- 8327	City of Glen Cove	118-168	Upper Glacial	06/23/77	--	1,1,2 Trichloroethylene Tetrachloroethylene
8880	Metco Inc.	221-247	Magothy	--	05/05/78	Trichloroethylene
--- 8887	Slater Electric	105-130	Upper Glacial	--	07/13/77	Trichloroethylene

¹ W.D. = Water District

EXPLANATION OF COLUMN HEADINGS AND ABBREVIATIONS USED IN TABLE 6

Well Number

Well numbers are assigned by the New York State Department of Environmental Conservation. The prefix N designates Nassau County.

Owner or Well User

The owner or well user is in most cases the name shown on the completion report that was sent to the New York State Department of Environmental Conservation by the driller. During this study, it was found that many of the wells have changed ownership or user. New owners or well users are listed if known.

The following abbreviations are used in the "owner/user" column:

AM. PHYSICS INST	American Institute of Physics
ASSOC	Associates
BAYVILLE	Village of Bayville
BEAVER DAM CLUB	Beaver Dam Winter Sports Club
CC	Country Club
CERRO WIRE	Cerro Wire and Cable Co.
CERTIFIED IND	Certified Industries
CERT. REDI MIX	Certified Redi-Mix Co., Inc.
CL	Club
CO	Company
C.W. POST COLL.	C.W. Post Center of Long Island University
FABRIC LEATHER	Fabric Leather Corp.
FAIRCHILD CORP.	Fairchild Space and Defense Systems
GENERAL INST.	General Instrument Corp.
GLEN COVE	City of Glen Cove
GLEN COVE BOT.	Glen Cove Bottling Co.
GLEN COVE HOSP.	The Community Hospital at Glen Cove
INC	Incorporated
KOLLSMAN INST.	Kollsman Instrument Co.
LOCUST VLY WD	Locust Valley Water District
L.I. LIGHTING CO.	Long Island Lighting Co.
L.I. RAILROAD CO.	Long Island Railroad Co.
L.I. STATE PARK	Long Island State Park and Recreation Commission
	Planting Field Arboretum
L.I. TUNGSTEN	Li Tungsten Corp.
MILL NECK ESTS.	Association of Owners of Mill Neck Estates
NASSAU CO DPW	Nassau County Department of Public Works
NASSAU CO WTR	Nassau County Water Co.
NATL. PARK SERV	National Park Service
NEW YORK STATE	New York State Conservation Department Cold Spring
	Harbor Hatchery
OLD WESTBURY	Village of Old Westbury
OYSTER BAY	Town of Oyster Bay
PIPING ROCK WTR	Piping Rock Water Co.
POWERS CHEMCO	Powers Chemco, Inc.
REG. PLAN. BOARD	Nassau-Suffolk Regional Planning Board
RIVESIDE PLAS.	Riverside Plastics Corp.
ST. PATRICKS	Saint Patrick's Roman Catholic Church
ST. UNIV. AT O.W.	State University of New York College at Old Westbury

EXPLANATION OF COLUMN HEADINGS AND ABBREVIATIONS USED IN TABLE 6 (Continued)

SEA CLIFF WTR	Sea Cliff Water Co.
SEL-VRA ACRES	Association of Property Owners of SEL-VRA Acres
U.S. GEOL. SURV	U.S. Geological Survey
WD	Water District

Map Coord

Locations of wells are given by map coordinates, based on a latitude and longitude grid system, to aid the reader in locating the wells shown in plate 1. In this system, 5-minute intervals of latitude are lettered consecutively from south to north, and 5-minute intervals of longitude are numbered consecutively from west to east. The grid coordinates are shown along the margins of plate 1.

Year Completed

Year completed refers to the year in which the well was reported to have been completed or accepted by the original well owner. It may not always be the year in which the well was actually drilled, however.

Altitude of Land-Surface Datum (LSD)

The altitude of land surface at the well was estimated from U.S. Geological Survey 7-1/2-minute quadrangle topographic maps. At most observation wells, however, land-surface elevation was estimated from spirit leveling of the altitude of the measuring points of the wells and is probably accurate to the nearest foot.

Use of Water

The following abbreviations indicate the primary purpose for which water from the well is used:

ARCD	air conditioning	IRR	irrigation
COM	commercial	OTHR	other
DOM	domestic	P.S.	public supply
INST	institutional	RECH	recharge
IND	industrial	UNSD	unused

Use of Well

The following abbreviations indicate the principal use of the well or the purpose for which the well or hole was drilled:

DEST	well or hole destroyed	TEST	test hole
OBS	observation well	UNSD	well unused
RECH	recharge water	WTDR	withdrawal of water

Depth of Well

The figures give well depth or total depth of the drilled test hole, in feet below land surface.

EXPLANATION OF COLUMN HEADINGS AND ABBREVIATIONS USED IN TABLE 6 (Continued)

Screen Setting and Total Screen Length

The altitudes of the top and bottom of the screened interval are given in feet above or below (-) sea level. The total length of screen or perforated pipe in that interval is given in feet. In some wells, screen was set at two or more intervals; in such cases the differences between the altitudes of the two screen settings is different from the total screen length.

Diameter of Well

The diameter of the well is the nominal inside diameter of the smallest or innermost casing at land surface, in inches.

Water Level (feet below land-surface datum)

The water level given is the reported original static water level, in feet above or below land surface, when the well was completed.

Date of Measurement

Date of water-level measurement is by month (M), day (D), and year (Y).

Lift Type

The following abbreviations indicate the type of pump or other conveyance used to bring water to the surface:

CENT	centrifugal	TURB	turbine
JET	jet	NONE	no pump in well
SUBM	submersible	OTHR	some other type of lift

Aquifer Developed

The following abbreviations indicate the hydrogeologic unit that yields water to the well. Where two or more units yield water to the well, the probable principal unit is given:

UPGLAC	Upper glacial aquifer	MAGOTHY	Magothy aquifer
PTWCU	Port Washington confining unit	LLOYD	Lloyd aquifer
PTWAQ	Port Washington aquifer		

Specific Capacity

The value in this column is the number of gallons per minute pumped from the well per foot of drawdown in the well, as reported by drillers.

Abbreviations

COORD	coordinates	IN	inches
D	day	LSD	land surface datum
DIAM	diameter	M	month
FT	feet	MEAS	measurement
GPM/FT	gallons per minute pumped per foot of drawdown in well	SL	sea level
		Y	year

Wells within 3 miles of Li Tungsten are marked as such --

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT DEVEL- TYPE	AQUIFER DEVELOPED	SPECIFIC CAPACITY [(GAL/MIN)/FT]
N 107	OLD WESTBURY	D 6	1935	212	P.S.	WTDR	504	-243 TO	-279	36	132	08-18-35	TURR	MAGOTHY	1
N 109	JERICHO WD	D 6	1925	48	UNSD	DEST	529	-384 TO	-465	59	26	06-27-24	NONE	LLOYD	20
N 110	JERICHO WD	D 6	1924	56	UNSD	OBS	519	-389 TO	-459	70	24.0	07-05-24	NONE	LLOYD	13
N 112	GLEN COVE	E 6	1930	53	UNSD	DEST	169	-79 TO	-116	37			NONE	UPGLAC	
N 114	NASSAU CC	E 6	1910	123	INR	WTDR	117	30 TO	10	20				MAGOTHY	
N 115	LOCUST VLY WD	E 6	1925	75	UNSD	UNSD	414	-265 TO	-332	67			TURR	PTWAO	7
N 116	LOCUST VLY WD	E 6	1925	80	UNSD	UNSD	254						NONE	UPGLAC	
N 117	LOCUST VLY WD	E 6		77	UNSD	UNSD	155			16			NONE	JPGLAC	
N 118	LOCUST VLY WD	E 6	1932	45	P.S.	WTDR	477	-347 TO	-406	59			TURR	LLOYD	19
N 119	LOCUST VLY WD	E 6	1935	80	P.S.	WTDR	572	-417 TO	-491	74			TURR	LLOYD	29
N 120	LOCUST VLY WD	E 6	1933	80	UNSD	TEST	554						NONE		
N 121	CREEK CLUR	E 6	1933	120	UNSD	TEST	415						NONE		
N 121	CREEK CLUR	E 6	1933	120	INR	WTDR	219	-29 TO	-87	42	56.5	10-00-33	TURR	UPGLAC	24
N 124	CREEK CLUR	E 6	1920	9	UNSD	OBS	390			12			NONE	LLOYD	
N 149	HICKSVILLE WD	D 7		161	UNSD	UNSD	153						NONE	UPGLAC	
N 150	HICKSVILLE WD	D 7		161	UNSD	DEST	144							UPGLAC	14
N 166	PIPING ROCK WTR	E 7	1936	55	UNSD	UNSD	114	-43 TO	-63	20	4.8	11-19-36	NONE	MAGOTHY	28
N 167	PIPING ROCK WTR	E 7	1936	55	UNSD	UNSD	123	-45 TO	-65	20			NONE	MAGOTHY	
N 173	M.C.TAYLOR	E 7	1920	34	DOM	WTDR	394			11	14.5	03-00-20	TURR	LLOYD	
N 198	JERICHO WD	D 8	1930	240	P.S.	WTDR	624	-327 TO	-377	50			TURR	MAGOTHY	37
N 199	JERICHO WD	D 8	1930	235	P.S.	WTDR	611	-309 TO	-365	56			TURR	MAGOTHY	28
N 202	OYSTER RAY WD	E 7		18	UNSD	UNSD	420						NONE	LLOYD	
N 486	A.HUTCHINSON	E 7		3			140			5					
N 511	W.P.WOODBRIDGE	E 7	1905	11	UNSD	OBS	359			6			NONE	PTWAO	
N 551	NATL. PARK SERV	E 7		154	UNSD	UNSD	325							PTWCU	
N 570	JERICHO WD	D 8	1937	237	P.S.	WTDR	600	-323 TO	-363	40	178	07-15-37	TURR	MAGOTHY	64
N 576	L.I.RAILROAD CO	D 7	1936	144	UNSD		409	-255 TO	-265	10			NONE	MAGOTHY	
N 585	OYSTER RAY WD	E 7	1937	18	P.S.	WTDR	74	-39 TO	-59	20	2	09-03-37	OTHR	UPGLAC	15
N 590	NATL. PARK SERV	E 8	1937	120	DOM	WTDR	165	-32 TO	-42	10	130	07-21-37		PTWCU	6
N 613	PIPING ROCK WTR	E 7	1937	55	UNSD	DEST	140	-61 TO	-81	20	5.5	12-10-37	NONE	MAGOTHY	18
N 614	PIPING ROCK WTR	E 7	1937	55	UNSD	UNSD	122	-44 TO	-64	20	4.5	12-28-37	NONE	MAGOTHY	28
N 638	OLD WESTBURY CC	D 6	1938	294	INR	WTDR	560	-250 TO	-265	15	209	00-00-62	TURR	MAGOTHY	3
N 660	POWERS CHEMCO	E 6		58	IND	WTDR	404			15			TURR	LLOYD	
N 661	POWERS CHEMCO	E 6	1939	60	UNSD	UNSD	403	-264 TO	-340	70			NONE	LLOYD	11
N 733	OYSTER RAY WD	E 7		18	UNSD	DEST	350			6			NONE	PTWAO	
N 734	OYSTER RAY WD	E 7		18	UNSD	UNSD	420			10			NONE	LLOYD	12
N 735	OYSTER RAY WD	E 7		18	P.S.	WTDR	100						OTHR	UPGLAC	
N 736	OYSTER RAY WD	E 7		20	P.S.	WTDR	70			6			OTHR	UPGLAC	
N 801	GLEN COVE	E 6		53	UNSD	DEST	36			10			NONE	UPGLAC	
N 802	GLEN COVE	E 6		53	UNSD	DEST	162			8			NONE	UPGLAC	

104002

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST PIPES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COM- PLETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	AQUIFER LIFT DEVEL- TYPE OPED	SPECIFIC CAPACITY [(GAL/MIN)/FT]
N A03	GLEN COVE	E 6		53	UNSD	DEST	162			8			NONE UPGLAC	
N A04	GLEN COVE	E 6		53	UNSD	DEST	151			8			NONE UPGLAC	
N A05	GLEN COVE	E 6		53	UNSD	DEST	120			6			NONE UPGLAC	
N A06	GLEN COVE	E 6		53	UNSD	DEST	122			6			NONE UPGLAC	
N A07	GLEN COVE	E 6		53	UNSD	DEST	144			8			NONE UPGLAC	
N A08	GLEN COVE	E 6		53	UNSD	DEST	55			8			NONE UPGLAC	
N A09	GLEN COVE	E 6		53	UNSD	DEST	49			8			NONE UPGLAC	
N A10	GLEN COVE	E 6		53	UNSD	DEST	52	17 TO	1	16	10		NONE UPGLAC	
N A11	GLEN COVE	E 6		53	UNSD	DEST	42			8			NONE UPGLAC	
N A11	GLEN COVE	E 6	1951	53	UNSD	DEST	58	11 TO	-5	16			NONE UPGLAC	
N A12	GLEN COVE	E 6		53	UNSD	DEST	52			8			NONE UPGLAC	
N A13	GLEN COVE	E 6		53	UNSD	DEST	55			8			NONE UPGLAC	
N A14	GLEN COVE	E 6		53	UNSD	DEST	144			8			NONE UPGLAC	
N A15	GLEN COVE	E 6		53	UNSD	DEST	161			6			NONE UPGLAC	
N A16	GLEN COVE	E 6		53	UNSD	DEST	160			6			NONE UPGLAC	
N A17	GLEN COVE	E 6		53	UNSD	DEST	164			10			NONE UPGLAC	
N A18	GLEN COVE	E 6		53	UNSD	DEST	159			10			NONE UPGLAC	
N A34	GLEN COVE	E 6		10	UNSD	UNSD	302	-272 TO	-292	20	8		NONE UPGLAC	
N A35	GLEN COVE	E 6	1931	10	P.S.	WTDR	303	-266 TO	-290	24	10		NONE UPGLAC	
N A42	SEA CLIFF WATER	E 6	1940	8	UNSD	UNSD	420	-357 TO	-407	50	20	FLOWING 07-19-40	NONE LLOYD	
N A44	L.I. RAILROAD CO	D 7		140	UNSD		258			10			NONE MAGNETHY	
N 901	SFA CLIFF WATER	E 6	1915	9	UNSD	DEST	84			10			NONE UPGLAC	
N 901	SFA CLIFF WATER	E 6	1951	9	P.S.	WTDR	68	-37 TO	-59	22	8		OTHR UPGLAC	
N 902	SFA CLIFF WATER	E 6	1921	9	UNSD	DEST	84						NONE UPGLAC	
N 902	SFA CLIFF WATER	E 6	1946	9	P.S.	WTDR	60			10			OTHR UPGLAC	
N 903	SEA CLIFF WATER	E 6	1921	9	P.S.	WTDR	184			10			OTHR UPGLAC	
N 904	SFA CLIFF WATER	E 6	1917	9	UNSD	UNSD	80			10			NONE UPGLAC	
N 905	SFA CLIFF WATER	E 6	1921	9	UNSD	DEST	80			8			NONE UPGLAC	
N 905	SEA CLIFF WATER	E 6	1951	9	P.S.	WTDR	67	-37 TO	-58	21	8		OTHR UPGLAC	
N 906	SEA CLIFF WATER	E 6	1927	9	P.S.	WTDR	419						OTHR LLOYD	
N 907	SEA CLIFF WATER	E 6		9	P.S.	WTDR	134			10			OTHR PTWCU	
N 908	SFA CLIFF WATER	E 6		9	P.S.	WTDR	293			10			OTHR PTWCU	
N 909	SFA CLIFF WATER	E 6		9	P.S.	WTDR	196			10			OTHR PTWCU	
N 1037	SEA CLIFF WATER	E 6	1940	10	P.S.	WTDR	68	-35 TO	-55	20	24	8 01-25-40	OTHR UPGLAC	34
N 1149	NASSAU CO DPW	E 6	1941	89	UNSD	OBS	82			2.50	48.25	09-25-41	NONE PTWCU	
N 1150	NASSAU CO DPW	E 6	1938	53	UNSD	DEST	21			1.25	15.29	06-09-38	NONE UPGLAC	
N 1150	NASSAU CO DPW	E 6	1966	46	UNSD	OBS	28	31 TO	28	3	1.25	19.57 05-27-66	TURB UPGLAC	
N 1151	NASSAU CO DPW	E 6	1938	34	UNSD	DEST	26			1.25	11.89	06-09-38	NONE UPGLAC	
N 1151	NASSAU CO DPW	E 6	1965	33	UNSD	OBS	23	13 TO	10	3	1.25	10.08 04-09-65	NONE UPGLAC	
N 1152	NASSAU CO DPW	E 6	1940	154	UNSD	DEST	130			4	102.94	08-06-40	NONE UPGLAC	

104003

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT DEVEL- OPED TYPE	AQUIFER	SPECIFIC CAPACITY ((GAL/MIN)/FT)	
N 1152	NASSAU CO DPW	E 6	1965	154	UNSD	OHS				4	107.74	06-07-65	NONE	JPGLAC		
N 1153	NASSAU CO DPW	E 6	1940	122	UNSD	OHS	86			2.50	59.70	09-09-40	NONE	MAGOTHY		
N 1170	NASSAU CO DPW	E 6	1938	10	UNSD	OHS	49			1.25			NONE	JPGLAC		
N 1170	NASSAU CO DPW	E 6	1976	10	UNSD	OHS	14	-1 TO	-6	5	4		NONE	JPGLAC		
N 1171	NASSAU CO DPW	E 6	1938	68	UNSD	DEST	41			1.25			NONE	JPGLAC		
N 1171	NASSAU CO DPW	E 6	1942	83	UNSD	DEST	38			2.50	20.90	09-11-42	NONE	JPGLAC		
N 1172	NASSAU CO DPW	E 6	1940	144	UNSD	OHS	102			2.50	83.35	09-24-40	NONE	JPGLAC		
N 1173	NASSAU CO DPW	E 6	1941	145	UNSD	DEST	97	53 TO	48	5	2.50	78.65	09-11-41	NONE	JPGLAC	
N 1174	NASSAU CO DPW	E 6	1940	113	UNSD	DEST	60			2.50	38.69	09-13-40	NONE	MAGOTHY		
N 1175	NASSAU CO DPW	D 6	1940	177	UNSD	DEST	158			4	92.50	10-24-40	NONE	MAGOTHY		
N 1176	NASSAU CO DPW	D 6	1940	195	UNSD	OHS	198			4	109.28	10-08-40	NONE	MAGOTHY		
N 1187	NASSAU CO DPW	E 7	1938	6	UNSD	DEST	25			1.25			NONE	JPGLAC		
N 1188	NASSAU CO DPW	E 7	1938	37	UNSD	DEST	34			1.25	17.03	07-25-38	NONE	JPGLAC		
N 1188	NASSAU CO DPW	E 7	1961	35	UNSD	OHS	29	9 TO	6	3	1.25	10.20	11-22-61	NONE	JPGLAC	
N 1189	NASSAU CO DPW	E 7	1940	67	UNSD	OHS	33			1.25	12.78	11-26-40	NONE	PTWCU		
N 1190	NASSAU CO DPW	E 7	1940	128	UNSD	OHS	99			4	67.62	11-06-40	NONE	JPGLAC		
N 1191	NASSAU CO DPW	E 7	1940	154	UNSD	DEST	97			2.50	77.76	11-22-40	NONE	JPGLAC		
N 1192	NASSAU CO DPW	D 7	1941	143	UNSD	OHS	78	70 TO	65	5	2.50	55.73	08-11-41	NONE	MAGOTHY	
N 1193	NASSAU CO DPW	D 7	1940	231	UNSD	DEST	161			2.50	141.40	10-18-40	NONE	MAGOTHY		
N 1194	NASSAU CO DPW	D 7	1940	174	UNSD	DEST	104			2.50	85.60	10-31-40	NONE	JPGLAC		
N 1194	NASSAU CO DPW	D 7	1961	168	UNSD	OHS	100			4	79.20	12-14-61	NONE	JPGLAC		
N 1195	NASSAU CO DPW	D 7	1941	147	UNSD	DEST	84	68 TO	63	5	2.50	64.45	09-16-41	NONE	JPGLAC	
N 1195	NASSAU CO DPW	D 7	1961	148	UNSD	TEST	155						NONE			
N 1195	NASSAU CO DPW	D 7	1961	148	UNSD	DEST	77			1.25	61.85	11-30-61	NONE	JPGLAC		
N 1195	NASSAU CO DPW	D 7	1966	148	UNSD	DEST	93			1.25	58.00	11-22-66	NONE	JPGLAC		
N 1195	NASSAU CO DPW	D 7	1976	148	UNSD	OHS	116	37 TO	32	5	4	63.70	08-18-76	NONE	MAGOTHY	
N 1206	NASSAU CO DPW	E 7	1938	9	UNSD	DEST	30			1.25			NONE	JPGLAC		
N 1207	NASSAU CO DPW	E 7	1938	23	UNSD	OHS	24			1.25			NONE	JPGLAC		
N 1208	NASSAU CO DPW	E 7	1938	59	UNSD	DEST	31			1.25	15.21	07-28-38	NONE	JPGLAC		
N 1208	NASSAU CO DPW	E 7	1959	59	UNSD	DEST	31			1.25			NONE	JPGLAC		
N 1208	NASSAU CO DPW	E 7	1963	58	UNSD	OHS	33	28 TO	25	3	1.25	13.45	02-19-63	NONE	JPGLAC	
N 1209	NASSAU CO DPW	E 7	1941	126	UNSD	DEST	68	63 TO	58	5	2.50	49.03	06-10-41	NONE	JPGLAC	
N 1209	NASSAU CO DPW	E 7	1942	126	UNSD	DEST	133			2.50	49.31	11-20-42	NONE	JPGLAC		
N 1209	NASSAU CO DPW	E 7	1943	126	UNSD	DEST	129			2.50	50.20	06-23-43	NONE	JPGLAC		
N 1209	NASSAU CO DPW	E 7	1943	126	UNSD	DEST	174			4	27.44	12-16-42	NONE	JPGLAC		
N 1209	NASSAU CO DPW	E 7	1961	122	UNSD	OHS	64			4	38.07	12-29-61	NONE	JPGLAC		
N 1210	NASSAU CO DPW	E 7	1941	188	UNSD	DEST	108			2.50	96.25	06-24-41	NONE	MAGOTHY		
N 1210	NASSAU CO DPW	E 7	1942	188	UNSD	DEST	140	53 TO	48	5	2.50	93.90	07-30-42	NONE	MAGOTHY	
N 1210	NASSAU CO DPW	E 7	1965	187	UNSD	OHS	143	47 TO	44	3	1.25	98.84	04-06-65	NONE	MAGOTHY	
N 1211	NASSAU CO DPW	D 7	1941	217	UNSD	OHS	156	66 TO	61	5	2.50	141.55	06-03-41	NONE	JPGLAC	

104004

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TESTS IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, N.E.K.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	AQUIFER LIFT DEVEL- OPED TYPE	SPECIFIC CAPACITY [(GAL/MIN)/FT]
N 1212	NASSAU CO DPW	D 7	1941	227	UNSD	DEST	125			4	96.18	04-25-41	NONE MAGOTHY	
N 1212	NASSAU CO DPW	D 7	1942	227	UNSD	OBS	185	48 TO	42	6	143.48	07-20-42	NONE MAGOTHY	
N 1213	NASSAU CO DPW	D 7	1941	175	UNSD	DEST	109	71 TO	66	5	89.98	05-15-41	NONE UPGLAC	
N 1214	NASSAU CO DPW	D 7	1938	149	UNSD	DEST	80			1.25	68.78	10-13-38	NONE UPGLAC	
N 1214	NASSAU CO DPW	D 7	1950	149	UNSD	DEST	77			1.25	62.00	02-18-50	NONE UPGLAC	
N 1214	NASSAU CO DPW	D 7	1965	149	UNSD	OBS	85	66 TO	63	3	73.14	09-22-65	NONE UPGLAC	
N 1224	NASSAU CO DPW	E 7	1941	25	UNSD	OBS	38	-10 TO	-13	3	22.37	10-06-41	NONE UPGLAC	
N 1225	NASSAU CO DPW	E 7	1938	8	UNSD	OBS	20			1.25	5.32	07-29-38	NONE UPGLAC	
N 1226	NASSAU CO DPW	E 7	1941	74	UNSD	OBS	62	-26 TO	-28	2	9.18	10-09-41	NONE PTWCU	
N 1227	NASSAU CO DPW	E 8	1941	172	UNSD	OBS	134	43 TO	38	5	120.17	07-23-41	NONE MAGOTHY	
N 1228	NASSAU CO DPW	D 8	1941	224	UNSD	DEST	189	41 TO	35	6	156.59	03-13-41	NONE UPGLAC	
N 1228	NASSAU CO DPW	D 8	1941	224	UNSD	DEST	179	51 TO	45	6	156.88	09-06-41	NONE UPGLAC	
N 1228	NASSAU CO DPW	D 8	1962	227	UNSD	OBS	174	54 TO	51	3	158.27	02-06-62	NONE UPGLAC	
N 1229	NASSAU CO DPW	D 8	1941	251	UNSD	OBS	201			4	173.17	01-09-41	NONE MAGOTHY	
N 1230	NASSAU CO DPW	D 8	1940	174	UNSD	DEST	144			2.50	90.52	12-13-40	NONE MAGOTHY	
N 1231	NASSAU CO DPW	D 8	1940	143	UNSD	DEST	83			2.50	61.46	11-27-40	NONE MAGOTHY	
N 1231	NASSAU CO DPW	D 8	1962	139	UNSD	OBS	81			2.50	53.72	03-30-62	NONE MAGOTHY	
N 1242	NASSAU CO DPW	E 8	1938	41	UNSD	DEST	31			1.25			NONE UPGLAC	
N 1242	NASSAU CO DPW	E 8	1953	41	UNSD	OBS	32			1.25	14.69	01-05-53	NONE UPGLAC	
N 1243	NASSAU CO DPW	E 8	1939	65	UNSD	DEST	22			1.25			NONE UPGLAC	
N 1243	NASSAU CO DPW	E 8	1953	65	UNSD	DEST	24	44 TO	41	3	7.15	01-07-53	NONE UPGLAC	
N 1243	NASSAU CO DPW	E 8	1954	67	UNSD	DEST				1.25			NONE UPGLAC	
N 1243	NASSAU CO DPW	E 8	1966	64	UNSD	DEST	28	39 TO	36	3	16.00	12-08-66	NONE MAGOTHY	
N 1243	NASSAU CO DPW	E 8	1975	64	UNSD	OBS	28	39 TO	36	3	6.44	09-27-75	NONE MAGOTHY	
N 1244	NASSAU CO DPW	D 8	1940	249	UNSD		262	-9 TO	-11	3	171.65	04-03-40	NONE MAGOTHY	
N 1245	NASSAU CO DPW	D 8	1940	260	UNSD	OBS	202			2.50	175.58	01-02-40	NONE MAGOTHY	
N 1246	NASSAU CO DPW	D 8	1940	186	UNSD	OBS	124			4	102.77	04-30-40	NONE MAGOTHY	
N 1327	SEA CLIFF WATER	E 6	1940	10	P.S.	WTDR	124	-91 TO	-116	25	FLOWING	05-22-40	OTHER UPGLAC	
N 1476	NASSAU CO DPW	E 7	1944	130	UNSD	OBS	81			4			NONE MAGOTHY	
N 1477	NASSAU CO DPW	E 7	1944	216	UNSD	OBS	194			4			NONE UPGLAC	
N 1481	NASSAU CO DPW	D 7	1944	149	UNSD	DEST	77			4	67.55	04-18-44	NONE UPGLAC	
N 1486	J.R.SOLERWITZ	E 8	1927	5	DOM	WTDR	500			8			NONE LLOYD	
N 1595	SEA CLIFF WATER	E 6	1940	11	P.S.	WTDR	125	-84 TO	-114	30	2	09-23-40	UPGLAC	15
N 1651	LOCUST VLY WD	E 6	1941	162	P.S.	WTDR	479	-223 TO	-303	80	145	01-19-41	TURB LLOYD	24
N 1767	OYSTER BAY	D 8	1941	251	DOM	WTDR	542	-310 TO	-331	21	180	10-10-41	MAGOTHY	10
N 1768	OYSTER BAY	D 8		250			260			8			MAGOTHY	
N 1773	ST.UNIV.AT O.W.	D 7	1942	228	UNSD	UNSD	293	-53 TO	-65	12	151	01-14-42	TURB MAGOTHY	
N 1774	ST.UNIV.AT O.W.	D 7		241	UNSD	UNSD	134			8			NONE UPGLAC	
N 1775	ST.UNIV.AT O.W.	D 7		188	UNSD	UNSD	286			8			TURB MAGOTHY	
N 1917	LI TUNGSTEN	E 6	1943	15	IND	WTDR	307	-281 TO	-291	10			TURB LLOYD	

104005

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT DEVEL- OPED TYPE	AQUIFER	SPECIFIC CAPACITY [(GAL/MIN)/FT]	
N 2017	FRIEDMAN	E 7	1945	10	DOM	WTDR	395	-375 TO	-384	9	8	FLOWING	04-25-45	LLOYD		
N 2027	SORFENSON LUMREN	E 6	1945	21	UNSD	DEST	74	-39 TO	-54	15	6	FLOWING	04-10-45	NONE	UPGLAC	17
N 2060	GLEN COVE ROT.	E 6	1946	24	UNSD	UNSD	82	-34 TO	-44	10	8	8	06-01-46		UPGLAC	13
N 2072	HICKSVILLE WD	D 7	1946	162	UNSD	DEST	159	24 TO	3	21	10	80	05-15-46	TURR	UPGLAC	28
N 2087	POWERS CHEMCO	E 6	1946	50	UNSD	DEST	75	-9 TO	-25	16	8	15	02-25-46	NONE	UPGLAC	2
N 2087	POWERS CHEMCO	E 6	1946	50	IND	WTDR	345	-284 TO	-295	11	8	20	07-15-52	TURR	LLOYD	6
N 2088	F.M.GOULD	E 8	1932	159			605								LLOYD	
N 2113	G.CARDELLI	E 7	1946	10	DOM	WTDR	449	-417 TO	-439	22	8	FLOWING	05-16-46		LLOYD	
N 2132	KOENIG	E 7	1907	10	UNSD	DEST	469			5		FLOWING	00-00-14	NONE	LLOYD	
N 2208	NEW YORK STATE	E 8	1903	15	IND	WTDR	74			6				NONE	UPGLAC	
N 2209	NEW YORK STATE	E 8	1903	15	IND	WTDR	84			6				NONE	UPGLAC	
N 2210	NEW YORK STATE	E 8	1903	15	IND	WTDR	84			5				NONE	UPGLAC	
N 2211	NEW YORK STATE	E 8	1903	15	IND	WTDR	66			6				NONE	UPGLAC	
N 2238	L.I.RAILROAD CO	E 7		10			198			8				PTWCU		
N 2241	RAKER-CAMPRELL	E 7	1947	18	DOM	WTDR	374	-346 TO	-358	12	8	*6	10-01-47	LLOYD		25
N 2316	PALL CORP	E 6	1930	157	IND	WTDR	170			6				TURR	UPGLAC	
N 2409	NEW YORK STATE	E 8	1947	15	IND	WTDR	93	-51 TO	-71	20	10	FLOWING	09-10-47	NONE	UPGLAC	18
N 2410	NEW YORK STATE	E 8	1947	15	IND	WTDR	90	-50 TO	-70	20	10	FLOWING	09-12-47	NONE	UPGLAC	25
N 2528	NASSAU CO DPW	E 7	1946	92	UNSD	TEST	343							NONE		
N 2528	NASSAU CO DPW	E 7	1947	93	UNSD	OHS	328	-185 TO	-189	4	6			NONE	UPGLAC	
N 2616	GLEN HEAD CC	E 6	1931	75	INR	WTDR	232	-109 TO	-146	37	12	8	01-30-30	TURR	UPGLAC	59
N 2920	SFL-VRA ACRES	E 8	1948	10	P.S.	WTDR				10					LLOYD	
N 3310	L.I.LIGHTING CO	D 6	1949	27	IND	WTDR	151	-93 TO	-124	31	12	4.9	06-27-49	TURR	UPGLAC	43
N 3444	JERICHO WD	D 7	1949	263	UNSD	TEST	460							NONE		
N 3466	GLEN COVE	E 6	1950	53	P.S.	WTDR	177	-95 TO	-120	25	12	FLOWING	04-25-50		UPGLAC	9
N 3474	JERICHO WD	D 7	1951	244	P.S.	WTDR	517	-208 TO	-268	60	18	153	06-02-50	TURR	MAGOTHY	31
N 3475	JERICHO WD	D 7	1950	208	P.S.	WTDR	487	-224 TO	-274	50	18	121	07-22-50	TURR	MAGOTHY	36
N 3496	OYSTER BAY WD	E 7	1950	18	P.S.	WTDR	102	-52 TO	-84	32	12				UPGLAC	
N 3561	OYSTER BAY WD	E 7	1950	18	P.S.	WTDR	120	-70 TO	-100	30	12	FLOWING	08-31-50		UPGLAC	
N 3569	CERRO WIRE	D 7	1951	181	IND	WTDR	402	-172 TO	-221	49	16	95	06-04-51	TURR	MAGOTHY	10
N 3838	SPIEGEL ASSOC.	D 7	1951	195	UNSD	DEST	163	42 TO	32	10	8	105	12-03-51	NONE	MAGOTHY	4
N 3850	FAIRCHILD CORP	D 7		185	UNSD	TEST	501							NONE		
N 3850	FAIRCHILD CORP	D 7	1953	185	UNSD	UNSD	445	-215 TO	-255	40	16	104	02-08-52	TURR	MAGOTHY	39
N 3860	FAIRCHILD CORP	D 7	1953	183	UNSD	UNSD	445	-217 TO	-257	40	16	101	03-25-52	SUBM	MAGOTHY	43
N 3874	FAIRCHILD CORP	D 7	1952	183	UNSD	UNSD	335	-127 TO	-147	20	16	106	11-06-52	TURR	MAGOTHY	8
N 3877	HICKSVILLE WD	D 7	1952	152	UNSD	TEST	555							NONE		
N 3878	HICKSVILLE WD	D 7	1952	150	UNSD	TEST	604							NONE		
N 3878	HICKSVILLE WD	D 7	1952	150	P.S.	WTDR	428	-225 TO	-278	53	18	67	07-22-52	TURR	MAGOTHY	53
N 3892	GLEN COVE	E 6	1953	145	UNSD	TEST	445							NONE		
N 3892	GLEN COVE	E 6	1953	145	P.S.	WTDR	251	6 TO	-101	54	16	87	10-07-53		UPGLAC	40

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST

S IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMPLETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT TYPE	AQUIFER DEVEL- OPED	SPECIFIC CAPACITY ((GAL/MIN)/FT)
N 3925	COCA COLA CO	D 7	1952	158	UNSD	UNSD	143	36 TO	15	21	63	08-14-52	TURR	UPGLAC	
N 3953	HICKSVILLE WD	D 7	1952	152	UNSD	TEST	514							NONE	
N 3953	HICKSVILLE WD	D 7	1953	152	P.S.	WTDR	419	-17 TO	-267	92	18	11-14-52	TURR	MAGOTHY	69
N 3982	A. DAVIS	E 7	1952	20	DOM	WTDR	419	-376 TO	-399	23	6	10-07-52	TURR	LLOYD	
N 4058	CERTIFIED IND	E 7	1952	75	UNSD	DEST	200							NONE	MAGOTHY
N 4095	PLAINVIEW WD	D 8	1954	150	P.S.	WTDR	495	-290 TO	-340	50	18	09-03-54	TURR	MAGOTHY	31
N 4096	PLAINVIEW WD	D 8	1954	150	P.S.	WTDR	499	-294 TO	-344	50	18	08-02-54	TURR	MAGOTHY	37
N 4097	PLAINVIEW WD	D 8	1954	158	P.S.	WTDR	470	-255 TO	-305	50	18	08-04-54	TURR	MAGOTHY	36
N 4133	JERICHO WD	D 7	1954	192	P.S.	WTDR	445	-208 TO	-258	50	18	05-29-54	TURR	MAGOTHY	17
N 4136	OYSTER RAY WD	E 7	1953	18	UNSD	UNSD	310							NONE	PTWAO
N 4137	OYSTER RAY WD	E 7	1953	18	UNSD	UNSD	188	-145 TO	-170	25	12	04-28-53	NONE	PTWCU	
N 4245	JERICHO WD	D 7	1955	222	P.S.	WTDR	571	-303 TO	-343	40	18	11-12-53	TURR	MAGOTHY	30
N 4246	JERICHO WD	D 7	1954	200	UNSD	UNSD	458	-203 TO	-253	50	18	11-05-54	TURR	MAGOTHY	31
N 4376	MARY G. BURKE	E 7	1953	58	DOM	WTDR	367	-298 TO	-308	10	6	12-07-53	TURR	LLOYD	15
N 4400	OYSTER RAY WD	E 8	1954	36	UNSD	TEST	400							NONE	
N 4400	OYSTER RAY WD	E 8	1957	36	P.S.	WTDR	302	-178 TO	-266	88	20	09-04-56	TURR	MAGOTHY	50
N 4431	CERTIFIED IND	D 7	1953	98	UNSD	DEST	30	79 TO	68	11	4	06-00-53	NONE	UPGLAC	11
N 4432	DYCKMAN LAUNDRY	E 6	1955	28	COM	WTDR	352	-304 TO	-320	16	6	04-00-55	TURR	LLOYD	2
N 4440	F. MARMORALE	E 7	1954	16	DOM	WTDR	316	-290 TO	-300	10	6	07-16-54		LLOYD	10
N 4462	NORTH SHORE CC	E 6	1954	69	UNSD	TEST	271							NONE	
N 4462	NORTH SHORE CC	E 6	1954	69	IMR	WTDR	181	-80 TO	-112	32	12	05-25-54	TURR	PTWCU	10
N 4633	MEADOWBROOK CL	D 7		176	UNSD	TEST	308							NONE	
N 4633	MEADOWBROOK CL	D 7	1954	176	IMR	WTDR	216	13 TO	-30	52	16	09-25-54	TURR	MAGOTHY	83
N 4639	NASSAU CC	E 6	1911	123		WTDR	250			10				MAGOTHY	
N 4760	PINE HOLLOW CC	E 7	1954	220	IMR	WTDR	247	5 TO	-27	32	12	09-15-54	TURR	UPGLAC	51
N 4891	PINE HOLLOW CC	E 7	1933	230	UNSD	UNSD	245			10		05-00-33	TURR	UPGLAC	9
N 5058	WM. J. LEVITT	D 7	1955	238	UNSD	UNSD	255	3 TO	-17	20	8	11-17-54	TURR	MAGOTHY	25
N 5071	NASSAU CC	E 6	1954	143	IMR	WTDR	242	-67 TO	-99	32	12	10-26-54	TURR	MAGOTHY	29
N 5086	S. L. LANG	D 7	1955	225	UNSD	DEST	193	36 TO	32	4	4	00-00-55	NONE	MAGOTHY	
N 5152	LOCUST VLY WD	E 6	1956	44	P.S.	WTDR	360	-261 TO	-311	50	18	08-10-56	TURR	PTWAO	11
N 5188	P. SAMRAD	E 7	1955	22	DOM	WTDR	375	-340 TO	-350	10	6		TURR	LLOYD	3
N 5201	JERICHO WD	D 6	1956	48	P.S.	WTDR	509	-386 TO	-456	70	18	06-12-56	TURR	LLOYD	27
N 5250	NASSAU CO DPW	E 6	1944	128	UNSD	DEST	89			2.50		06-23-44	NONE	UPGLAC	
N 5250	NASSAU CO DPW	E 6	1967	123	UNSD	OBS	101			1.25		01-24-67	NONE	UPGLAC	
N 5261	GLEN COVE	E 6	1955	145	UNSD	TEST	302							NONE	
N 5261	GLEN COVE	E 6	1955	145	P.S.	WTDR	235	14 TO	-85	59	18	05-14-55	SURF	PTWCU	43
N 5332	CERTIFIED IND	E 7	1955	73	UNSD	DEST	162	-44 TO	-89	45	12	11-26-55	NONE	UPGLAC	34
N 5335	CERT. REDI MIX	D 7	1955	170	UNSD	DEST	144	47 TO	26	21	6	00-00-55	NONE	MAGOTHY	
N 5450	ENGINEERS CC	D 6	1955	57	IMR	WTDR	80	-1 TO	-23	22	12	06-29-55	TURR	UPGLAC	15
N 5672	BEAVER DAM CLUM	E 7	1955	25	COM	WTDR	121	-76 TO	-96	20	8	12-06-55	TURR	UPGLAC	

104007

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)		TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT DEVEL- TYPE	AQUIFER DEVELOP- ED	SPECIFIC CAPACITY [(GAL/MIN)/FT]
N 5677	KOLLSMAN INST.	D 7	1955	218	UNSD	TEST	429								NONE	
N 5677	KOLLSMAN INST.	D 7	1956	218		WTOR	257	47 TO	-39	60	12	130	06-22-56	TURR	MAGOTHY	44
N 5762	GLEN COVE	E 6	1956	145	UNSD	TEST	310								NONE	
N 5762	GLEN COVE	E 6	1956	145	P.S.	WTOR	281	-76 TO	-135	59	18	81	07-05-56	SUBM	MAGOTHY	58
N 5792	SEA CLIFF WATER	E 6	1956	140	UNSD	TEST	361								NONE	
N 5792	SEA CLIFF WATER	E 6	1957	140	P.S.	WTOR	300	-115 TO	-155	40	20	84.4	11-07-57	TURR	UPGLAC	175
N 5851	ST.UNIV.AT O.W.	D 7	1956	218	DUM	WTOR	177	47 TO	41	6	6	128	08-31-56	SUBM	MAGOTHY	2
N 5901	CERT.REDI-MIX	D 7	1956	179	UNSD	DEST	148	42 TO	31	11	4	90	06-02-56	NONE	MAGOTHY	
N 5994	GLEN COVE HOSP	E 6	1957	130	INST	WTOR	226	-43 TO	-96	36	16	73	09-22-56	TURR	MAGOTHY	43
N 6042	MILL NICK ESTS.	E 7		10	P.S.	WTOR	347	-318 TO	-730	12	8				PTWAO	
N 6076	PLAINVIEW WD	D 8	1956	158	UNSD	TEST	694								NONE	
N 6076	PLAINVIEW WD	D 8	1957	158	P.S.	WTOR	358	-138 TO	-200	62	20	73	02-11-57	TURR	MAGOTHY	41
N 6077	PLAINVIEW WD	D 8	1956	158	UNSD	TEST	692								NONE	
N 6077	PLAINVIEW WD	D 8	1957	158	P.S.	WTOR	665	-240 TO	-702	62	20	75	03-06-57	TURR	MAGOTHY	45
N 6092	JERICHO WD	D 8	1958	241	P.S.	WTOR	637	-320 TO	-790	70	18	184	06-25-57	TURR	MAGOTHY	52
N 6093	JERICHO WD	D 8	1957	259	P.S.	WTOR	612	-287 TO	-747	60	18	171	09-09-57	TURR	MAGOTHY	54
N 6190	HICKSVILLE WD	D 7	1957	177	UNSD	TEST	542								NONE	
N 6190	HICKSVILLE WD	D 7	1958	177	P.S.	WTOR	605	-373 TO	-423	50	20	94	08-22-57	TURR	MAGOTHY	41
N 6191	HICKSVILLE WD	D 7	1957	176	UNSD	TEST	676								NONE	
N 6191	HICKSVILLE WD	D 7	1958	176	P.S.	WTOR	555	-313 TO	-774	61	20	93.5	06-26-57	TURR	MAGOTHY	37
N 6289	PIPING ROCK CL	E 6	1957	162	UNSD	TEST	385								NONE	
N 6289	PIPING ROCK CL	E 6	1957	162	IHR	WTOR	219	40 TO	-57	37	12	71	09-19-57	TURR	UPGLAC	19
N 6294	U.S. GEOL SURV	E 7	1957	93	UNSD	DEST	28				1.25	22.81	06-17-57	TURR	UPGLAC	
N 6294	U.S. GEOL SURV	E 7	1966	93	UNSD		37				1.25				NONE	UPGLAC
N 6416	ZARA ASPHALT CO	E 6	1958	15	UNSD	TEST	295								NONE	
N 6416	ZARA ASPHALT CO	E 6	1954	15	UNSD	UNSD	107	-83 TO	-92	9	6	6.5	06-06-54	TURR	UPGLAC	1
N 6435	LAVISTA	E 7	1958	58	DUM	WTOR	438	-360 TO	-780	15	6	38.5	06-08-58	SURM	LLOYD	
N 6444	BROOKVILLE CC	E 6	1954	170	IHR	WTOR	257	-51 TO	-87	36	12	75	06-30-58	TURR	MAGOTHY	37
N 6531	RIVERSIDE PLAS.	D 7	1954	178	UNSD	DEST	119	64 TO	59	5	6	99	09-25-58	NONE	UPGLAC	8
N 6531	METCO INC	D 7	1966	178	IHR	WTOR	174	17 TO	5	12	6	102	05-05-66	SURM	UPGLAC	10
N 6549	POWERS CHEMCO	E 6	1958	32	IND	RECH	425	-292 TO	-793	60	8	20	08-13-58	NONE	LLOYD	14
N 6579	GLEN COMPONENTS	E 6	1958	57		WTOR	146	-73 TO	-89	16	4				TURR	UPGLAC
N 6580	PLAINVIEW WD	D 8	1958	158	UNSD	TEST	702					75	08-13-58	TURR		
N 6580	PLAINVIEW WD	D 8	1958	158	P.S.	WTOR	601	-365 TO	-438	63	20	75	08-13-58	TURR	MAGOTHY	54
N 6587	ZARA ASPHALT	E 6	1958	15	UNSD	UNSD	58	-25 TO	-41	16	6	7	06-06-58	TURR	UPGLAC	
N 6651	JERICHO WD	D 7	1960	232	P.S.	WTOR	615	-328 TO	-378	50	18	133.7	05-17-60	TURR	MAGOTHY	27
N 6655	METCO INC	D 7	1959	122	UNSD	UNSD	236	-74 TO	-114	40	8	47	04-24-59	NONE	MAGOTHY	15
N 6665	U.S. GEOL SURV	D 6	1959	97	UNSD		29	70 TO	68	2	1.25				NONE	UPGLAC
N 6666	U.S. GEOL SURV	D 6	1959	97	UNSD		12								NONE	UPGLAC
N 6667	U.S. GEOL SURV	D 6	1959	94	UNSD		43	53 TO	51	2	1.25				NONE	UPGLAC

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT TYPE	AQUIFER DEVEL- OPED	SPECIFIC CAPACITY ((GAL/MIN)/FT)	
N 6668	U.S. GEOL SURV	E 6	1959	103	UNSD	OBS	43			1.25				NONE	UPGLAC	
N 6669	U.S. GEOL SURV	E 6	1959	89	UNSD	OBS	44			1.25				NONE	UPGLAC	
N 6670	U.S. GEOL SURV	E 6	1959	81	UNSD	OBS	13			1.25				NONE	UPGLAC	
N 6675	PAR ARNEBERG	E 7	1959	7	DOM	WTDR	460	-448 TO	-453	5				SURM	LLOYD	
N 6708	ZARA ASPHALT CO	E 6	1959	13	UNSD	OBS	50	-33 TO	-37	4	4	5.5	06-00-59	NONE	UPGLAC	
N 6741	CERRO WIRE	D 7	1959	141	IND	WTDR	423	-192 TO	-242	50	18	102	09-04-59	TURR	MAGOTHY	35
N 6768	L.I. STATE PARK	E 7	1914	208	INST	WTDR	175	45 TO	33	12	8			TURR	MAGOTHY	
N 6806	CEDAR BROOK CC	E 6	1960	154	IND	WTDR	323	-133 TO	-163	30	12	86	02-18-60	TURR	MAGOTHY	33
N 6860	GENERAL INST.	D 7	1960	138	UNSD	DEST	94	52 TO	42	10	8	57	04-04-60	NONE	UPGLAC	10
N 6876	U.S. GEOL SURV	E 8	1960	146	UNSD	TEST	113							NONE		
N 6877	U.S. GEOL SURV	E 7	1960	130	UNSD	TEST	133							NONE		
N 6878	U.S. GEOL SURV	E 7	1960	35	UNSD		23	15 TO	12	3	1.25			NONE	UPGLAC	
N 6879	U.S. GEOL SURV	E 7		131	UNSD	OBS	131	2 TO	0	2	1.25			NONE	MAGOTHY	
N 6880	U.S. GEOL SURV	E 7	1960	115	UNSD	TEST	133							NONE		
N 6881	U.S. GEOL SURV	D 6		94	UNSD		75	22 TO	19	3	1.25			NONE	UPGLAC	
N 6882	U.S. GEOL SURV	D 6	1960	140	UNSD		77	66 TO	63	3	1.25			NONE	UPGLAC	
N 6883	U.S. GEOL SURV	D 6	1960	118	UNSD		92	39 TO	36	3	1.25			NONE	UPGLAC	
N 6884	U.S. GEOL SURV	E 7	1960	191	UNSD		108	86 TO	83	3	1.25			NONE	UPGLAC	
N 6885	U.S. GEOL SURV	E 7	1960	165	UNSD		114	54 TO	51	3	1.25			NONE	UPGLAC	
N 6886	U.S. GEOL SURV	E 7	1960	164	UNSD		94	69 TO	66	3	1.25			NONE	UPGLAC	
N 6887	U.S. GEOL SURV	F 8	1960	160	UNSD		90	73 TO	70	3	1.25			NONE	UPGLAC	
N 6888	U.S. GEOL SURV	E 8	1960	84	UNSD		54	33 TO	30	3	1.25			NONE	MAGOTHY	
N 6889	U.S. GEOL SURV	D 8	1960	290	UNSD	TEST	135							NONE		
N 6973	NASSAU CO DPW	D 7	1960	48	UNSD	DEST	34	17 TO	14	3	1.25	8.23	08-02-60	NONE	UPGLAC	
N 7030	JERICHO WD	D 7	1962	158	P.S.	WTDR	531	-322 TO	-372	50	20	75	04-23-62	TURR	MAGOTHY	10
N 7034	WOODCREST CLUR	D 7	1961	219	IND	WTDR	232	18 TO	-13	31	12	145	03-16-61	TURR	UPGLAC	42
N 7045	ST.UNIV.AT O.W.	D 7	1961	241	UNSD	UNSD	151	105 TO	90	15	8	143	05-21-61	TURR	MAGOTHY	
N 7047	L.I. STATE PARK	E 7	1962	223	INST	WTDR	264	11 TO	-41	52	12	169	06-09-61	SURM	MAGOTHY	39
N 7066	MEYER GOLDSTEIN	E 7	1961	9	UNSD	UNSD	89	-65 TO	-80	15	6	2	05-15-61	SURM	PTWCU	7
N 7115	MUTTONTOWN CC	E 7	1961	205	IND	WTDR	274	-29 TO	-69	40	12			TURR	MAGOTHY	
N 7152	U.S. GEOL SURV	E 7	1961	14	UNSD	OBS	370	-346 TO	-356	10	6	6	08-17-61	NONE	LLOYD	
N 7190	U.S. GEOL SURV	E 7	1961	14	UNSD	OBS	240	-223 TO	-226	3	2	8.24	09-07-61	NONE	PTWCU	
N 7191	U.S. GEOL SURV	E 7	1961	14	UNSD	OBS	142	-125 TO	-128	3	2	3.94	09-07-61	NONE	PTWCU	
N 7192	U.S. GEOL SURV	E 7	1961	14	UNSD	OBS	40	-23 TO	-26	3	2	14.31	09-07-61	NONE	UPGLAC	
N 7193	U.S. GEOL SURV	E 7	1961	14	UNSD	UNSD	14	-1 TO	-4	3	1.25	10.88	09-07-61	NONE	UPGLAC	
N 7277	CERTIFIED IND	E 7	1962	77	UNSD	UNSD	235	-122 TO	-157	35	12			NONE	UPGLAC	
N 7419	OYSTER BAY	D 8	1963	243	UNSD	UNSD	325	-57 TO	-82	25	10	173	08-14-63	SURM	MAGOTHY	9
N 7420	AM.PHYSICS INST	D 8	1963	243	COM	WTDR	265	33 TO	18	15	6	211	10-09-63	SURM	MAGOTHY	4
N 7427	PHOTOCIRCUITS	E 6	1963	58	IND	WTDR	161	-62 TO	-103	41	12	3	05-13-63	TURR	UPGLAC	57
N 7439	GREEN COVE	E 6	1963	22		WTDR	212	-182 TO	-188	6	4			SURM	LLOYD	

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMPLETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	AQUIFER TYPE	LIFT DEVEL- OPED	SPECIFIC CAPACITY ((GAL/MIN)/FT)
N 7446	JERICHO WD	D 7	1964	222	P.S.	WTDR	494	-221 TO -271	50	20	146	05-26-64	TURB MAGOTHY		30
N 7450	NASSAU CO DPW	D 6	1975	176	UNSD	ORS	134	47 TO 42	5	4			NONE	MAGOTHY	
N 7478	NASSAU CO DPW	D 7	1963	217	UNSD	ORS	165				131.40	07-18-63	NONE	MAGOTHY	
N 7510	F.F. PASSARELLA	E 7	1964	19	DOM	WTDR	329	-302 TO -310	8	8	12	04-21-64	SUM	LLOYD	2
N 7526	PLAINVIEW WD	D 8	1964	228	P.S.	WTDR	691	-342 TO -460	73	20	140	08-03-64	SUM	MAGOTHY	43
N 7546	NASSAU CO DPW	E 7	1964	11	UNSD	ORS	364	-348 TO -353	5	4			NONE	LLOYD	
N 7547	NASSAU CO DPW	E 6	1966	9	UNSD	TEST	322			6			NONE		
N 7549	OLD WESTBURY	D 6	1965	198	P.S.	WTDR	504	-251 TO -301	50	20	126	06-03-65	TURB	MAGOTHY	22
N 7562	HICKSVILLE WD	D 7	1964	163	P.S.	WTDR	550			20	80	06-01-64	TURB	MAGOTHY	28
N 7570	BAYVILLE	E 7	1964	125	UNSD	TEST	522						NONE		
N 7593	JERICHO WD	E 8	1965	253	P.S.	WTDR	473	-155 TO -215	60	20	205	05-24-65	TURB	MAGOTHY	40
N 7614	POWERS CHEMCO	E 6	1964	32	IND	WTDR	393	-319 TO -360	41	10	32	08-28-64	TURB	LLOYD	4
N 7620	RAYVILLE	E 7	1964	125	P.S.	WTDR	480	-287 TO -355	64	16	113.36	09-09-64	TURB	LLOYD	19
N 7643	RAYVILLE	E 7	1964	125	P.S.	WTDR	214	-34 TO -93	59	20	121.6	09-18-64	TURB	UPGLAC	169
N 7644	J.D. MOONEY	E 7	1964	19	DOM	WTDR	320	-286 TO -301	15	4	13	09-04-64	SUM	LLOYD	5
N 7664	ENGINEERS CC	D 6	1965	51	IRR	WTDR	85	-5 TO -26	21	12			TURB	UPGLAC	22
N 7665	LOCUST VLY WD	E 6	1966	218	P.S.	WTDR	375	-102 TO -152	50	20	172	12-11-65	TURB	UPGLAC	30
N 7672	NASSAU CO DPW	D 7	1964	177	UNSD	ORS	159	20 TO 14	2	2	90.00	11-02-64	NONE	MAGOTHY	
N 7719	BAYVILLE	E 7	1964	20	UNSD	ORS	400	-378 TO -380	2	4			NONE	BERROCK	
N 7745	W.J. LEVITT	E 7	1965	150	DOM	WTDR	215	-40 TO -65	25	16	105	02-24-65	TURB	PTWCU	6
N 7772	JERICHO WD	E 7	1966	258	P.S.	WTDR	568	-245 TO -305	60	20	194	05-19-66	TURB	MAGOTHY	23
N 7773	JERICHO WD	E 7	1966	230	P.S.	WTDR	565	-270 TO -330	60	20	188	05-24-66	TURB	MAGOTHY	30
N 7781	JERICHO WD	D 7	1965	217	P.S.	WTDR	459	-177 TO -237	60	20	140	06-29-65	TURB	MAGOTHY	42
N 7782	ST. PATRICKS	E 6	1965	95	ARCD	WTDR	224	-105 TO -131	26	8	40.2	03-14-65	TURB	MAGOTHY	
N 7830	MILL RIVER CLUB	E 7	1965	118	IRR	WTDR	197	-48 TO -79	31	12	67	05-05-65	TURB	MAGOTHY	33
N 7834	GLEN HEAD CC	E 6	1965	150	IRR	WTDR	202	-21 TO -52	31	12	116	05-25-65	TURB	UPGLAC	27
N 7857	SEA CLIFF WATER	E 6	1966	195	P.S.	WTDR	614	-365 TO -419	54	20	195	05-10-66	SUM	LLOYD	13
N 7858	TAM OSHANER CC	D 7	1966	214	IRR	WTDR	375	-92 TO -142	50	16	140	03-01-66	TURB	MAGOTHY	40
N 8043	JERICHO WD	D 8	1966	222	P.S.	WTDR	688	-293 TO -466	173	20	153	06-10-66	TURB	MAGOTHY	48
N 8048	POWERS CHEMCO	E 6	1966	60		RECH	370	-266 TO -310	44	12			NONE	LLOYD	
N 8123	WINSTON GUEST	E 7	1966	263	OTHR	WTDR	324	-56 TO -63	7	6	215	09-00-66	SUM	MAGOTHY	
N 8183	OYSTER BAY WD	E 7	1966	90	UNSD	TEST	487						NONE		
N 8183	OYSTER BAY WD	E 7	1968	90	P.S.	WTDR	230	-91 TO -140	49	16	54.5	11-17-67	TURB	UPGLAC	30
N 8224	PHOTOCIRUITS	E 6	1970	58	IND	WTDR	155	-46 TO -97	51	12	11.5	01-29-70	TURB	UPGLAC	254
N 8249	HICKSVILLE WD	D 7	1967	163	P.S.	WTDR	495	-237 TO -327	90	20	89	02-25-67	SUM	MAGOTHY	71
N 8259	NASSAU CO DPW	E 6	1967	70	UNSD	ORS	42	30 TO 28	2	1.25	35.50	01-17-67	NONE	UPGLAC	
N 8326	GLEN COVE	E 6	1967	53	UNSD	TEST	507						NONE		
N 8326	GLEN COVE	E 6	1965	53	P.S.	WTDR	164	-67 TO -112	45	20	6.5	07-26-67	SUM	UPGLAC	33
N 8327	GLEN COVE	E 6	1967	53	UNSD	TEST	362						NONE		
N 8327	GLEN COVE	E 6	1965	53	P.S.	WTDR	164	-65 TO -115	50	20	13.5	09-06-67	SUM	UPGLAC	41

CLOSEST WELL

104010

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TESTS IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT TYPE	AQUIFER DEVEL- OPED	SPECIFIC CAPACITY (GAL/MIN)/FT)
N 4355	JERICHO WD	D 7	1969	258	P.S.	WTDR	595	-272 TO -332	60	20	194	04-25-69	TURR	MAGOTHY	42
N 4394	GLEN COVE HOSP.	E 6	1969	13A		RECH	580	-379 TO -442	63	8				NONE	LLOYD
N 4426	WILL NECK ESTS.	E 7	1968	10	P.S.	WTDR	360	-335 TO -350	15	8	FLOWING	05-20-68	SURM	PTWAO	3
N 4430	NASSAU CO DPW	E 7	1968	190	UNSD	OBS	145	50 TO 45	5	4	133.17	04-10-68	NONE	MAGOTHY	
N 4432	C.W.POST COLL.	D 6	1968	165	IRR	WTDR	250	-55 TO -85	30	10	107	05-07-68	SURM	MAGOTHY	26
N 4492	MRS.G.PELLICORO	D 7	1964	178	DOM	WTDR	150	34 TO 29	5	6				SURM	JPGLAC
N 4493	J.GIANETTO	D 7	1968	175	DOM	WTDR	255	-75 TO -80	5	6				SURM	MAGOTHY
N 4542	MUTTONTOWN CC	E 7	1969	175	IRR	WTDR	335	-119 TO -160	41	12	116	04-30-69	SURM	UPGLAC	24
N 4583	NASSAU CO DPW	D 8	1969	194	UNSD		177	22 TO 17	5	4				NONE	MAGOTHY
N 4597	G.VAN AKEN	E 8	1969	100	DOM	WTDR	228	-116 TO -126	10	6				SURM	UPGLAC
N 4606	NASSAU CO DPW	D 8	1969	197	UNSD		80	121 TO 117	4	2	71.60	08-20-69	NONE	UPGLAC	
N 4610	NASSAU CO DPW	E 6	1969	9	UNSD	OBS	22	-12 TO -14	2	1.25	8.27	08-06-69	NONE	UPGLAC	
N 4642	GLEN OAKES CC	D 7	1970	243	IRR	WTDR	400	-126 TO -157	31	12	185	05-14-70	SURM	MAGOTHY	27
N 4658	OLD WESTBURY	D 7	1970	325	UNSD	TEST	670							NONE	
N 4658	OLD WESTBURY	D 7	1972	320	P.S.	WTDR	615	-230 TO -290	60	20	248.4	03-30-72	TURR	MAGOTHY	49
N 4681	FOX RUN CC	E 7	1970	200	IRR	WTDR	370	-117 TO -169	52	12	133	09-12-70		MAGOTHY	32
N 4690	FABRIC LEATHER	E 6	1970	25		WTDR	347	-292 TO -317	25	8				LLOYD	
N 4709	FABRIC LEATHER	E 6	1970	22	IND	RECH	312	-218 TO -290	72	6	8	10-07-70	NONE	LLOYD	
N 4713	JERICHO WD	D 6	1970	168	UNSD	TEST	412							NONE	
N 4713	JERICHO WD	D 6	1972	168	P.S.	WTDR	377	-144 TO -204	60	20	113.1	03-23-72	TURR	MAGOTHY	51
N 4716	NASSAU CO DPW	E 6	1970	47	UNSD	OBS	25			1.25	7.60	09-29-70	NONE	UPGLAC	
N 4776	RAYVILLE	E 7	1972	9A	P.S.	WTDR	459	-301 TO -361	60	20	106.3	06-24-71	TURR	LLOYD	29
N 4805	G.E.RODUIT	E 7	1971	63	DOM	WTDR	457	-384 TO -394	10	5	53.5	09-10-71	SURM	LLOYD	6
N 4807	CERTIFIED IND	D 7	1971	11A	IND	WTDR	140	9 TO -22	31	8	17	10-25-71	TURR	MAGOTHY	9
N 4880	METCO INC	D 7	1972	122	IND	WTDR	247	-99 TO -125	26	8	51	10-03-72	SURM	MAGOTHY	19
N 4887	SLATER ELECTRIC	E 6	1972	65	IND	WTDR	130	-40 TO -65	25	8	12	10-17-72	SURM	UPGLAC	6
N 4888	NASSAU CO DPW	D 7	1972	174	UNSD	OBS	111	68 TO 63	5	4	91.38	10-25-72	NONE	UPGLAC	
N 4898	L.I.LIGHTING CO	D 6	1973	18	UNSD	TEST	223							NONE	
N 4928	NASSAU CO DPW	E 7	1973	10	UNSD	OBS	31	-18 TO -21	3	1.25	8.06	01-18-73	NONE	UPGLAC	
N 4937	L.I.LIGHTING CO	D 6	1973	18	COM	WTDR	164	-103 TO -143	40	12	3	10-10-73	TURR	UPGLAC	24
N 4962	MRS.S.PRATT	E 6	1973	6	DOM	WTDR	420	-365 TO -414	41	4				LLOYD	
N 4995	THURSTON SMITH	E 7	1974	41	DOM	WTDR	405	-354 TO -364	10	6				SURM	LLOYD
N 5023	PINE MOLLOW CC	E 7	1974	219	IRR	WTDR	247	2 TO -28	30	12	175	07-09-74	TURR	UPGLAC	50
N 5059	NASSAU CO DPW	D 7	1974	228	UNSD	OBS	175	58 TO 53	5	4	117.90	10-31-74	NONE	MAGOTHY	
N 5066	GLEN COVE	E 6	1975	143	UNSD	TEST	651							NONE	
N 5066	GLEN COVE	E 6	1975	143	UNSD	TEST	460	-277 TO -317	40					LLOYD	
N 5066	GLEN COVE	E 6	1975	143	UNSD	OBS	270	-77 TO -127	50	12	92	09-00-75		MAGOTHY	
N 5068	NATL. PARK SERV	E 8		154		WTDR	325			6				PTWCU	
N 5076	NATL. PARK SERV	E 8	1975	154		WTDR	199	-35 TO -45	10	8				PTWCU	
N 5087	NASSAU CO DPW	E 7	1975	157	UNSD	OBS	111	51 TO 46	5	4	93.60	08-08-75	NONE	UPGLAC	

104011

TABLE 6.--WELL COMPLETION DATA ON SELECTED WELLS AND TEST HOLES IN NORTHERN PART OF TOWN OF OYSTER BAY, NASSAU COUNTY, NEW YORK.

WELL NUMBER	OWNER OR WELL USER	MAP COORD.	YEAR COMP- LETED	ALTITUDE OF LSD (FT ABOVE SEA LEVEL)	USE OF WATER	USE OF WELL	DEPTH OF WELL (FT)	SCREEN SETTING (FT ABOVE OR BELOW (-) SEA LEVEL)	TOTAL SCREEN LENGTH (FT)	DIAM OF WELL (IN)	WATER LEVEL (FT BELOW LSD)	DATE OF MEAS. (M-D-Y)	LIFT DEVEL- TYPE OPED	AQUIFER	SPECIFIC CAPACITY [(GAL/MIN)/FT]
N 9089	NASSAU CO DPW	D 8	1975	173	UNSD	OBS	178	0 TO	-5	5	4	93.20 11-19-75	NONE	MAGOTHY	
N 9100	NASSAU CO DPW	E 6	1976	54	UNSD	OBS	70	-11 TO	-16	5	4	13.85 02-27-76	NONE	PTWCU	
N 9115	NASSAU CO DPW	E 6	1976	145	UNSD	OBS	110	40 TO	35	5	4		NONE	MAGOTHY	
N 9117	NASSAU CO DPW	E 6	1976	112	UNSD	OBS	73	44 TO	39	5	4	40.73 04-05-76	NONE	MAGOTHY	
N 9127	NASSAU CO DPW	E 7	1976	10	UNSD	OBS	41	-26 TO	-31	5	4	6.32 07-09-76	NONE	JPGLAC	
N 9152	NASSAU CO DPW	E 8	1976	40	UNSD	OBS	58	-13 TO	-18	5	4		NONE	JPGLAC	
N 9154	NASSAU CO DPW	E 7	1976	34	UNSD	OBS	66	-27 TO	-32	5	4		NONE	PTWCU	
N 9170	REG.PLAN.BOARD	D 7	1977	184	UNSD	TEST	553						NONE		
N 9170	REG.PLAN.BOARD	D 7	1977	184	UNSD	OBS	510	-321 TO	-326	5	1.25	95.5 01-00-77	NONE	MAGOTHY	
N 9189	NASSAU CO CPW	E 7	1977	59	UNSD	OBS	42	22 TO	17	5	4	13.05 03-02-77	NONE	JPGLAC	
N 9210	GLEN COVE	E 6	1979	142	P.S.	WTDR	275	-67 TO	-128	61	20	99.2 08-19-77		MAGOTHY	
N 9211	GLEN COVE	E 6	1979	142	P.S.	WTDR	269	-60 TO	-122	62	20		TURR	MAGOTHY	34
N 9259	HENRY R. STERN	E 7	1977	58	INR	UNSD	5 10			3 1	0	55.5 09-02-77	SURM	JPGLAC	15
N 9276	D.MOLTERRSCH	E 7	1978	10	UNSD	TEST	321						NONE		
N 9300	NASSAU CO WTR	E 7		45	UNSD	DEST							NONE	JPGLAC	
N 9301	NASSAU CO WTR	E 7		45	UNSD	DEST							NONE	JPGLAC	
N 9302	NASSAU CO WTR	E 7		45	UNSD	DEST							NONE	JPGLAC	
N 9303	NASSAU CO WTR	E 7		45	UNSD	DEST							NONE	JPGLAC	
N 9314	NASSAU CO DPW	E 7	1977	32	UNSD	OBS	54	-17 TO	-22	5	4		NONE	PTWCU	
N 9315	NASSAU CO DPW	E 6	1977	9	UNSD	OBS	41	-27 TO	-32	5	4	3.40 05-04-77	NONE	JPGLAC	
N 9316	NASSAU CO DPW	E 7	1977	25	UNSD	OBS	58	-28 TO	-33	5	4	21.36 07-13-77	NONE	JPGLAC	
N 9317	NASSAU CO DPW	D 7	1977	218	UNSD	OBS	194	29 TO	24	5	4		NONE	MAGOTHY	
N 9334	GLEN COVE	E 6	1978	143	UNSD	TEST	631						NONE		
N 9334	GLEN COVE	E 6	1978	143	UNSD	TEST	603	-417 TO	-460	43			TURR	LLOYD	
N 9334	GLEN COVE	E 6		143	P.S.	WTDR								MAGOTHY	
N 9353	NASSAU CO DPW	D 7	1978	143	UNSD	OBS	101	47 TO	42	5	4	57.82 05-11-78	NONE	MAGOTHY	
N 9455	REG.PLAN.BOARD	D 7	1977	184	UNSD	OBS	195	-6 TO	-11	5	1.25	95.5 01-00-77	NONE	JPGLAC	
N 9456	REG.PLAN.BOARD	D 7	1977	184	UNSD	OBS	361	-172 TO	-177	5	1.25	95.5 01-00-77	NONE	MAGOTHY	
N 9463	HICKSVILLE WD	D 7	1979	141	P.S.	WTDR	638	-414 TO	-497	70	20			MAGOTHY	14
N 9464	MARVIN SCHUR	E 7	1979	22	DOM	WTDR	330	-298 TO	-308	10	4	20 03-00-79	SURM	LLOYD	
N 9478	NASSAU CO DPW	E 6	1978	9	UNSD	OBS	24	-10 TO	-15	5	2	3.47 11-13-78	NONE	JPGLAC	
N 9488	HICKSVILLE WD	D 7	1979	161	UNSD	TEST	638						NONE		
N 9488	HICKSVILLE WD	D 7	1979	161	P.S.	WTDR	583			60	20			MAGOTHY	21
N 9489	S.L.LANG	D 7	1979	225	DOM	WTDR	198	32 TO	27	5	6	150 04-00-79	SURM	MAGOTHY	
N 9520	OYSTER BAY WD	E 7	1979	90	UNSD	TEST	556						NONE		
N 9520	OYSTER BAY WD	E 7		90	P.S.	WTDR		-361 TO	-422	61				PTWAO	
N 9593	H.O.KOHLER	E 7	1979	5	DOM	WTDR	370	-353 TO	-365	12	6			LLOYD	
N 9595	F.H.GILLMORE	E 7	1980	20	DOM	WTDR	467	-416 TO	-447	31	6	43 09-15-80	CENT	LLOYD	
N 9606	MICHAEL HURLEY	E 8		121	UNSD	TEST	203						NONE		
N 9606	MICHAEL HURLEY	E 8	1980	121	DOM	WTDR	134	-8 TO	-13	5	4	106 12-00-79	SURM	JPGLAC	

PLATE 1A. LOCATIONS OF

SELECTED WELLS AND TEST HOLES AND OF HYDROGEOLOGIC SECTIONS






PLATE 2A. ALTITUDE AND CONFIGURATION OF BEDROCK SURFACE



- -450 — LINE OF EQUAL BEDROCK-SURFACE ALTITUDE--Dashed where inferred. Contour interval 50 feet. Datum is NGVD of 1929.
- -462 WELL-DATA POINT--Number is aquifer-surface altitude, in feet below (-) NGVD of 1929.
- A — ○ — A LINE OF HYDROGEOLOGIC SECTION--Open circle is control point. (Sections are shown on plate 1B).


PLATE 2B. ALTITUDE AND CONFIGURATION OF THE LLOYD AQUIFER





104015

PLATE 6A. WATER-TABLE CONFIGURATION IN 1980

104016



104017



REFERENCE NO. 13

104018

WELLS WITHIN 3 MILES OF LI TUNGSTEN, GLEN COVE, NY

UN = Unused, P.S. = Public Supply, IND = Independent, COM = Commercial, IRR = Irrigation,
UNK = Unknown, AC = Air Conditioning

<u>Well No.</u>	<u>Use</u>	<u>Contaminated</u>
109	UN	
110	UN	
112	UN	
114	IRR	
115	UN	
116	UN	
117	UN	
118	P.S.	
119	P.S.	
120	UN	
121	UN	
121A	IRR	
660	IND	
661	UN	
801-818	UN	
834	UN	
835	P.S.	
842	UN	
901	P.S.	
902	P.S.	
903	P.S.	
904	UN	
905-909	P.S.	
1037	P.S.	
1149-1153	UN	
1171-1174	UN	
1327	P.S.	
1595	P.S.	
1651	P.S.	
1917	IND	
2027	UN	
2060	UN	
2087	IND	
2316	IND	X
2616	IRR	
3310	IND	
3466	P.S.	X
3892	UN	X
4432	COM	
4440	DOM	
4462	UN	
4639	UNK	
5071	IRR	
5201	P.S.	
5250	UN	
5261	UN	X

<u>Well No.</u>	<u>Use</u>	<u>Contaminated</u>
5450	IRR	
5762	UN	
5792	P.S.	
6289	UN	
6289	IRR	
6416	UN	
6444	IRR	
6549	IND	
6579	UNK	X
6587	UN	
6665	UN	
6668-70	UN	
6708	UN	
6806	IRR	
6881	UN	
6883	UN	
6973	UN	
7427	IND	X
7439	UNK	
7614	IND	
7664	IRR	
7782	AC	
7834	IRR	
7857	P.S.	
8048	UNK	
8224	IND	
8259	UN	
8326	P.S.	X
8327	P.S.	X
8394	UNK	
8690	UNK	
8709	IND	
8716	UN	
8887	IND	X
8898	UN	
8973	COM	
9066	UN	
9100	UN	
9115	UN	
9117	UN	
9210	P.S.	
9211	P.S.	
9334	P.S.	

REFERENCE NO. 14

104021

Uncontrolled Hazardous Waste Site Ranking System

A Users Manual (HW-10)

Originally Published in
the July 16, 1982, *Federal Register*

United States
Environmental Protection
Agency

1984

104022

PERMEABILITY

TABLE 2
PERMEABILITY OF GEOLOGIC MATERIALS*


Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0
Silt, loess, silty clays, silty loams, clay loams; less permeable limestone, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestone, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

*Derived from:

Davis, S. W., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979


MEAN ANNUAL LAKE EVAPORATION (In Inches)



Based on period 1946-55


104024

NORMAL ANNUAL TOTAL PRECIPITATION (Inches)



104025

1 YEAR 24-HOUR RAINFALL (inches)



104026

REFERENCE NO. 15

104027

NUS CORPORATION

TELECON NOTE

CONTROL NO:

02-2902-06

DATE:

5/29/89

TIME:

0940

DISTRIBUTION:

Denton Avenue Landfill

BETWEEN:

Don Myott, P.E.

OF: NCDOH, Bureau of
Public Water Supply

PHONE:

(516) 535-2201

AND:

Brian Dietz, NUS Corp.

(NUS)

DISCUSSION:

call concerning the "on-site" monitoring wells and groundwater usage within 3-miles of the site:

Mr Myott informed me of the following:

* the DA monitoring wells are located on county property (outside of the landfill) and are owned by NCDOH. The wells have 4" (diameter) casings (PVC) with screens. They are not equipped with pumps and NCDOH sampled them with a 4" submersible pump. There are no locks on the wells but the proper wrench is needed to unscrew the caps. The wells can be sampled at any time but NCDOH should be contacted ahead of time (2-3 days prior). The wells were last sampled in Nov/Dec 1982. The analyses of these samples are presented in the ^{EA} Phase I Report that is located in the "Denton Ave Landfill" site file).

* the public supply wells ^{BD are the major source} supply the drinking water for the people within ^{3 miles of the site} the site.

* The number of private wells within 3 miles of the site is very small. The site is near the moraine and installing private wells can be very expensive. There may be some private industrial wells within 3 miles of the site; however, all of the drinking water is supplied by public supply wells ^{BD}

* the "on-site" recharge basin recharges the upper glacial aquifer

* two supply wells located immediately east of the site are "restricted use" due to the presence of organics. They may not be available for

use because it is not as economical to treat them as the other wells.

Mr. Myott will be sending.

Copies of Hagstrom maps that pinpoint the public supply wells within 3 miles of the site, as well as information regarding the districts and number of people served by each. He will also try to send a copy of a report and merged map (generated by an NCDOH consultant in 1986) that pinpoints all of the public supply, private supply, and industrial wells within Nassau County.

Brian Dietz
3/29/89

Site	⊕	NOTE
Lat.		
(Town or County)		

REFERENCE NO. 16











104030

for decisions on the use of specific tracts.




104032


LEGEND

-  IPSWICH-UDIPSAMMENTS: Dominantly nearly level, very poorly drained, organic soils and nearly level, moderately well drained to excessively drained, coarse-textured soils; on tidal flats
-  MONTAUK-ENFIELD: Dominantly nearly level to strongly sloping, well drained, medium-textured and moderately coarse textured soils; on knolls and hills
-  RIVERHEAD-ENFIELD-URBAN LAND: Dominantly nearly level to strongly sloping, well drained, moderately coarse textured and medium-textured soils and Urban land; on low hills and ridges
-  RIVERHEAD-PLYMOUTH: Dominantly moderately steep or steep, well drained and excessively drained, moderately coarse textured and coarse-textured soils; on hillsides
-  UDIPSAMMENTS-BEACHES-URBAN LAND: Dominantly nearly level or gently sloping, excessively drained to moderately well drained, coarse-textured soils, Beaches, and Urban land; on barrier beaches
-  URBAN LAND: Dominantly nearly level or gently sloping areas that are covered by buildings, roads, sidewalks, and parking lots; on plains and low hills
-  URBAN LAND-HEMPSTEAD: Dominantly Urban land and nearly level, well drained, medium-textured soils; on plains
-  URBAN LAND-MONTAUK-RIVERHEAD: Dominantly Urban land and nearly level to strongly sloping, well drained, medium-textured and moderately coarse textured soils; on low hills
-  URBAN LAND-RIVERHEAD: Dominantly Urban land and nearly level, well drained, moderately coarse textured soils; on plains
-  URBAN LAND-UDIPSAMMENTS-SUDBURY: Dominantly Urban land and nearly level, excessively drained to moderately well drained, coarse-textured and moderately coarse textured soils; on plains

COMPILED 1985

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
CORNELL UNIVERSITY AGRICULTURAL EXPERIMENT STATION
GENERAL SOIL MAP
NASSAU COUNTY, NEW YORK





REFERENCE NO. 17

104034

GRAPHICAL EXPOSURE MODELING SYSTEM

(GEMS)

USER'S GUIDE

VOLUME 2. MODELING

Prepared for:

U.S. ENVIRONMENTAL PROTECTION AGENCY
OFFICE OF PESTICIDES AND TOXIC SUBSTANCES
EXPOSURE EVALUATION DIVISION
Task No. 3-2
Contract No. 68023970
Project Officer: Russell Kinerson
Task Manager: Loren Hall

Prepared by:

GENERAL SCIENCES CORPORATION
8401 Corporate Drive
Landover, Maryland 20785

Submitted: December 1, 1986

GEMS> I

Li Tungsten

LATITUDE 40:51:42 LONGITUDE 73:38:17 1980 POPULATION

KM	0.00-.400	.400-.810	.810-1.60	1.60-3.20	3.20-4.80	4.80-6.40	SECTOR TOTALS
S 1	731	3631	5561	25505	12014	20416	67858
RING	731	3631	5561	25505	12014	20416	67858
TOTALS							

GEMS> I

Li Tungsten

LATITUDE 40:51:42 LONGITUDE 73:38:17 1980 HOUSING

KM	0.00-.400	.400-.810	.810-1.60	1.60-3.20	3.20-4.80	4.80-6.40	SECTOR TOTALS
1	242	1287	2079	8472	4040	7079	23199
RING	242	1287	2079	8472	4040	7079	23199
TOTALS							

Distance (miles)

Population

Houses

0-1/4	731	242
0-1/2	4362	1529
0-1	9923	3608
0-2	35428	12080
0-3	47442	16120
0-4	67858	23199

REFERENCE NO. 18

104037

CONTROL NO:

DATE:

8/7/89

TIME:

16:40

DISTRIBUTION:

TO FILE- LI TUNGSTEN

07-8907-78

BETWEEN:

JIM GILMORE

OF:

NY DEC

PHONE:

(516) 751-7900

AND:

STEVE OKULEWICZ, NUS CORP. EDISON

DISCUSSION:

ASKED MR. GILMORE ABOUT STATE WATER QUALITY CLASSIFICATION OF HEMPSTEAD HARBOR AND GLEN CUE CREEK. HE INFORMED ME THAT HEMPSTEAD HARBOR NORTH OF MAR MEAD IS CLASSIFIED AS SA - SUITABLE FOR SHELL FISHING FOR MARKET PURPOSES AND PRIMARY-SECONDARY CONTACT RECREATION. PRIMARY CONTACT RECREATION MEANS SWIMMING, SECONDARY CONTACT RECREATION MEANS FISHING. THE CLASSIFICATION FOR GLEN CUE CREEK FROM THE MOUTH TO PRATT'S POND IS CLASSIFIED AS CLASS I - SECONDARY CONTACT RECREATION EXCEPT FOR PRIMARY CONTACT RECREATION AND SHELL FISHING FOR MARKET PURPOSES.

ALSO, TO OBTAIN A COPY OF THE WATER QUALITY

ACTION ITEMS:

REGULATIONS FOR SURFACE AND GROUNDWATER TO CONTACT: PETER BLACK - 518-457-3495, ASK FOR TITLE 6, CHAPTER 10, PART 700-705

REFERENCE NO. 19

104039

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

8/4/89

TIME:

11:30

DISTRIBUTION:

File - LI TUNESTEN
CJ-8907-78

BETWEEN:

DEBRA ROTHBERG

OF: JONES, DAY, REVIS
& ROGUE

PHONE:

(212) 376-3939

AND:

STEVE CHULEWICZ NUS EMISON

DISCUSSION:

CALLED HER ABOUT OWNERSHIP OF LI TUNESTEN.
SHE INFORMED ME THAT THE OWNERS ARE
GLEN COVE DEVELOPMENT COMPANY - 34 WADSWORTH
PLACE, BALTIMORE MD. MY CORRESPONDENCE SHOULD
BE MAILED TO DEBRA ROTHBERG - 599 LEXINGTON
AVE, NYC 10072.

ACTION ITEMS:

REFERENCE NO. 20

104041

CONTROL NO:

DATE:

8/8/89

TIME:

9:30

DISTRIBUTION:

TO FILE - LI TUNGSTEN

02-8907-78

BETWEEN:

JIM GILMORE

OF:

NY DEC

PHONE:

(516) 751-7900

AND:

STEVE OKULEWICZ, NUS CORP, EDISON N.J.

DISCUSSION:

I ASKED MR. GILMORE IF ANY WETLANDS EXISTED WITHIN 7 MILES OF THE SITE THAT WERE GREATER THAN 5 ACRES IN AREA. HE SAID WETLANDS EXISTED IN THE GARVIES POINT PRESERVE BUT WERE NOT 5 ACRES IN AREA, THEY ARE SMALLER. I ALSO ASKED ABOUT PERMANENT ENDANGERED SPECIES IN THE AREA.

HE TOLD ME THAT NO OFFICIAL ANNOUNCEMENT HAS BEEN MADE BUT ARE CONSIDERING THE PORCUPINE FALCON TO BE LISTED. HE IS NOT SURE IF NESTING AREAS HAVE BEEN FOUND WITHIN 7 MILES OF LI TUNGSTEN.

ACTION ITEMS:

REFERENCE NO. 21

104043

SUNY, Bldg. 40, Stony Brook, NY 11794-3070

September 28, 1987

Robert J. Mangan, P.E.
Director of Public Works
City Hall
Glen Cove, NY 11542

Dear Mr. Mangan:


Some of the results are enclosed from the Li Tungsten site. These are the lined and unlined pond water tests, which we took on August 12, 1967.

The other results will follow soon. There was no heavy metal contamination found as shown here.

Sincerely,

Agnes Gara
Asst. Sanitary Engineer.

AG:cp
Enclosures



8-6-87

L. Tunstun Site Glen Cove

samples collected by J. Hofmann / Agnes Gara

- 400 SS-1 soil sample, grab, collected near discolored soil and dead vegetation
- 410 WS-1 water sample, grab, collected at south-west corner of lined pond
- 420 SLS-1 sludge sample, grab, collected south side of lined pond, just below surface of water-sludge interface
- 430 WS-2 Water sample, grab, collected at south side of unlined pond

NEW YORK STATE DEPARTMENT OF HEALTH
 ADAMS WORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: F71006657 SAMPLE RECEIVED: 87/08/12/11 CHARGE: 4.89
 PROGRAM: 6301: DIV. SOLID & HAZARDOUS WASTE - DEC REGION 1
 SOURCE ID: DRAINAGE BASIN: 17 GAZETTEER CODE: 2901
 POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: LJ-TUNGSTEN GARVIES PT RD GLEN COVE
 DESCRIPTION: WS-2 SOUTH SIDE OF UNLINED POND
 REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
 TEST PATTERN: 10-159: COMPLETE METAL SCAN - TOTAL RECOVERABLE
 SAMPLE TYPE: 340: INDUSTRIAL WASTE, UNCHLORINATED
 TIME OF SAMPLING: 87/08/06 14:27 DATE PRINTED: 87/09/22

ANALYSIS: ICP-6 ICP GROUPING 6 - COMPLETE SCAN, TOTAL RECOVERABLE

PARAMETER	RESULT
MERCURY	< 0.2 MCG/L
ARSENIC, TOTAL RECOVERABLE	34. MCG/L
SELENIUM, TOTAL RECOVERABLE	< 5.0 MCG/L
BERYLLIUM, TOTAL RECOVERABLE	< 1. MCG/L
SILVER, TOTAL RECOVERABLE	< 10. MCG/L
BARIUM, TOTAL RECOVERABLE	240. MCG/L
CADMIUM, TOTAL RECOVERABLE	< 5. MCG/L
COBALT, TOTAL RECOVERABLE	600. MCG/L
CHROMIUM, TOTAL RECOVERABLE	20. MCG/L
COPPER, TOTAL RECOVERABLE	170. MCG/L
IRON, TOTAL RECOVERABLE	1690. MCG/L
MANGANESE, TOTAL RECOVERABLE	400. MCG/L
NICKEL, TOTAL RECOVERABLE	90. MCG/L
STRONTIUM, TOTAL RECOVERABLE	3670 MCG/L
TITANIUM, TOTAL RECOVERABLE	< 5. MCG/L
VANADIUM, TOTAL RECOVERABLE	10. MCG/L
ZINC, TOTAL RECOVERABLE	140. MG/L
LEAD, TOTAL RECOVERABLE	430. MCG/L
ANTIMONY, TOTAL RECOVERABLE	< 50. MCG/L
TIN, TOTAL RECOVERABLE	< 50. MCG/L
THALLIUM, TOTAL RECOVERABLE	< 20. MCG/L
ALUMINUM, TOTAL RECOVERABLE	450. MCG/L

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

PARAMETER	RESULT
MOLYBDENUM, TOTAL RECOVERABLE	1.7 MG/L
TUNGSTEN, TOTAL RECOVERABLE	< 50. MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(1), RO(3), LPHE(1), FED(), INFO-P(), INFO-L()

N.Y.S. DEPT. OF ENVIRONMENTAL CONSERVATION
 REGION I HEADQUARTERS
 BUILDING 40, STATE UNIVERSITY OF N.Y.
 STONY BROOK, N.Y. 11790

SUBMITTED BY: HOFMANN

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 871006658 SAMPLE RECEIVED: 87/06/12/11 CHARGE: 4.89
 PROGRAM: 6301: DIV. SOLID & HAZARDOUS WASTE - DEC REGION 1
 SOURCE ID: DRAINAGE BASIN: 17 GAZETTEER CODE: 2901
 POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: LT TUNGSTEN GARVIES PT RD GLEN COVE
 DESCRIPTION: WS-1 SOUTHWEST CORNER LINED POND
 REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
 TEST PATTERN: 10-156: COMPLETE METAL SCAN - TOTAL RECOVERABLE
 SAMPLE TYPE: 340: INDUSTRIAL WASTE, UNCHLORINATED
 TIME OF SAMPLING: 87/08/06 14:10 DATE PRINTED: 87/09/22

ANALYSIS: ICP-6 ICP GROUPING 6 - COMPLETE SCAN, TOTAL RECOVERABLE

PARAMETER	RESULT
MERCURY	0.3 MCG/L
ARSENIC, TOTAL RECOVERABLE	51. MCG/L
SELENIUM, TOTAL RECOVERABLE	< 5.0 MCG/L
BERYLLIUM, TOTAL RECOVERABLE	< 1. MCG/L
SILVER, TOTAL RECOVERABLE	14. MCG/L
BARIUM, TOTAL RECOVERABLE	76. MCG/L
CADMIUM, TOTAL RECOVERABLE	< 5. MCG/L
COBALT, TOTAL RECOVERABLE	605. MCG/L
CHROMIUM, TOTAL RECOVERABLE	6. MCG/L
COPPER, TOTAL RECOVERABLE	850. MCG/L
IRON, TOTAL RECOVERABLE	3200. MCG/L
MANGANESE, TOTAL RECOVERABLE	832. MCG/L
NICKEL, TOTAL RECOVERABLE	201. MCG/L
STRONTIUM, TOTAL RECOVERABLE	115. MCG/L
TITANIUM, TOTAL RECOVERABLE	49. MCG/L
VANADIUM, TOTAL RECOVERABLE	7. MCG/L
ZINC, TOTAL RECOVERABLE	246. MG/L
LEAD, TOTAL RECOVERABLE	60. MCG/L
ANTIMONY, TOTAL RECOVERABLE	105. MCG/L
TIN, TOTAL RECOVERABLE	< 50. MCG/L
THALLIUM, TOTAL RECOVERABLE	< 20. MCG/L
ALUMINUM, TOTAL RECOVERABLE	1070. MCG/L

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

PARAMETER	RESULT
MOLYBDENUM, TOTAL RECOVERABLE	1.5 MG/L
TUNGSTEN, TOTAL RECOVERABLE	< 50. MG/L

**** END OF REPORT ****

COPIES SENT TO: CO(1), RO(3), LPHE(1), FED(), INFO-P(), INFO-L()

N.Y.S. DEPT. OF ENVIRONMENTAL CONSERVATION
 REGION-1 HEADQUARTERS
 BUILDING 40, STATE UNIVERSITY OF N.Y.
 STONY BROOK, N.Y. 11790

SUBMITTED BY: HOFMANN

NEW YORK STATE DEPARTMENT OF HEALTH
ADSWORTH CENTER FOR LABORATORIES AND RESEARCH

SE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 871009130 SAMPLE RECEIVED: 87/08/12/11 CHARGE: 22.57
PROGRAM: 6301:DTV. SOLID & HAZARDOUS WASTE - DEC REGION 1
SOURCE ID: DRAINAGE BASIN: 17 GAZETTEFR CODE: 2901
POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
LATITUDE: LONGITUDE: Z DIRECTION:
LOCATION: LT TUNGSTEN GARVIES PT RD GLEN COVE
DESCRIPTION: SLS-1 SOUTH SIDE OF LINED PD MIDDLE
REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
TEST PATTERN: 10-035: METALS IN SOLID MATERIAL
SAMPLE TYPE: 620: WET SLUDGE
TIME OF SAMPLING: 87/08/06 14:20 DATE PRINTED: 87/09/24

DATA REPORTED WITH UNITS OF MG/L OR MCG/L ARE ANALYTICAL
VALUES OBTAINED ON THE EP-TOT LEACHATE.

PARAMETER	RESULT
SOLIDS, DRY	23. PERCENT
ARSENIC IN DRY SOLIDS	1200. MCG/G
MERCURY IN DRY SOLIDS	1.4 MCG/G
SELENIUM IN DRY SOLIDS	0.5 MCG/G
BERYLLIUM IN DRY SOLIDS	110. MCG/G
SILVER IN DRY SOLIDS	< 8. MCG/G
BARIUM IN DRY SOLIDS	364. MCG/G
CADMIUM IN DRY SOLIDS	17.4 MCG/G
COBALT IN DRY SOLIDS	3240. MCG/G
CHROMIUM IN DRY SOLIDS	218. MCG/L
COPPER IN DRY SOLIDS	3820. MCG/G
MANGANESE IN DRY SOLIDS	8400. MCG/G
NICKEL IN DRY SOLIDS	896. MCG/G
STRONTIUM IN DRY SOLIDS	73. MCG/G
TITANIUM IN DRY SOLIDS	186. MCG/G
VANADIUM IN DRY SOLIDS	340. MCG/G
ZINC IN DRY SOLIDS	3280. MCG/G
MOLYBDENUM IN DRY SOLIDS	5960. MCG/L
ANTIMONY IN DRY SOLIDS	400. MCG/G
TIN IN DRY SOLIDS	800. MCG/G
THALLIUM IN DRY SOLIDS	< 16. MCG/L
ALUMINUM IN DRY SOLIDS	22600. MCG/G
DIGESTION OF SOLIDS FOR METALS	DONE
DIGESTION OF SOLIDS FOR HG	DONE

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(1), RO(3), LPHE(1), FED(), INFO-P(), INFO-L()

N.Y.S. DEPT. OF ENVIRONMENTAL CONSERVATION
REGION 1 HEADQUARTERS
BUILDING 40, STATE UNIVERSITY OF N.Y.
STONY BROOK, N.Y. 11790

SUBMITTED BY: HOFMANN

104049

NEW YORK STATE DEPARTMENT OF HEALTH
WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 871009130 SAMPLE RECEIVED: 87/08/12/11 CHARGE: 22.57
POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
LOCATION: LI TUNGSTEN GARVIES PT RD GLEN COVE
TIME OF SAMPLING: 87/08/06 14:20 DATE PRINTED: 87/09/24

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
TUNGSTEN IN DRY SOLIDS	< 5000. μ CG/L
PREP OF SAMPLE FOR FP TOX	DONE

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 μ CG/L
ARSENIC	< 10. μ CG/L
SELENIUM	< 5. μ CG/L
LEAD	32. μ CG/L
BERYLLIUM	123. μ CG/L
SILVER	14. μ CG/L
BARIUM	368. μ CG/L
CADMIUM	56. μ CG/L
COBALT	6600. μ CG/L
CHROMIUM	5. μ CG/L
COPPER	134. μ CG/L
IRON	< 10. μ CG/L
MANGANESE	14400. μ CG/L
NICKEL	1690. μ CG/L
STRONTIUM	3780. μ CG/L
TITANIUM	< 5. μ CG/L
VANADIUM	< 5. μ CG/L
ZINC	5640. μ CG/L
MOLYBDENUM	31. μ CG/L
ANTIMONY	< 50. μ CG/L
TIN	< 50. μ CG/L
THALLIUM	37. μ CG/L
ALUMINUM	9680. μ CG/L

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
LEAD IN DRY SOLIDS	17800. μ CG/G

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
IRON IN DRY SOLIDS	129000. μ CG/G

**** END OF REPORT ****

*Ref. Winblom
518-474-0516*

104050

NEW YORK STATE DEPARTMENT OF HEALTH
 WADSWORTH CENTER FOR LABORATORIES AND RESEARCH

PAGE 1

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 871009131 SAMPLE RECEIVED: 87/08/12/11 CHARGE: 22.57
 PROGRAM: 6301: DIV. SOLID & HAZARDOUS WASTE - DEC REGION 1
 SOURCE ID: DRAINAGE BASIN: 17 GAZETTEER CODE: 2901
 POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
 LATITUDE: LONGITUDE: Z DIRECTION:
 LOCATION: LT TUNGSTEN GARVIES PT RD GLEN COVE
 DESCRIPTION: SS- WEST END OF DEAD VEGETATION S OF LINED POND
 REPORTING LAB: 10: LABORATORY OF INORGANIC ANALYTICAL CHEMISTRY - ALBANY
 TEST PATTERN: 10-035: METALS IN SOLID MATERIAL
 SAMPLE TYPE: 000: SOIL, SAND
 TIME OF SAMPLING: 87/08/06 14:00 DATE PRINTED: 87/09/24

DATA REPORTED WITH UNITS OF MG/L OR MCG/L ARE ANALYTICAL
 VALUES OBTAINED ON THE EP-TOT LEACHATE.

PARAMETER	RESULT
SOLIDS, DRY	85. PERCENT
ARSENIC IN DRY SOLIDS	5700. MCG/G
MERCURY IN DRY SOLIDS	0.67 MCG/G
SELENIUM IN DRY SOLIDS	6.3 MCG/G
BERYLLIUM IN DRY SOLIDS	2.8 MCG/G
SILVER IN DRY SOLIDS	< 8. MCG/G
BARIUM IN DRY SOLIDS	63. MCG/G
CADMIUM IN DRY SOLIDS	104. MCG/G
COBALT IN DRY SOLIDS	34. MCG/G
CHROMIUM IN DRY SOLIDS	13.6 MCG/L
COPPER IN DRY SOLIDS	5320. MCG/G
MANGANESE IN DRY SOLIDS	112. MCG/G
NICKEL IN DRY SOLIDS	28.4 MCG/G
STRONTIUM IN DRY SOLIDS	79. MCG/G
TITANIUM IN DRY SOLIDS	166. MCG/G
VANADIUM IN DRY SOLIDS	13. MCG/G
ZINC IN DRY SOLIDS	6040. MCG/G
MOLYBDENUM IN DRY SOLIDS	886. MCG/L
ANTIMONY IN DRY SOLIDS	44. MCG/G
TIN IN DRY SOLIDS	< 40. MCG/G
THALLIUM IN DRY SOLIDS	< 16. MCG/L
ALUMINUM IN DRY SOLIDS	4980. MCG/G
DIGESTION OF SOLIDS FOR METALS	DONE
DIGESTION OF SOLIDS FOR HG	DONE

**** CONTINUED ON NEXT PAGE ****

COPIES SENT TO: CO(1), RO(3), LPHE(1), FED(), INFO-P(), INFO-L()

N.Y.S. DEPT. OF ENVIRONMENTAL CONSERVATION
 REGION 1 HEADQUARTERS
 BUILDING 40, STATE UNIVERSITY OF N.Y.
 STONY BROOK, N.Y. 11790

SUBMITTED BY: HOFMANN

104051

NEW YORK STATE DEPARTMENT OF HEALTH
ADSWORTH CENTER FOR LABORATORIES AND RESEARCH

2

RESULTS OF EXAMINATION

FINAL REPORT

SAMPLE ID: 871009131 SAMPLE RECEIVED: 87/08/12/11 CHARGE: 22.57
POLITICAL SUBDIVISION: GLEN COVE C. COUNTY: NASSAU
LOCATION: LI TUNGSTEN GARVIES PT RD GLEN COVE
TIME OF SAMPLING: 87/08/06 14:00 DATE PRINTED: 87/09/24

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
TUNGSTEN IN DRY SOLIDS	< 5000. MCG/L
PREP OF SAMPLE FOR EP TOX	DONE

ANALYSIS: ICP-1 ICP GROUPING 1

-----PARAMETER-----	-----RESULT-----
MERCURY	< 0.2 MCG/L
ARSENIC	180. MCG/L
SELENIUM	< 5. MCG/L
LEAD	4600. MCG/L
BERYLLIUM	< 1. MCG/L
SILVER	24. MCG/L
BARIUM	46. MCG/L
CADMIUM	59. MCG/L
COBALT	55. MCG/L
CHROMIUM	12. MCG/L
COPPER	2700. MCG/L
IRON	5850. MCG/L
MANGANESE	127. MCG/L
NICKEL	37. MCG/L
STRONTIUM	93. MCG/L
TITANIUM	< 5. MCG/L
VANADIUM	< 5. MCG/L
ZINC	1930. MCG/L
MOLYBDENUM	60. MCG/L
ANTIMONY	98. MCG/L
TIN	< 50. MCG/L
THALLIUM	< 20. MCG/L
ALUMINUM	4950. MCG/L

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
LEAD IN DRY SOLIDS	37600. MCG/G

FOLLOWING PARAMETERS NOT PART OF TEST PATTERN

-----PARAMETER-----	-----RESULT-----
IRON IN DRY SOLIDS	74000. MCG/G

**** END OF REPORT ****

104052

REFERENCE NO. 22

104053

New York State Department of Environmental Conservation

MEMORANDUM

Li Tungsten File

FROM:

R. Becherer

SUBJECT:

Analytical Data

DATE:

July 15, 1986

The following data has been collected at the Li Tungsten site.
(See attached map)

AREA


1. This sample was collected from six of the drums in the main processing area.
 3. These samples were taken from the lined basin just north of Garvies Point Road.
 4. These three samples were collected from three disposal sites in area four. There is a northern, middle and southern runoff area.
- 004 This data is from one of the facility's wastewater discharges.

RB:11

Attachment

cc: G. Brezner
T. Candela

Robert A. Becherer



NASSAU COUNTY DEPARTMENT OF HEALTH
DIVISION OF LABORATORIES AND RESEARCH
ENVIRONMENTAL HEALTH LABORATORIES

TRACE ORGANICS

Access Number: 503335
Source: LI TUNGSTEN, 63 HEPB HILL RD., GLEN COVE
Matrix: WATER
Site: OUTFALL 004
Date Sampled: 11/27/85
Date of Report: 12/04/85

VOLATILE HALOGENATED	MRC (ug/l)	RESULT (ug/l)
TRICHLOROFLUOROMETHANE -----	NR	NR
METHYLENE CHLORIDE -----		
1,1,2-TRICHLOROTRIFLUOROETHANE -----	5	11
1,1-DICHLOROETHYLENE -----		
c & t-1,2-DICHLOROETHYLENE -----	14	NR
1,1-DICHLOROETHANE -----	NR	NR
CHLOROFORM -----	1	
1,1,1-TRICHLOROETHANE -----	1	1
CARBON TETRACHLORIDE -----	1	1
TRICHLOROETHYLENE -----	1	1
BROMODICHLOROMETHANE -----	1	1
c-1,3-DICHLOROPROPENE -----		
DIBROMOCHLOROMETHANE -----	1	1
1,1,2-TRICHLOROETHANE -----	1	1
1,2-DIBROMOETHANE -----	1	1
TETRACHLOROETHYLENE -----	1	1
BROMOFORM -----	2	1

VOLATILE AROMATICS	MRC (ug/l)	RESULT (ug/l)
BENZENE -----	2	NR
TOLUENE -----	4	NR
CHLOROBENZENE -----	2	NR
ETHYLBENZENE -----	5	NR
XYLENE (o,m,p) -----	6	NR
DICHLOROBENZENE (o,m,p) -----	11	NR

=====

MRC - MINIMUM REPORTABLE CONCENTRATION NR - NOT ANALYZED
NR - NO RESULT DUE TO TECHNICAL REASONS - RESAMPLE SUGGESTED
PPB: AIR - ml/l WATER - ug/l SOIL - ng/g

DEC 03 1985

104056

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL
AND HAZARDOUS WASTESDivision of Laboratories and Research
Nassau County Department of Health

- 1 ☐ Routine
 2 ☐ Resample
 3 ☒ Special
 4 ☐ Complaint
 5 ☐ Other

Lab. No.

13652

Field No.

UN196

Source Information (Please Print)

Premises

Li Tungsten

Address

63 Herb Hill Rd.

Town

Glen Cove

Collection Point

composite of sludge from

6 drums on Li property

Sampler's Comments:

- claylike; dk brown color

- EP Toxicity

Month Day Year

Date Collected

12 13 85

Date Received

DEC 13 1985

Date Reported

8

Collection Time

11 : am

Collected By:

V. Nigro

Bureau :

1 ☒ Land Resources Management9 ☐ Other (specify)

Sample Type:

A ☐ WaterD ☐ Waste SolventB ☒ SoilE ☐ OilC ☐ SludgeF ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
(1)	Aluminum mg/l	25.0	15	Chloride mg/l		29	Chromium hex. mg/l	
(2)	Arsenic mg/l	<0.005	16	Cyanide mg/l		30	FINAL pH	5.5
(3)	Barium mg/l	<0.5	17	Fluoride mg/l		31		
(4)	Cadmium mg/l	0.33	18	MBAS mg/l		32		
(5)	Chromium, Total mg/l	<0.01	19	pH INITIAL	10.3	33		
(6)	Copper mg/l	34.5	20	Phenols mg/l		34		
(7)	Iron, Total mg/l	0.41	21	Solids, Suspended mg/l		35		
(8)	Lead mg/l	0.04	22	Solids, Total Diss. mg/l		36		
(9)	Manganese mg/l	20.0	23	Sulfate mg/l		37		
10	Mercury mg/l		24	Ammonia nitrogen mg/l		38		
(11)	Nickel mg/l	32.0	25	Kjeldahl nitrogen mg/l		39		
(12)	Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l		27	Nitrate nitrogen mg/l		41		
(14)	Zinc mg/l	215	28	Total Phos. mg/l		42		

Examiner's Comments

104057

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL
AND HAZARDOUS WASTES

Division of Laboratories and Research
Nassau County Department of Health

- 1 ☐ Routine
2 ☐ Resample
3 ☒ Special
4 ☐ Complaint
5 ☐ Other

Lab. No.

13651

Field No.

UN-195

Source Information (Please Print)

Premises

Li Tungsten

Address

63 Herb Hill Rd

Town

Glen Cove

Collection Point

Composite of recharge basin soil.
across street from li; on Garries Pt.
Rd.

Sampler's Comments:

- sample orange
- EP Toxicity

Date Collected Month 12 Day 13 Year 85
Date Received DEC 13 1985
Date Reported 8

Collection Time 10:50 am
Collected By: U. Nigro

Bureau:

- 1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1	Aluminum mg/l	25.0	15	Chloride mg/l		29	Chromium hex. mg/l	
2	Arsenic mg/l	0.015	16	Cyanide mg/l		30	FINAL pH	5.6
3	Barium mg/l	<0.5	17	Fluoride mg/l		31		
4	Cadmium mg/l	0.094	18	MBAS mg/l		32		
5	Chromium, Total mg/l	0.02	19	pH INITIAL	9.5	33		
6	Copper mg/l	4.45	20	Phenols mg/l		34		
7	Iron, Total mg/l	0.10	21	Solids, Suspended mg/l		35		
8	Lead mg/l	0.08	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	13.3	23	Sulfate mg/l		37		
10	Mercury mg/l		24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	6.75	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l		27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	10.5	28	Total Phos. mg/l		42		

Examiner's Comments

CHEMICAL EXAMINATION OF INDUSTRIAL AND HAZARDOUS WASTES

Division of Laboratories and Research

Nassau County Department of Health

- 1 ☐ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Field No.

VN-180

Month Day

Source Information (Please Print)

Premises

Li Tungsten

Address

63 Herb Hill Rd

Town

Glen Cove

Collection Point

catch basin / lagoon soil sample

Date Collected

10/7/85

Date Received

10/7/85

Date Reported

Collection Time

10:00a

Collected By:

U. Nigro

Sampler's Comments:

- Extraction procedure, please
- DEC sample taken during hurricane

Bureau:

- 1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☒ Water D ☐ Waste Solvent
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1	Aluminum mg/l	3.0	15	Chloride mg/l		29	Chromium hex. mg/l	
2	Arsenic mg/l	0.037	16	Cyanide mg/l		30	Final pH	3
3	Barium mg/l	<0.5	17	Fluoride mg/l		31		
4	Cadmium mg/l	0.063	18	MBAS mg/l		32		
5	Chromium, Total mg/l	<0.01	19	pH INITIAL	3.5	33		
6	Copper mg/l	4.10	20	Phenols mg/l		34		
7	Iron, Total mg/l	10.50	21	Solids, Suspended mg/l		35		
8	Lead mg/l	0.78	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	0.27	23	Sulfate mg/l		37		
10	Mercury mg/l	INTER-FERENCE	24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	0.10	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l	<0.05	27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	0.72	28	Total Phos. mg/l		42		

Examiner's Comments

104059

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL AND HAZARDOUS WASTES

Division of Laboratories and Research

Massachusetts Department of Health

- 1 ☒ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No.

Field No.

VN-74

Source Information (Please Print)

Address *Li Tunnery*

Address *Li Tunnery*

Address *Li Tunnery*

Collection Point *Access to Li Tunnery*

Northernmost pile of soil - access - Tunnery

Sampler's Comments:

*- EP Toxicity
- Li property*

Date Collected Month *4* Day *4* Year *86*

Date Received

Date Reported

Collection Time *1:15 PM*

Collected By: *V. Nigro*

Bureau:

1 ☐ Land Resources Management

9 ☐ Other (specify)

Sample Type:

A ☐ Water

D ☐ Waste Solvent

B ☒ Soil

E ☐ Oil

C ☐ Sludge

F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1	Aluminum mg/l	<i><0.5</i>	15	Chloride mg/l		29	Chromium hex. mg/l	
2	Barium mg/l	<i>0.033</i>	16	Cyanide mg/l		30	<i>final pH</i>	<i>3.1</i>
3	Bismuth mg/l	<i><0.5</i>	17	Fluoride mg/l		31		
4	Cadmium mg/l	<i><0.001</i>	18	MBAS mg/l		32		
5	Chromium, Total mg/l	<i><0.01</i>	19	pH <i>initial</i>	<i>3.8</i>	33		
6	Copper mg/l	<i>0.17</i>	20	Phenols mg/l		34		
7	Iron, Total mg/l	<i>0.64</i>	21	Solids, Suspended mg/l		35		
8	Lead mg/l	<i>0.04</i>	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	<i>0.16</i>	23	Sulfate mg/l		37		
10	Mercury mg/l	<i><0.0005</i>	24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	<i><0.05</i>	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l	<i><0.005</i>	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l	<i><0.05</i>	27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	<i>0.12</i>	28	Total Phos. mg/l		42		

Sampler's Comments

MAY 16 1986

104060

CHEMICAL EXAMINATION OF INDUSTRIAL AND HAZARDOUS WASTES

Division of Laboratories and Research

Nassau County Department of Health

- 1 ☒ Routine
2 ☐ Resample
3 ☐ Special
4 ☐ Complaint
5 ☐ Other

Lab. No.

1975

Field No.

UN-75

Sample Information (Please Print)

Premises *Li Tungsten*

Address *1000 Hill Rd*

Town *Green Cove*

Collection Point *across the road from Tungsten*

middle pile of soil - west of fenced tank

Sampler's Comments:

FP Toxicity

- a new Janet Lt.

Month *4* Day *4* Year *86*

Date Collected:

Date Received

Date Reported

Collection Time *1:20 p.m.*

Collected By: *V. Niemi*

Bureau:

- 1 ☒ Land Resources Management
9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
B ☒ Soil E ☐ Oil
C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
<input checked="" type="checkbox"/>	Aluminum mg/l	<i><0.5</i>	15	Chloride mg/l		29	Chromium hex. mg/l	
<input checked="" type="checkbox"/>	Arsenic mg/l	<i>0.041</i>	16	Cyanide mg/l		30	<i>final pH</i>	<i>3.6</i>
<input checked="" type="checkbox"/>	Barium mg/l	<i><0.5</i>	17	Fluoride mg/l		31		
<input checked="" type="checkbox"/>	Cadmium mg/l	<i><0.001</i>	18	MBAS mg/l		32		
<input checked="" type="checkbox"/>	Chromium, Total mg/l	<i><0.01</i>	19	pH <i>initial</i>	<i>3.6</i>	33		
<input checked="" type="checkbox"/>	Copper <i>mr</i> mg/l	<i>1.17</i>	20	Phenols mg/l		34		
<input checked="" type="checkbox"/>	Iron, Total <i>mr</i> mg/l	<i>3.75</i>	21	Solids, Suspended mg/l		35		
<input checked="" type="checkbox"/>	Lead <i>mg</i> mg/l	<i>0.04</i>	22	Solids, Total Diss. mg/l		36		
<input checked="" type="checkbox"/>	Manganese <i>mr</i> mg/l	<i>0.15</i>	23	Sulfate mg/l		37		
<input checked="" type="checkbox"/>	Mercury <i>mr</i> mg/l	<i><0.0005</i>	24	Ammonia nitrogen mg/l		38		
<input checked="" type="checkbox"/>	Nickel <i>mr</i> mg/l	<i><0.05</i>	25	Kjeldahl nitrogen mg/l		39		
<input checked="" type="checkbox"/>	Selenium <i>mg</i> mg/l	<i><0.005</i>	26	Nitrite nitrogen mg/l		40		
<input checked="" type="checkbox"/>	Silver <i>mr</i> mg/l	<i><0.05</i>	27	Nitrate nitrogen mg/l		41		
<input checked="" type="checkbox"/>	Zinc <i>mr</i> mg/l	<i>0.13</i>	28	Total Phos. mg/l		42		

Miner's Comments

MAY 16 1986

104061

LABORATORY REPORT

CHEMICAL EXAMINATION OF INDUSTRIAL
AND HAZARDOUS WASTES

Division of Laboratories and Research

Nassau County Department of Health

- 1 ☒ Routine
 2 ☐ Resample
 3 ☐ Special
 4 ☐ Complaint
 5 ☐ Other

Lab. No. 1913

Field No.

VN-74

Site Information (Please Print)

Premises Li Tungsten

Address Hwy 10111111

Town Glen Cove

Collection Point across the street from Li Tungsten

sample soil/runoff - running in SE direction

Sampler's Comments:

- low toxicity

- across street

- Li property

Month Day Year
 Date Collected 11 11 86
 Date Received
 Date Reported

Collection Time 1:25 PM

Collected By: J. H. H.

Bureau:

- 1 ☒ Land Resources Management
 9 ☐ Other (specify)

Sample Type:

- A ☐ Water D ☐ Waste Solvent
 B ☒ Soil E ☐ Oil
 C ☐ Sludge F ☐ Other

CHEMICAL EXAMINATION

SPECIAL ANALYSIS

Check	Metals	Result	Check	Non-Metals	Result	Check	Constituent	Result
1	Aluminum mg/l	<0.5	15	Chloride mg/l		29	Chromium hex. mg/l	
2	Arsenic mg/l	<0.005	16	Cyanide mg/l		30		
3	Barium mg/l	<0.5	17	Fluoride mg/l		31	final pH	3.1
4	Cadmium mg/l	<0.001	18	MBAS mg/l		32		
5	Chromium, Total mg/l	<0.01	19	pH initial	3.8	33		
6	Copper mg/l	0.14	20	Phenols mg/l		34		
7	Iron, Total mg/l	0.19	21	Solids, Suspended mg/l		35		
8	Lead mg/l	0.09	22	Solids, Total Diss. mg/l		36		
9	Manganese mg/l	0.33	23	Sulfate mg/l		37		
10	Mercury mg/l	<0.0005	24	Ammonia nitrogen mg/l		38		
11	Nickel mg/l	<0.05	25	Kjeldahl nitrogen mg/l		39		
12	Selenium mg/l	<0.005	26	Nitrite nitrogen mg/l		40		
13	Silver mg/l	<0.05	27	Nitrate nitrogen mg/l		41		
14	Zinc mg/l	0.13	28	Total Phos. mg/l		42		

Analyst's Comments

MAY 16 1986

104062

REFERENCE NO. 23

104063

0024-C
02-8703-68


New York State Department of Environmental Conservation
Wildlife Resources Center
Delmar, NY 12054

RECEIVED

APR 16 1987

NYS CORPORATION

SENT TO _____



Henry G. Williams
Commissioner

April 10, 1987

Mr. David J. Grupp
NUS Corporation
Fieldcrest Avenue
Raritan Plaza III
Edison, NJ 08837

Dear Mr. Grupp:

We have reviewed the Significant Habitat Program and the Natural Heritage Program files with respect to the proposed project in the Town of Oyster Bay, Nassau County, NY.

We have identified the following potential concerns:

One Mile Radius

Rare Plants

Aristolochia serpentaria - Virginia snakeroot. This was last collected in 1879 in the vicinity of Glen Cove, NY. This is listed as "SH", State Historical, by the NY Natural Heritage Program. This means that no extant sites are known but that it may be rediscovered.

Two Mile Radius

Rare Plants

Aristolochia serpentaria - Virginia snakeroot. This was last collected in 1915 in the vicinity of Sea Cliff, NY.

Asclepias variegata - White milkweed. This was collected in the vicinity of Glen Cove, NY; however, no date was recorded. It is listed as "S1," critically imperiled in NYS because of extreme rarity, by the NY Natural Heritage Program.

Significant Habitats

SW 30-009 - Hempstead Harbor. This area has been designated as a "Significant Coastal Fish and Wildlife Habitat" by the NYS Department of

State under Policy 7 of the Waterfront Revitalization and Coastal Resources Act of 1981. It is considered one of the 10 most important waterfowl wintering areas on the north shore of Long Island, most noted for scaup, canvasback and black ducks. In addition, the bay provides nursery and feeding habitat for striped bass, scaup, bluefish, Atlantic silverside, menhaden, winter flounder and blackfish.

Three Mile Radius

Rare Plants

Corydalis flavula - Yellow harlequin. This plant was last collected in 1907 in the vicinity of Manhasset Neck on the west side of Hempstead Harbor. It is listed as "S1" by the NY Natural Heritage Program.

Silene caroliniana va. pennsylvanica - Wild pink. This plant was confirmed in 1986 in Locust Valley near Forest Avenue and Bayville Road. It is listed as "S3," rare in NY State, by the NY Natural Heritage Program.

Significant Habitats

SW 30-009 - (see description above)

SW 30-005 - Dosoris Pond and SW 30-006 - adjacent woodlands. Dosoris Pond is a relatively large, protected brackish pond, rare in Nassau County. The woodlands and wetlands surrounding the pond support several heron spp. as feeding and occasionally breeding habitat.

SW 30-011 - Estate lands south and east of Glen Cove. This general area supports a variety of wildlife including several amphibians and wintering waterfowl concentrations. Spotted salamander, a State listed special concern species, has been reported from an area near Matinecock.

SW 30-013 - Glen Cove to Mill Neck Bay Waterfowl Area. This offshore area is most noted for wintering scaup, mallard, Canada geese and black ducks. More information concerning these sites may be available from the following sources:

Protected Significant Coastal Fish and Wildlife Habitats

SW 30-009 -
Hempstead Harbor

Mr. Thomas F. Hart
NYS DOS
162 Washington Avenue
Albany, NY 12231
(518) 474-3642

Rare Plants

Dr. Steven Clemants
NY Natural Heritage Program
Wildlife Resources Center
Delmar, NY 12054
(518) 439-7488

or

Mr. Robert Zaremba
The Nature Conservancy
P.O. Box 72
Cold Spring Harbor, NY 11724
(516) 367-3225

Significant Habitats

Regional Wildlife Manager
NYS DEC
SUNY @ Stony Brook - Bldg. 40
Stony Brook, NY 11790
(516) 751-7900

Our files are continually growing as new habitats and occurrences of rare species and communities are discovered. In most cases, site-specific or comprehensive surveys for plant and animal occurrences have not been conducted. For these reasons, we can only provide data which has been assembled from our files. We cannot provide a definitive statement on the presence or absence of species, habitats or natural communities. This information should not be substituted for on-site surveys that may be required for environmental assessment.

If this project is still active one year from now we recommend that you contact us again so that we may update this response.

Requests for data from the New York Natural Heritage Program and the Significant Habitat Program are now being consolidated. When requesting information from our files please include a brief description of the proposed project and a photocopy of the appropriate topographic quadrangle(s) with the site or sites identified. All requests should be addressed as follows:

ATTN: Information Services
Significant Habitat Unit
NYS Dept. of Environmental Conservation
Wildlife Resources Center
Delmar, NY 12054-9767

Our phone number is (518)439-7486. Please make a note of these changes.

If we can be of further assistance please do not hesitate to contact us.

Sincerely,



John W. Ozard
Senior Wildlife Biologist
Significant Habitat Unit

cc: H. Knoch
T. Hart
S. Clemants
R. Zaremba

JWO:sjs

REFERENCE NO. 24

104068

[WH FRL 2511-2]

**Aquifers Underlying Kings and Queens
Counties, New York Determination**

AGENCY: Environmental Protection
Agency, Region II.

ACTION: Notice of determination:
aquifers underlying Kings and Queens
Counties, New York.

SUMMARY: Notice is hereby given that pursuant to section 1424(e) of the Safe Drinking Water Act (Pub. L. 93-523) the Administrator of the Environmental Protection Agency has determined that the aquifer underlying Kings and Queens Counties, New York, is the sole or principal source of drinking water for the southeastern portion of Queens County, New York, and which, if contaminated, would create a significant hazard to public health.

ADDRESS: The data on which these findings are based are available to the public and may be inspected during normal business hours at the U.S. Environmental Protection Agency, Water Supply Branch, 26 Federal Plaza, New York, New York 10278.

FOR FURTHER INFORMATION CONTACT:
Damian J. Duda, U.S. Environmental
Protection Agency, Water Supply
Branch, 26 Federal Plaza, New York,
New York 10278—Tel. (212) 264-1800.

SUPPLEMENTARY INFORMATION: The Safe
Drinking Water Act was enacted on

December 16, 1974. Section 1424(e) of the Act states:

If the Administrator determines, on his own initiative or upon petition, that an area has an aquifer which is the sole or principal drinking water source for the area and which, if contaminated, would create a significant hazard to public health, he shall publish notice of the determination in the Federal Register. After the publication of any notice, no commitment for Federal financial assistance (through a grant, contract, loan guarantee or otherwise) may be entered into for any project which the Administrator determines may contaminate such aquifer through a recharge zone so as to create a significant hazard to public health but a commitment for Federal financial assistance may, if authorized under another provision of law, be entered into to plan or design the project to assure that it will not so contaminate the aquifer.

Background

On June 18, 1979, the Jamaica Water Supply Company, Lake Success, New York, petitioned the Administrator to amend the Long Island (Nassau/Suffolk) designation of June 21, 1978, 43 FR 28811 to include the aquifers underlying Kings and Queens Counties, New York, as a sole source aquifer under the provisions of section 1424(e) of the Safe Drinking Water Act.

Public Participation

A notice of receipt of this petition, together with a request for comments was published in the Federal Register August 29, 1979, 44 FR 50649. In response to the Notice and request for comments, written comments were received from a State, and a local governmental agency. Both commenters claimed that the designation would be premature since there is an absence of final rules and regulations on the sole or principle source aquifer program under Section 1424(e). The letters further stated that New York State will be developing a ground-water management program and that the EPA should await the outcome of these studies before considering designation of the aquifer. The agency does not agree with the letters requesting further delay since the ground water management studies referred to are not directly related to the sole source designation request. In addition, EPA had sufficient information to write a background document which serves as the basis for designation.

On October 4, 1979, the Environmental Protection Agency (EPA) held a public hearing in Queens County, New York City, New York to hear the views of persons interested in the Kings and Queens Aquifer issue. Two groups presented testimony at the public hearing. The first group represented the

petitioner, Jamaica Water Supply Company and the second represented the New York State Department of Health, Bureau of Public Water Supply. There were no representatives of the public present at the public hearing.

Basis for the determination

On the basis of the information which is available to this Agency the Administrator has made the following findings, which are the basis for the determination noted above:

(1) The Kings and Queens aquifers which underly the southeastern portion of Queens County are the sole or principal source of drinking water for approximately 650,000 people in such area, which is the service area of the Jamaica Water Supply Company. In 1979, the aquifers supplied approximately 60 million gallons per day (mgd) of water from 63 wells located in or near the water supply franchise area of the Jamaica Water Supply Company. Current water supply treatment practice for public supplies is generally limited to disinfection for drinking purposes. There is no alternative source of drinking water supply which could replace these aquifers if they were contaminated.

While the Kings and Queens aquifers are not utilized as the sole or principal source of drinking water for the Borough of Kings or for any other portion of Queens County, the geographic boundaries of Kings and Queens Counties are the recharge zone for the aquifers underlying the southeastern portion of Queens County. The recharge zone also encompasses parts of Nassau County, New York. Aquifers underlying Nassau and Suffolk Counties, New York have already been designated as a sole or principal source aquifer under Section 1424(e) of the Safe Drinking Water Act.

(2) The aquifers underlying Kings and Queens Counties are vulnerable to contamination through their recharge zone, particularly from leaking sewer pipes. Other sources such as past farming practices and present fertilization of lawns and gardens may also be significant. The area contains leaking fuel tanks and leachate from open dumps and improperly operated landfill sites all of which add to the contamination of the ground water. In addition, EPA analysis shows that further and continued withdrawal of water over and above the aquifers sustained yield would cause the salt-fresh water interface to move into the aquifers recharge zone thereby threatening the ground water quality by increasing the chloride content in the water. Since ground water contamination can be difficult or impossible to reverse, and because this

aquifer is relied upon for drinking purposes by many people, contamination of the aquifer would pose a significant hazard to public health.

(3) When an aquifer has been designated as the sole or principal source of drinking water, the area in which projects may be reviewed is the area encompassed by: (1) the boundary of the designated aquifer's recharge zone, and (2) its stream-flow source zone.

The Administrator has determined that the recharge zone and stream-flow source zone for the aquifers underlying southeastern Queens County are defined by the outside boundary of Kings County (Borough of Brooklyn) and Queens County (Borough of Queens) in the city of New York and parts of Nassau County. Since the parts of Nassau County within the recharge and streamflow source zones of the aquifers underlying southeastern Queens County are already under sole or principal source protection as the result of the Agency's prior designation of the aquifers underlying Nassau/Suffolk Counties, today's designation will extend the area for project review to encompass projects undertaken in the Boroughs of Brooklyn and Queens in the city of New York.

Information Utilized in This Determination

The petition, written and verbal comments submitted by the public, a detailed map of the area and independent analysis by EPA are available to the public and may be inspected during normal business hours at the office of the Environmental Protection Agency, Region II, Water Supply Branch, 26 Federal Plaza, Room 24-130, New York, New York 10278.

A copy of the above documentation is also available at the U.S. Environmental Protection Agency, Waterside Mail, Public Information and Reference Unit, Room 2922, 401 M. Street S.W., Washington, DC 20460.

Project Review

EPA proposed national regulations for implementing Section 1424(e) of the Safe Drinking Water Act on September 29, 1977, at 42 FR 51620. The proposed regulations contain procedures for review of Federal financially assisted projects which could contaminate "sole or principal source" aquifers through the recharge zone so as to create a significant hazard to public health. They are being used as interim guidance until promulgation of final regulations. Questions and comments concerning the possible effect of the regulations on

Federally assisted projects in the designated Kings/Queens Aquifer should be directed to the Water Supply Branch, U.S. Environmental Protection Agency, Region II, 26 Federal Plaza, New York, New York 10278.

EPA Region II is working with the Federal agencies, which may sponsor projects in the area of concern, to develop interagency procedures whereby EPA will be notified of proposed commitments for projects which could contaminate the designated aquifer. EPA will evaluate such projects and, where necessary, conduct an in-depth review, including soliciting public comments where appropriate.

Although the project review process cannot be delegated, the Regional Administrator in Region II will rely, to the maximum extent possible, upon close coordination with State and local agencies to ensure consistency with their program objectives. Their input will be given full consideration and the Federal review process will function so as to complement and support State and local protection programs.

Federal funding may be withheld from any project which, upon review, may contaminate the aquifer through a recharge zone so as to create a significant hazard to public health.

Economic and Regulatory Impact

Pursuant to the provisions of the Regulatory Flexibility Act (RFA), 5 U.S.C. 605(b), I hereby certify that the attached rule will not have a significant impact on a substantial number of small entities. For purposes of this Certification the "small entity" shall have the same meaning as given in Section 601 of the RFA. This action is only applicable to the Kings-Queens Area.

The only affected entities will be those area-based business, organizations or governmental jurisdictions that request Federal financial assistance for projects which have the potential for contaminating the aquifer so as to create a significant hazard to public health. EPA does not expect to be reviewing small isolated commitments of financial assistance on an individual basis, unless a cumulative impact on the aquifer is anticipated; accordingly, the number of affected small entities will be minimal.

For those small entities which are subject to review, the impact of today's action will not be significant. Most projects subject to this review will be preceded by a ground water impact assessment required pursuant to other Federal laws, such as the National Environmental Policy Act, as amended (NEPA), 42 U.S.C. 4321, et seq.

Integration of those related review procedures with sole source aquifer review will allow EPA and other Federal agencies to avoid delay or duplication of effort in approving financial assistance, thus minimizing any adverse effect on those small entities which are affected. Finally, today's action does not prevent grants of Federal financial assistance which may be available to any affected small entity in order to pay for the redesign of the project to assure protection of the aquifer.

Under Executive Order 12291, EPA must judge whether a regulation is "major" and therefore subject to the requirement of a Regulatory Impact Analysis. This regulation is not "major" because it will not have an annual effect of \$100 million or more on the economy, will not cause any major increase in costs or prices, and will not have significant adverse effects on competition, employment, investment, productivity, innovation, or the ability of United States enterprises to compete in domestic or export markets. Today's action only affects the designated area. It provides an additional review of ground water protection measures, incorporating State and local measures whenever possible, for only those projects which request Federal financial assistance. Accordingly, a Regulatory Impact Analysis will not be required.

Dated: January 12, 1983

William D. Ruckelshaus,
Administrator.

(FR Doc. 84-1286 Filed 1-23-84; 2:45 am)
BILLING CODE 6560-50-41

REFERENCE NO. 25

104072

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION II

IN THE MATTER OF LI TUNGSTEN SITE

Glen Cove Development Company,
Respondent.

Proceeding Under Section 106(a) of the
Comprehensive Environmental Response,
Compensation and Liability Act
(42 U.S.C. § 9606(a)).

ADMINISTRATIVE ORDER
ON CONSENT

Index No. II CERCLA-90215

JURISDICTION

1. THIS ADMINISTRATIVE ORDER ON CONSENT ("Consent Order") IS ISSUED to the Glen Cove Development Company ("Respondent"), by the United States Environmental Protection Agency ("EPA") pursuant to the authority vested in the President of the United States by Section 106(a) of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980, as amended ("CERCLA"), 42 U.S.C. § 9606(a), which authority was delegated to the Administrator of EPA by Executive Order 12580, dated January 23, 1987, and duly redelegated to the Regional Administrator of EPA Region II. Notice of this Consent Order has been given to the New York State Department of Environmental Conservation ("NYSDEC"), as required by Section 106(a) of CERCLA, 42 U.S.C. § 9606(a).

2. Respondent agrees to undertake all actions required by the terms and conditions of this Consent Order, including, but not limited to, the Scope of Work ("Appendix A") and the Compliance Schedule ("Appendix B") which are attached hereto and incorporated herein.

3. Respondent agrees not to contest the authority or jurisdiction of the Regional Administrator to issue this Consent Order and also agrees not to contest the terms of this Consent Order in any action to enforce its provisions.

4. This Consent Order shall apply to and be binding upon Respondent, as well as its agents, officers, directors, officials, contractors, receivers, trustees, successors and assigns.

DEFINITIONS

5. Unless otherwise defined herein, terms used in this Consent Order that are defined in Section 101 of CERCLA, 42 U.S.C. § 9601, shall have the meanings ascribed to them therein.

FINDINGS OF FACT AND CONCLUSIONS OF LAW

6. Respondent is a general partnership duly organized and existing under the laws of the State of New York and is owned by the Old Court Holdings Company and the Old Court Joint Ventures, Inc..

7. Respondent owns property, located at the intersections of Herhill Road and Dickson Lane in the City of Glen Cove, Nassau County, New York, known as the Li Tungsten Corporation facility (hereinafter referred to as the "Facility" or the "Site").

8. The Facility includes approximately ten (10) buildings and is located in a commercial area within one quarter of a mile of a public recreation area and residential dwellings. The Facility is situated above a sole source aquifer and is bounded to the south by the Glen Cove Creek into which surface water run-off discharges. The Glen Cove Creek is a tidal creek of Glen Cove Harbor.

9. Between 1941 and June of 1985, raw ore and scrap metals were processed at the Facility to produce an enriched tungsten product.

10. From 1941 to 1972, the Facility was owned and operated by the Wah Chang Smelting and Refining Company of America, Inc. ("Wah Chang"). In 1972, Wah Chang formed a wholly owned subsidiary, known as the Li Tungsten Corporation. Wah Chang retained title to the property and leased the premises to the Li Tungsten Corporation which, in turn, operated the Facility.

11. In November of 1984, Respondent purchased the Facility and the Li Tungsten leasing arrangement from Wah Chang and continued the lease arrangement with the Li Tungsten Corporation. In June of 1985, the Li Tungsten Corporation ceased operations at the Facility and filed a voluntary petition for bankruptcy pursuant to Chapter 11 of the Bankruptcy Code. No manufacturing operations have been conducted at the Site since June of 1985.

12. Prior to the issuance of this Consent Order, Respondent, through its consultants, undertook the following measures at the Site:

- a) an external inspection of fifty tanks at the Facility to determine whether they were secure against rupture or leakage;
- b) the sampling, draining, and drumming for disposal of the contents of two tanks determined not to be secure;
- c) the packing of identifiable laboratory contents at the Facility;
- d) the over-packing and/or staging of 108 drums containing acids, organics, and waste oil to a secure area at the Site;
- e) the inventory, sampling, and removal of pressurized gas cylinders;
- f) the removal of approximately one tank truck of anhydrous ammonia from the Facility, and
- g) the establishment of twenty-four hour security at the Facility.

13. On March 29, 1989, NYSDEC inspected the Site and conducted an initial survey of the conditions as they existed at the Site at that time. NYSDEC reported the presence of, among other things, (a) approximately one hundred (100) drums containing liquid chemicals which were tentatively identified as containing cyanide, acids, and alkalis, (b) numerous storage tanks containing unknown quantities of liquid chemicals, (c) approximately twenty-six (26) pressurized cylinders containing chemicals, and (d) approximately twelve (12) transformers, some of which are leaking and are suspected to contain polychlorinated biphenyls ("PCBs"). The survey also revealed elevated radiation levels, the source of which is believed to be radium, thorium, and uranium, which are associated with ore from certain sources and is present as a result of the tungsten refining and manufacturing process.

14. On April 14, 1989, NYSDEC formally requested that EPA undertake appropriate response action at the Site pursuant to CERCLA, at which time EPA also assumed the lead enforcement role with regard to response actions at the Site.

15. On April 16 and 26-28, 1989, EPA inspected the Facility and conducted a preliminary investigation. The investigation confirmed the conditions reported by NYSDEC and tentatively identified the contents of the drums, including hydrofluoric acid, nitric acid, hydrochloric acid, carbon tetrachloride, and perchloroethylene ("PCE"). A number of the

drums containing processed wastes and solids are badly corroded with portions of their contents deposited onto warehouse floors and the yard at the Facility.

16. The substances present at the Site can cause a variety of adverse human health effects with prolonged or direct exposure, including adverse effects on the central nervous system, the respiratory system, and the cardiovascular system.

17. The Facility constitutes a "facility" within the meaning of Section 101(9) of CERCLA, 42 U.S.C. § 9601(9).

18. Cyanide, hydrofluoric acid, nitric acid, hydrochloric acid, carbon tetrachloride, and PCE are hazardous substances, as that term is defined in Section 101(14) of CERCLA, 42 U.S.C. § 9601(14).

19. Releases and/or threatened releases of hazardous substances have occurred at the Site, as that term "release" is defined in Section 101(22) of CERCLA, 42 U.S.C. § 9601(22), in that, among other things, such substances have leaked, spilled, been abandoned and/or have been otherwise released into the environment. In addition, there is a threat of further releases at and from the Site.

20. Conditions present at the Site pose a threat to the public health or welfare or the environment, based on factors set forth at Section 300.65(b)(2) of the National Contingency Plan ("NCP"), 40 C.F.R. § 300.65(b)(2) (July 1, 1986), including, but not limited to, the following:

- a) Actual or potential exposure to hazardous substances or pollutants or contaminants by nearby populations, animals, or food chain;
- b) Actual or potential contamination of drinking water supplies or sensitive ecosystems;
- c) Hazardous substances or pollutants or contaminants in drums, barrels, tanks, or other bulk storage containers, that may pose a threat of release;
- d) Other situations or factors which may pose threats to public health or welfare or the environment.

21. Respondent is a "person", as defined in Section 101(21) of CERCLA, 42 U.S.C. § 9601(21), and an owner and/or operator as defined in Section 101(20)(A), 42 U.S.C. § 9601(20)(A) of the Facility. Respondent is thus a responsible

party under Section 107(a) of CERCLA, 42 U.S.C. § 9607(a), and is liable for all costs of response, plus interest, incurred by the United States Government.

22. Respondent has been given an opportunity to discuss with EPA the basis for issuance of this Consent Order and its terms. Respondent has prepared Appendices A and B, attached hereto, for the performance of a removal action at the Site.

23. Respondent does not, by signing this Consent Order, concede that the "Findings of Fact and Conclusions of Law" set forth herein are correct or complete. Nor does Respondent admit that it is in any way responsible for any contamination at the Site or in any way liable for future response action(s) at the Site or any costs attendant to such response action(s).

DETERMINATION

Based on the FINDINGS and CONCLUSIONS set forth above, EPA Region II has determined that the release or threatened release of one or more hazardous substances or pollutants or contaminants from the Facility may present an imminent and substantial endangerment to the public health or welfare or the environment within the meaning of Section 106(a) of CERCLA, 42 U.S.C. § 9606(a).

ORDER

Based on the foregoing FINDINGS, DETERMINATION, and the entirety of the Administrative Record, IT IS HEREBY ORDERED that, to protect the public health, welfare, and the environment, it is necessary that certain actions be taken to abate the conditions at the Site, and further, that Respondent shall undertake a response action at the Site in accordance with the requirements specified below. All activities set forth below shall be initiated and completed as soon as possible, even though maximum time periods for their completion are specified in Appendix B.

DESCRIPTION OF WORK

24. Respondent agrees to implement the work set forth in Appendix A within the time frames established in Appendix B, both of which are attached hereto and which include plans for the following:

- a) providing continuing Site security;
- b) containing and addressing materials exhibiting elevated radioactivity;
- c) securing and disposing of laboratory chemicals;

- d) inventory and removal of drums containing chemicals;
- e) characterization of the tanks at the Site;
- f) precautionary monitoring and selected sampling of asbestos at the Site;
- g) sampling and analysis of sediments from the creek adjacent to the Facility;
- h) inventory and characterization of transformers at the Site, and
- i) clean-up of mercury spill within a building at the Site.

25. Appendices A and B attached hereto shall be deemed incorporated into and an enforceable part of this Consent Order.

26. EPA approval of all plans, reports, and other submittals required under the terms of this Consent Order shall constitute a finding that such submittals are deemed consistent with the NCP.

27. EPA shall make the final determination as to the sufficiency and/or acceptability of all work, as set forth in Appendix A, conducted under this Consent Order, including but not limited to each required submittal.

DESIGNATED COORDINATOR, ON-SCENE COORDINATOR,
OTHER PERSONNEL

28. Within three (3) calendar days of the effective date of this Consent Order, Respondent shall select a coordinator, to be known as the Designated Coordinator, and submit the name, address, and telephone number of the Designated Coordinator to Charles Fitzsimmons, the EPA On-Scene Coordinator ("OSC") and Alison Hess, the EPA Enforcement Project Officer, as set forth in paragraph 35 of this Consent Order. The Designated Coordinator shall be responsible for the Respondent's oversight of implementation of this Consent Order. The OSC and the Enforcement Project Officer are the persons designated by EPA to be responsible for on-scene monitoring of actions and activities required pursuant to this Consent Order. All EPA correspondence to the Respondent shall be sent promptly, in writing, to the Designated Coordinator. EPA will notify the Designated Coordinator if there is a personnel change in either the OSC or Enforcement Project Officer position.

29. All activities required of Respondent under the

terms of this Consent Order shall be performed only by qualified persons possessing all necessary permits, licenses, and other authorizations required by federal, state, and local governments.

30. As appropriate during the course of implementation of the actions required of Respondent pursuant to the Consent Order, Respondent or its consultants or contractors, acting through the Designated Coordinator, may confer with the EPA concerning the required actions. Based upon new circumstances or new information not in the possession of the EPA on the date of issuance of this Consent Order, the Designated Coordinator may submit a request to EPA, in writing, as set forth in paragraph 35 of this Consent Order, for approval of a modification to Appendices A and B. If approved by EPA in writing, such modification shall be deemed incorporated into this Consent Order.

31. In the event of a significant change in conditions at the Site, the Designated Coordinator shall immediately notify the EPA Enforcement Project Officer, at (212) 264-6040, and the EPA OSC, at the following telephone numbers: (201) 321-6608 (during business hours), or (201) 548-8730 (after business hours). In the event that EPA determines that the activities performed pursuant to this Consent Order or any emergency circumstance occurring at the Site pose a threat to human life or health or the environment, EPA may direct Respondent to cease further implementation of any actions pursuant to this Consent Order or to take other and further actions reasonably necessary to abate the threat. This provision is not to be construed so as to limit any powers EPA may have under Section 300.65 of the NCP, 40 C.F.R. § 300.65, or any other applicable provision of the NCP, or under any other applicable law or regulation.

32. Respondent's activities under this Consent Order shall be performed within the time limits set forth in Appendix B unless performance is delayed by events which constitute force majeure. For purposes of this Consent Order, force majeure is defined as any event arising from circumstances which are beyond the control of Respondent and could not have been avoided by the exercise of due care. Financial considerations shall not be considered circumstances beyond the control of Respondent. When an event constituting force majeure occurs, Respondent shall be obligated to perform the affected activities within a time period which shall be extended for a period of time reasonably attributable to force majeure. Respondent shall notify the EPA in writing, in the manner set forth in paragraph 35 of this Consent Order, as soon as possible following Respondent's awareness that circumstances constituting force majeure have occurred or are likely to occur. Failure by respondent to notify EPA in a timely manner shall constitute a waiver of its right to assert force majeure as a defense in any action brought by EPA to enforce the terms of this Consent Order. The burden of proving

that an event constituting force majeure has occurred shall rest with Respondent.

REPORTING REQUIREMENTS

33. All reports and other documents submitted by Respondent to EPA (other than the bi-monthly progress reports referred to in paragraph 34) which purport to document Respondent's compliance with the terms of this Consent Order shall be signed by a corporate officer of Respondent or the Designated Coordinator on behalf of Respondent.

34. Respondent shall provide bi-monthly written progress reports to the EPA Enforcement Project Officer and the OSC. Such reports shall fully describe all actions and activities undertaken and all validated sampling results obtained pursuant to this Consent Order since the prior report, as well as anticipated activities to be conducted at the Site during the next reporting period.

35. All submittals and notifications to EPA pursuant to this Consent Order shall be made in writing, with one copy sent to the OSC:

Charles Fitzsimmons - Li Tungsten OSC
Response and Prevention Branch
U.S. Environmental Protection Agency
Woodbridge Avenue
Edison, NJ 08837
(201) 321-6608

and two copies sent to the Enforcement Project Officer:

Carole Petersen, Chief
New York/Caribbean Compliance Branch
Emergency and Remedial Response Division
U.S. EPA, Region II
Room 737
26 Federal Plaza
New York, NY 10278
Attn: Alison Hess
Enforcement Project Officer
(212) 264-6040

All notices required to be given to Respondent pursuant to the terms of this Consent Order shall be sent to the Designated Coordinator, with one copy to the following addressees:

Debra Rothberg, Esq.
Jones, Day, Reavis & Pogue
599 Lexington Avenue
New York, NY 10022

Glen Cove Development Company
34 Market Place, Suite 301
Baltimore, MD 21202

Attn: Li Tungsten

ACCESS AND AVAILABILITY OF DATA

36. Respondent shall in no way hinder full and unimpeded access to the Site or any structure at the Site by EPA and NYSDEC, as well as their respective representatives, agents, employees, contractors and consultants. Respondent shall not prohibit such persons from being present at the Site at any and all times and from observing any and all activities conducted pursuant to this Consent Order. If Respondent is unable to obtain access to any portion of the Site, Respondent shall make its best effort to obtain access to any such portion of the Site prior to requesting that EPA assist in obtaining such access.

37. In accordance with applicable law, EPA and NYSDEC shall have full access to all records, including, but not limited to, contractual documents maintained or created by Respondent or its contractors or consultants in connection with implementation of the work under this Consent Order (except for records which are properly asserted as attorney work product or attorney/client privilege). In addition, all data, information, and records created or maintained in connection with implementation of the work under this Consent Order shall, upon request, be available to EPA without delay, and all persons, including employees and contractors, who engage in activity under this Consent Order shall be available to and shall cooperate with the United States and/or EPA in providing such sources of information.

38. Respondent agrees to preserve, during the pendency of this Consent Order and for a minimum of eight (8) years after its termination, all records and documents in its possession or in the possession of its employees, agents, or contractors which in any way relate to the Site, despite any internal document retention policy to the contrary. After this eight year period, Respondent shall notify EPA at least thirty (30) calendar days prior to the destruction of any such documents. Upon request by EPA, Respondent shall make available to EPA such records or copies of any such records (except for records which are properly asserted as attorney work product or attorney/client privilege). Additionally, if EPA requests that some or all documents be preserved for a longer period of time, Respondent shall either comply with that request or provide the originals or copies, if such originals are not available, of the requested documents to EPA.

39. Respondent agrees not to conduct any response action at the Site, except those specifically referenced in Appendix A, without receiving written approval in advance by EPA.

40. Upon request by the EPA, Respondent shall provide split samples of any material sampled in connection with implementation of this Consent Order.

GENERAL PROVISIONS

41. All actions and activities carried out by Respondent pursuant to this Consent Order shall be done in accordance with all applicable federal, state, and local laws, regulations, and requirements and with CERCLA, the NCP, and any amendments thereto which may become effective prior to the date of EPA certification of completion, as set forth in paragraph 57, infra.

42. Any waste disposal conducted by Respondent pursuant to this Consent Order shall comply with all requirements of CERCLA, 42 U.S.C. §§ 9601-9675, including Section 121(d)(3), 42 U.S.C. § 9621(d)(3), RCRA, 42 U.S.C. §§ 6901-6991, the Toxic Substances Control Act ("TSCA"), 15 U.S.C. §§ 2601-2654, and all regulations and guidance promulgated pursuant thereto.

43. EPA shall be notified, in the manner set forth in paragraph 35 of this Consent Order, of the selection of any waste treatment, storage, or disposal facilities to be utilized for waste disposal conducted pursuant to this Consent Order at least five (5) days prior to off-site shipment of such wastes.

44. In the event that, for any reason, off-site treatment or disposal facilities are not available at the time Respondent may require such facilities for the completion of tasks required under this Consent Order, Respondent shall arrange, subject to EPA approval, for an authorized facility to store these wastes until such disposal or treatment facilities are available.

45. All sampling and analyses performed pursuant to this Consent Order shall conform to EPA Quality Assurance/Quality Control (QA/QC) and Chain of Custody procedures as set forth in Appendix A to this Consent Order.

46. All records produced by Respondent and delivered to the EPA in the course of implementing this Consent Order shall be available to the public unless identified as confidential by Respondent pursuant to 40 C.F.R. Part 2, Subpart B, and determined by EPA to merit confidential treatment, in accordance with Section 104(e)(7) of CERCLA, 42 U.S.C. § 9604(e)(7), and applicable regulations.

47. Neither EPA nor the United States, by issuance of this Consent Order, assumes any liability for any acts or

omissions by Respondent, or Respondent's employees, agents, contractors or consultants in carrying out any action or activity pursuant to this Consent Order, nor shall EPA or the United States be held as a party to any contract entered into by Respondent, Respondent's officers, employees, agents, contractors or consultants in carrying out any action or activity pursuant to this Consent Order.

48. Nothing contained in this Consent Order shall affect Respondent's right to seek and obtain contribution or indemnification from other parties potentially liable for conditions which exist at the Site, except as limited by the rights reserved to EPA under Section 113 of CERCLA, 42 U.S.C. § 9613.

49. Nothing contained in this Consent Order shall affect any right, claim, interest, defense, or cause of action of any party hereto with respect to third parties.

50. EPA reserves the right to pursue third parties within its enforcement discretion for response actions and or cost recovery in connection with the Site.

51. Respondent agrees to reimburse EPA for all response costs incurred by the U.S. Government prior to the issuance and during the performance of the Consent Order. EPA shall transmit to Respondent periodic accountings of all such response costs with a narrative of the activities for which the costs were incurred. The response costs shall include those incurred by EPA, or by a contractor selected by EPA, with respect to work conducted by Respondent associated with the actions undertaken pursuant to this Consent Order. Within ten (10) business days of receipt of an accounting, Respondent will remit a check for the amount of those costs, made payable to the Hazardous Substance Superfund. Checks should specifically reference the identity of the Superfund site and the index number of this Consent Order. Payment should be sent to:

U.S. Environmental Protection Agency - Region II
Superfund Accounting
P.O. Box 360188M
Pittsburgh, PA 15251

A letter of explanation shall accompany the payment; a copy of the letter shall be sent to the Chief, New York/Caribbean Compliance Branch (whose address appears in paragraph 35 of this Consent Order).

52. Nothing herein shall constitute or be construed as a satisfaction or release from liability for Respondent, or Respondent's agents, contractors, lessees, receivers, successors or assigns with respect to any conditions or claims arising as a

result of past, current, or future operations, ownership, use of the Site, or disposal at the Site of hazardous substances. Respondent also agrees to indemnify and hold harmless EPA and the United States Government, its agencies, departments, agents, and employees for all claims, causes of action, damages, and costs of any type or description by third parties for any injuries or damages to persons or property resulting from acts or omissions of Respondent or its officers, directors, officials, receivers, trustees, successors, or assigns in carrying out any activities at the Site.

53. Nothing in this Consent Order constitutes a decision on pre-authorization of funds under Section 111(a)(2) of CERCLA, 42 U.S.C. § 9611(a)(2). Furthermore, Respondent agrees that it will not petition for reimbursement under Section 106(b) of CERCLA, 42 U.S.C. § 9606(b), for the performance of any actions required under this Consent Order.

ENFORCEMENT

54. Failure of Respondent to satisfy any terms of this Consent Order completely and expeditiously may result in EPA taking the required actions unilaterally, pursuant to Section 104 of CERCLA, 42 U.S.C. § 9604.

55. If Respondent fails, without prior EPA approval, to comply with any of the requirements or deadlines set forth in this Consent Order, Respondent shall each make payments to the EPA in the amount indicated below for each day of non-compliance:

<u>Days After Required Date</u>	<u>Stipulated Penalties</u>
11 to 20 days	\$1000.00
21 to 30 days	\$3000.00
31 to 45 days	\$5000.00

Any such penalty shall accrue as of the sixth day after the applicable deadline has passed and shall be due and payable ten days following receipt of the written demand from EPA or, if no such demand is received, on the thirtieth day following the date the penalty begins to accrue and shall be due and payable every thirtieth day thereafter. Payment of any such penalty to the EPA shall be made to EPA by certified check in accordance with paragraph 51 of this Consent Order. After forty-five consecutive days of non-compliance, EPA reserves the right to pursue civil penalties up to \$25,000 per day pursuant to Section 106(b) of CERCLA, 42 U.S.C. § 9606(b), in lieu of these stipulated penalties.

56. Violation of this Consent Order as a result of Respondent's failure to comply with any provision herein, including but not limited to any failure to comply with Appendices A and B, attached hereto, shall be enforceable pursuant to Sections 106(b) and 113(b) of CERCLA, 42 U.S.C.

§§ 9606(b) and 9613(b). Respondent may also be subject to an action for cost recovery, civil penalties of up to \$25,000 per day of violation of this Consent Order, and/or punitive damages (including treble damages), as provided in Sections 107(a), 106(b), and 107(c)(3) of CERCLA, 42 U.S.C. §§ 9607(a), 9606(b), and 9607(c)(3), respectively, for failure to comply with the terms of this Consent Order. Nothing herein shall preclude EPA from taking any additional enforcement actions, and/or other actions as it may deem necessary for any purpose, including the prevention or abatement of an imminent and substantial danger to the public health, welfare, or the environment arising from conditions at the Site, and recovery of the costs thereof.

Termination and Satisfaction

57. The provisions of this Consent Order shall be deemed satisfied upon receipt by Respondent of written certification from EPA that Respondent has demonstrated that all of the terms of this Consent Order, including, but not limited to, Appendices A and B, have been completed in accordance with the terms hereof to the satisfaction of EPA.

58. When Respondent concludes that it has completed the work required under the terms of this Consent Order, Respondent shall so notify EPA by submitting documentation demonstrating that it has complied with and completed the implementation of this Consent Order. That documentation shall further include a certification statement, signed by a responsible corporate officer of Respondent, which states the following:


"I certify that the information contained in or accompanying this submission is true, accurate, and complete.

"As to (the) (those) identified portions(s) of this submission for which I cannot personally verify (its) (their) truth and accuracy, I certify, as the company official having supervisory responsibility for the person(s) who, acting under my direct instructions, made the verification that the information is true, accurate, and complete."

Following receipt of the aforementioned documentation, and if EPA determines that the work required has been carried out in accordance with the terms of this Consent Order, EPA will notify Respondent to that effect, in writing, as set forth in paragraph 57.

59. This Consent Order shall be effective on the date of receipt of an executed copy by Counsel for Respondent. All times for performance of activities required herein will be calculated from the effective date.

U.S. ENVIRONMENTAL PROTECTION AGENCY

 *James R. Marshall* *for*
WILLIAM J. MUSZYNSKI, P.E.
Acting Regional Administrator
U.S. Environmental Protection Agency
Region II

7/21/89
Date of Issuance

APPENDIX A

SCOPE OF WORK

**INTERIM ACTIONS
AT THE
LI TUNGSTEN SITE
63 HERB HILL ROAD
GLEN COVE, NEW YORK**

Prepared by:

**FRED C. HART ASSOCIATES, INC.
530 FIFTH AVENUE
NEW YORK, NEW YORK 10036-5166**

July 17, 1989

TABLE OF CONTENTS

1.0 Introduction	1
2.0 Purpose	3
3.0 Interim Actions	4
3.1 Site Security	4
3.1.1 Proposed Action	4
3.2 Radioactive Materials	5
3.2.1 Proposed Action	5
3.3 Laboratory Chemicals	6
3.3.1 Proposed Action	6
3.4 Drum Inventory and Removal	7
3.4.1 Proposed Action	7
3.5 Tank Characterization	7
3.5.1 Proposed Action	7
3.6 Asbestos	8
3.6.1 Proposed Action	8
3.7 Creek Sampling	9
3.7.1 Proposed Action	9
3.8 Transformer Oil Characterization	10
3.8.1 Proposed Action	10
3.9 Mercury Clean-up	10
3.9.1 Proposed Action	10

List of Figures

Figure 1 Site Map	2
-----------------------------	---

1.0 INTRODUCTION

The Li Tungsten facility (herein after referred to as the "Site") is located at 63 Herb Hill Road, Glen Cove, New York. The Site is 26 acres and consists of three separate parcels. The main operations at the Site were conducted on the parcel bordered by Glen Cove Creek to the south and Herb Hill Road to the north and a second parcel to the west of Dickson Lane. The parcel bordered by Herb Hill Road on the south and Dickson Lane on the west contains no facility structures. A map of the Site is provided in Figure 1.

Based on documents in the possession of the Glen Cove Development Company (GCDC) and obtained from records maintained at the Site the following background information was developed. The Site was operated from the 1940's to approximately 1985 by the Wah Chang Trading Company and its wholly owned subsidiary the Li Tungsten Corporation. The operation involved the processing of ore and scrap tungsten concentrates to ammonium paratungstate (APT) and subsequently formulating APT to metal tungsten powder and tungsten carbide powder. Other specialty products such as tungsten carbide powder plus cobalt and other material for plasma spraying; tungsten titanium carbide powder; tantalum carbide powder; tungsten spray powder; crystalline tungsten powder; and, molybdenum spray powder were also produced.

The property was acquired by GCDC in 1984 and leased to The Li Tungsten Corporation. The market for tungsten was apparently depressed by the 1980's and operations at the Li Tungsten facility had slowed by this time. The Li Tungsten operation declared bankruptcy in 1985.

GCDC is a New York State general partnership jointly owned by Old Court Joint Ventures, Inc. and Old Court Holdings Corporation, Inc., both of which in turn are wholly-owned subsidiaries of Old Court Savings and Loan, Inc. (in Receivership) located in Maryland.

-2-




Figure 1

Tungsten Facility

Fred C. Hart Associates, Inc. (HART) was retained by GCDC to coordinate implementation of interim actions to address certain environmental conditions at the Site. This scope of work (SOW) sets forth those proposed interim actions which were identified by the United States Environmental Protection Agency (USEPA) Region II pursuant to its authority under The Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) 42 U.S.C. Section 9601 et. seq. This scope of work is prepared as an attachment to the USEPA Administrative Order on Consent, Index No. II CERCLA-90215. The work proposed in this document will be consistent with practices described in:

"Characterization of Hazardous Waste Sites". NTIS PB87-120291, August 1985.

"Guidance Document for Clean-up of Surface Tank and Drum Sites". NTIS PB87-110672, May 1985.

"Drum Handling Practice at Hazardous Waste Sites". NTIS PB86-165362 OSHA, January 1986.

"29 CFR 1910.120 OSHA Regulations."

"EPA Standard Operating Safety Guidelines". OSWER 10/88.

All sampling and analyses performed by respondent shall conform to the USEPA quality assurance/quality control (QA/QC) and chain of custody procedures and in conformance with the USEPA publication entitled, Test Methods for Evaluating Solid Waste (SM-846 November 1986 as updated) and the USEPA document entitled, Guidance for Preparation of Combined Work/OA Project Plan for Environmental Monitoring (OAMS 005/80).

2.0 PURPOSE

This SOW outlines plans for interim actions at the Site. These interim actions were identified by the USEPA because of concerns regarding the stability and security of the Site. GCDC proposes to undertake

interim actions identified in this document pursuant to the aforementioned administrative order.

As stated during previous discussions with the USEPA, GCDC, through the Receivership, must comply with strict guidelines regarding the allocation of funds. To obtain approval for funding for one or more items, a fairly accurate cost estimate or range is required. The Circuit Court in Baltimore monitoring the Receivership must authorize expenditure of any funds. As a result, an order must be signed by the Circuit Court in Baltimore to formally allocate the funds to complete these interim actions. The court is expected to issue this order by June 12, 1989. GCDC through the receivership has obtained approval for a few of these items and has completed or is in the process of completing some of these actions.

3.0 INTERIM ACTIONS

The following interim actions were discussed at two meetings with the USEPA. Those interim actions which have already been completed (i.e. MEKP and cylinder removal) are not discussed or included on the schedule. The remaining interim actions and the plans for implementation are discussed in the following sections. A schedule for completion of these actions is also included.

3.1 Site Security

Based upon the USEPA reconnaissance of the Site, security was identified to be a major concern. Because of damage to the perimeter fence or the absence of a fence in some areas, access to the Site could not be controlled. Although one 24 hour guard is stationed and periodically patrols in a marked car outside the boundary of the Site, the USEPA believes that certain areas may not be readily accessible to a lone security patrol (northwestern boundary of the Site parcel just west of Dickson Lane). Therefore EPA requested that in addition to GCDC proceeding with fencing, the security patrol at the Site be upgraded.

3.1.1 Proposed Action. GCDC is proceeding with securing the Site perimeter with fencing. A priority will be given to installing a line of fence to impede access along the northwestern perimeter of the parcel located west of Dickson Lane. As of this date, all repairs have been made to the existing fence and gates. The fence posts along the northwestern parcel have been installed. Fencing in this area and between Chemco and the Site parcel north of Herb Hill Road is expected to be completed by June 23, 1989. Furthermore, GCDC has placed another security guard in a marked vehicle for the 8-hour shift from approximately 4:00 p.m. to midnight. This guard is stationed along the Site perimeter on Dickson Lane. A security presence in this area, for the period of time proposed, is intended to dissuade trespassers from entering the northwest Site parcel. During the course of implementing one or more of the interim actions, workers will be on-site during the day and it is less likely that unauthorized individuals will trespass. As certain interim actions are completed, (i.e. fencing completion etc.) GCDC would like the opportunity to downgrade the security force. Funds which do not have to be expended on guards can be targeted for additional stabilization and/or removal actions.

3.2 Radioactive Materials

USEPA has recommended the collection, staging and subsequent removal of isolated drums or containers of residual ore or slag that has exhibited elevated radioactivity readings. These drums or containers have been identified via preliminary radiological surveys conducted by Nassau County Department of Health (NCDOH) and listed in their status reports. The USEPA also did some preliminary radiological surveying and will provide maps depicting the location of the containers it identified to the extent it differs from those items in the NCDOH report.

3.2.1 Proposed Action. The NDL Organization has been contracted to undertake a comprehensive, real-time radiological survey both inside and outside the Site buildings. The purpose of this survey would be to identify any areas where on-site worker access needs to be restricted as a result of radioactivity levels and/or any special protective measures to

be taken while working in those areas. Since worker access to many areas of the Site will be required to complete other interim actions or future remedial work, this radiological survey is prudent and necessary. With the USEPA approval, this survey will include:

- 1) a gamma ray survey of the property and buildings on an approximate 25 foot x 25 foot grid;
- 2) Fixed and removable alpha radiation survey of buildings;
- 3) Collection and gamma spectral analysis of process material (and mud pond sediments);
- 4) Preparation of report summarizing the findings of the survey.

During the course of this radiological survey, readily accessible drums or containers which exhibit elevated readings will be moved to an agreed upon on-site location to which access can be restricted. Based on the results of the survey, up to fifteen (15) containers (including the ones previously identified at the Site) which are characterized as low level radioactive waste will be removed for disposal.

3.3 Laboratory Chemicals

Small quantities of identifiable laboratory chemicals have already been secured and placed in overpacks. In addition, small quantities of unidentified laboratory chemicals remain in some areas. USEPA has recommended characterization, overpacking and disposal, as needed, for all the laboratory chemicals.

3.3.1 Proposed Action. The existing laboratory overpacks will be removed for disposal. The chemicals in existing overpacks may have to be redistributed and placed in special containers. All existing laboratory overpacks which can be removed, as is, by ENSCO (the contractor who completed the overpacking) to its disposal facility will be done. Any remaining laboratory overpacks will be repackaged and reinventoried by the

selected disposal contractor. Any packing lists in compliance with the contractors packing guidelines will be spot checked for accuracy. The existing laboratory overpacks will be moved to a fully permitted transfer facility to await approval of the disposal site. The remaining unidentified laboratory chemicals will be characterized in the field. Up to 200 additional bottles, jars and/or containers will undergo a fingerprint analysis in an isolated area of the Site. This fingerprinting will be done under a portable fume hood. Based on these results, the chemicals will be appropriately packaged for off-site disposal.

3.4 Drum Inventory and Removal

USEPA has recommended the characterization and removal of drums containing chemicals (solid and liquid) at the Site. Specifically, USEPA referred to 50 to 100 units located in the Dickinson Warehouse area (northwest parcel).

3.4.1 Proposed Action. A number of drums containing liquids had been identified in the report prepared by RTP Environmental Associates, Inc. in May 1988. Based on the RTP report, approximately 108 drums of liquids were moved to inside the Dice Building (Main Facility Property). EPA's identification of 50 to 100 units (containers, drums, etc.) containing solid and liquids is in addition to the drums already placed in the Dice Building.

Based on this information, up to 250 drums of liquid/solid chemicals will be characterized for removal and disposal. The drummed contents will be screened for radioactivity in conjunction with the characterization for the purpose of bulking prior to detailed laboratory analysis for disposal. It is assumed that 125 drums will be characterized as waste water treatment candidates and 125 drums will be characterized as incineration candidates.

3.5 Tank Characterization

USEPA has recommended characterization of any liquids remaining in tanks at the Site. The purpose of this characterization would be to

(2131n-7)

determine if the contents of any tank warrants immediate removal; to identify the types of materials present in different locations so that the appropriate emergency services units are aware of materials on-site; and, ultimately, to ascertain the most practical treatment and disposal options for these liquids.

3.5.1 Proposed Action. Currently, the only inventory of the tanks on the Site and their contents is in the RTP report. According to the report, this inventory was based on a review of records at the Site and a walk-through with a former employee of Li Tungsten. In many instances the tank size and contents (as of May 1988) is indicated. This information does not preclude the need for a more definitive characterization. To accomplish this, representative on-site testing for parameters, including but not limited to, RCRA characteristics, metals and screening for radioactive materials may be the most practical approach. A request for bid (RFB) for this characterization will be solicited (see schedule). The approach and methodology to be used for this characterization will be provided to the USEPA prior to implementation. The results of the characterization will serve to identify the nature of the materials in tanks, their location and evaluate further actions.

3.6 Asbestos

USEPA stated its concern with the presence of large quantities of asbestos in certain areas of the Site. These concerns previously involved worker exposure.

3.6.1 Proposed Action. An asbestos abatement/removal project is more consistent when a long-term remedial program is implemented at the Site. The major concern regarding asbestos is to on-site workers during field activities. Therefore, in order to protect workers, access to areas which are known to contain large quantities of friable asbestos (Lounge Building Area) will be limited. These areas will be designated on a Site map in the Health and Safety Plan. Additional protective gear will be used by personnel working in these areas. Consistent with OSHA requirements, HART will set up ambient air sampling for a specific time period in the

vicinity of these areas to check whether fibers are being dispersed into the air stream. This work will be in addition to health and safety monitoring which will be implemented during the duration of on-site activities.

Two high volume air samples will be analyzed by phase contrast microscopy (PCM) to determine an eight hour time weighted average of asbestos concentration. PCM only determines the total number of fibers and does not distinguish between types of material. If OSHA standards are exceeded using PCM, another two air samples (taken at the same time) will be analyzed by transmission electron microscopy (TEM). In addition, between 25 to 50 bulk asbestos samples will be collected for analysis via polarized light microscopy with dispersion staining (PLMDS). Three to five samples will be collected of each homogeneous area and an estimate of the volume of material sampled, its percent asbestos, location and condition will be presented on a Site map.

3.7 Creek Sediment Sampling

USEPA has recommended that samples of sediment from the creek be obtained for analysis of appropriate radionuclides. The agency proposed these samples be obtained in the vicinity of the outfalls from the Site. According to available information, five (5) outfalls discharged from the Site to the creek when the facility operated. Therefore, five (5) sediment samples were requested.

3.7.1 Proposed Action. A creek sediment sampling program is premature and more in line with a long-term remedial study not a short, interim action. Nevertheless, five (5) creek sediment samples will be collected for radioactivity analysis only. The sampling and analysis will be done by personnel associated with New York University Medical Center, Institute of Environmental Medicine. The individuals will do the work as consultants to GCDC and not under the banner of the University. One sediment sample will be taken in the creek, east of the Site while three sediment samples will be collected in the vicinity of the outfalls and one sediment sample will be obtained from the western portion of the creek.

The samples will be placed in aluminum cans and assayed, (after one to two weeks), for gamma-emitting radionuclides (^{40}K , ^{137}Cs , ^{226}Ra -daughters, ^{228}Th -daughters and ^{228}Ra -daughters) using an intrinsic Ge detector. A portion of the sample will be removed and assayed radiochemically for ^{234}U , ^{238}U , ^{232}Th , ^{230}Th and ^{228}Th . Although the sample collection will be completed in a short period of time, the radionuclide analysis and report will require approximately 3 to 4 months.

3.8 Transformer Inventory and Characterization

USEPA has recommended the inventory of transformers at the Site and characterization of the oils inside the transformers. During its inspection, one transformer located outside a building on the main facility property appeared to have leaked onto the asphalt surface.

3.8.1 Proposed Action. HART has identified sixteen (16) transformers at the Site. The previous RTP report indicated twenty-one (21) transformers and two (2) oil circuit breakers. The contractor who completed the survey for RTP (Empire Environmental Services) will be contacted to account for these five (5) additional transformers and two (2) oil circuit breakers. In any event, a sample oil from the identified transformers will be collected for PCB analysis. Based on these analyses, arrangements for disposal and associated costs will be prepared.

3.9 Mercury Clean-up

An area inside the Benbow (Reduction) building was identified by the USEPA field reconnaissance team to have mercury on the floor. USEPA recommended this area be cleaned.

3.9.1 Proposed Action. Once the dimension of the area is defined, a field team in protective clothing will spread an absorbant lead based salt on the floor surface. The floor surface will be swept and the material placed in a plastic 55-gallon drum. All equipment used in the cleaning will also be placed in the drum. A representative sample (wipe or sweep) will be collected for mercury analysis after the clean-up is completed.

APPENDIX B
SCHEDULE OF COMPLIANCE

**INTERIM ACTIONS
AT THE
LI TUNGSTEN SITE
63 HERB HILL ROAD
GLEN COVE, NEW YORK**

Prepared by:

**FRED C. HART ASSOCIATES, INC.
530 FIFTH AVENUE
NEW YORK, NEW YORK 10036-5166**

July 17, 1989

TABLE OF CONTENTS

1.0 Estimated Schedule 1

List of Figures

Figure 1 Estimated Schedule of Interim Actions. . . 2

1.0 ESTIMATED SCHEDULE

An estimated schedule for the implementation of the interim actions described in this SOW is presented in Figure 2. The time lines include mobilization, field activities and necessary laboratory analysis. Footnotes for each of the listed items are also included. Although the estimated schedule indicates that work will start once an interim order is established, a number of items are ongoing or have already been completed. To the extent practical, interim actions will be completed in short time frames.

HART will provide a bi-monthly status report to the USEPA which summarizes the on-going or completed activities and transmits relevant documentation. The recipients of these status reports are indicated in the order on consent.




FIGURE 2

Estimated Schedule
Interim Actions at Li Tungsten

FRED C. HART ASSOCIATES, INC.

Notes:

* Start date coincides with interim order

- 1: Fencing is ongoing. Estimated completion is June 23rd. Security guards (one 24 hr. and one 8 hr.) are also provided at the Site.
- 2: Radiological survey to be conducted by the NDL Organization. Currently scheduled to begin the week of June 19, 1989.
- 3: Previously identified containers exhibiting elevated radioactivity readings will be staged in the wire plant. Once survey is completed, up to fifteen containers, characterized as low level radioactivity waste, will be removed from the Site.
 - 3a: This time line reflects the staging of containers exhibiting elevated radioactivity levels in the wire plant building.
 - 3b: This time line reflects removal of up to fifteen containers characterized as low level radioactive waste once laboratory analysis and disposal site arrangements are completed.
- 4: Initiation of laboratory pack removal to immediately follow radiological survey time frame allows for mobilization, random checking of packing inventories against drum contents, repackaging if necessary, and removal to appropriate staging or disposal facility.
- 5: Unknown laboratory chemical characterizations will be completed in an isolated area using a fume hood.
- 6: Drum characterization assumes a total of 250 drums (125 for waste water treatment analysis and 125 for incineration analysis).
- 7: Drum removal (see 6) to begin following receipt of detailed laboratory analysis.
 - 7a: Time frame to review laboratory results of drums and arranging for appropriate disposal of up to 250 drums.
 - 7b: Time frame to remove up to 250 drums to an approved disposal facility.
- 8: Tank contents characterization includes identifying which tanks contain liquids and their approximate volumes.
 - 8a: Time frame to soliciting competitive bids, review and select contractor and notify USEPA prior to implementation.
 - 8b: Time frame to complete the tank characterization.
- 9: Time frame, to monitor/sample for asbestos. Includes two high volume air samples and between 25 and 50 bulk samples for laboratory analysis.

10: Creek Sampling will be scheduled.

10a: Radionuclide analysis and reporting to be completed in approximately 3 months

11: Characterization of transformer oils to follow radiological survey.

12: Mercury on floor of Benbow Building to be cleaned.

13: Summary Report of completed Interim Actions.

REFERENCE NO. 26

104105

Fred C. Hart Associates, Inc.



September 21, 1989

Mr. Charles Fitzsimmons
Environmental Engineer-OSC
USEPA Region II
Woodbridge Avenue
Edison, New Jersey 08837

New York, NY
Albany, NY
Boston, MA
Cherry Hill, NJ
Detroit, MI
Hartford, CT
Irvine, CA
Jacksonville, FL
Liberty Corner, NJ
Pittsburgh, PA
Sacramento, CA
Washington, DC
Houston, TX
West Chester, PA

Re: Partial Laboratory Results of Air and Bulk Samples - Li Tungsten

Dear Mr. Fitzsimmons:

Enclosed are copies of the analytical results which have been received by HART. These include air samples for asbestos, metals and volatile organics from a number of indoor and outdoor sampling points at the Li Tungsten facility in Glen Cove.

The asbestos air results are contained on a single data sheet from Laboratory Testing Services. These air samples were obtained from five locations, four of which were inside buildings. A summary sheet of the results of air samples for metals is attached to the laboratory data sheets. Also, a summary sheet for the air samples for volatile analysis is attached to the laboratory data sheets. These volatile air samples were obtained inside the laboratories on the main parcel (A). Where applicable, the TLV for a specific volatile compound is noted. The results of air samples for inorganic acid gases have not yet been received from the laboratory.

A total of 51 bulk samples were collected for analysis of asbestos containing materials. The results of this analysis including a description and map of the sample location is also in this package.

Sincerely,

James A. Perazzo
Associate-Manager of Geosciences

104106

Asbestos Bulk Sampling Data - (06/26 - 06/27/89)

<u>Number</u>	<u>Type</u>	<u>Analysis</u>
ASB 1.	Trowelled on tank insulation	69% Chrysotile
ASB 2.	Black paper/fabric matrix behind ASB 1	5% Chrysotile
ASB 3.	Block material supported by wide mesh hanging from tank	45% Amosite
ASB 4.	Pipe insulation between tanks L9D and L9C	No asbestos detected (NAD)
ASB 5.	Pipe joint compounds on elbow (of ASB 4)	60% Chrysotile
ASB 6.	Floor dust (near APT)	NAD
ASB 7.	Stacked pipe insulation (preformed)	60% Amosite
ASB 8.	Hanging insulation on pipes (preformed)	60% Amosite
ASB 9.	Pipe insulation associated with Tank 85	30% Amosite 20% Chrysotile 2% Crocidolite
ASB 10.	Outside wall (block with flakes)	10% Chrysotile
ASB 11.	Wall board, 2nd level, northern section	NAD
ASB 12.	Trowelled on tank insulation above anhydrous tank	NAD
ASB 13.	Block material (same area as ASB 12)	NAD
ASB 14.	Wall material (east inner wall - along stairwell)	NAD
ASB 15.	Plasterboard from locker room - 2nd level	NAD
ASB 16.	Preformed block insulation, roof on locker room	20% Amosite 20% Chrysotile

<u>Number</u>	<u>Type</u>	<u>Analysis</u>
ASB 17.	White powder beneath overhead piping (same as ASB 16)	NAD
ASB 18.	Insulation on small furnace	25% Amosite 25% Chrysotile
ASB 19.	Plaster board particles - collapsed on floor	NAD
ASB 20.	Ceiling tile - collapsed on floor	NAD
ASB 21.	Pipe joint compound (1st lab from wire plant)	20% Amosite 35% Chrysotile 2% Crocidolite
ASB 22.	Solid insulation on pipe (same area as ASB 21)	30% Amosite 30% Chrysotile 15% Crocidolite
ASB 23.	Duplicate (of ASB 22)	25% Amosite 30% Chrysotile 5% Crocidolite
ASB 24.	Ceiling board (brown)	NAD
ASB 25.	Safe interior (insulation) debris on floor	NAD
ASB 26.	Pipe insulation in boiler room	25% Chrysotile
ASB 27.	Insulation debris fallen from overhead pipe rack	40% Amosite 15% Chrysotile
ASB 28.	Refractory cement spill on wet floor in machine shop	NAD
ASB 29.	Mineral wool (white boxes in machine shop)	NAD
ASB 30.	Pipe (overhead) insulation - preformed	35% Amosite 20% Chrysotile
ASB 31.	Outside coating on tank 35	30% Chrysotile
ASB 32.	Pipe (overhead) insulation between tank 35 and 36	NAD
ASB 33.	Refractory material on underside of furnace 105	NAD
ASB 34. (2173n-2)	Refractory block - in drum, outside SW corner of Dice	<1% Amosite

<u>Number</u>	<u>Type</u>	<u>Analysis</u>
ASB 35.	Pipe insulation - dropped from overhead rack	<1% Chrysotile
ASB 36.	Wall board (just inside from stack)	NAD
ASB 37.	Insulation around flue coming out of stack area	80% Chrysotile 40% Amosite
ASB 38.	Troweled on cement (same as ASB 37)	45% Chrysotile
ASB 39.	Pipe insulation - inside boiler area	35% Amosite 20% Chrysotile
ASB 40.	Fibreboard, warehouse stack	NAD
ASB 41.	Refractory lining in furnace	NAD
ASB 42.	Pipe insulation stacked	40% Amosite 10% Chrysotile 5% Crocidolite
ASB 43.	Wall board - west wall	NAD
ASB 44.	Wall board - west wall	NAD
ASB 45.	Slag on floor	NAD
ASB 46.	Deteriorized wall board	NAD
ASB 47.	Deteriorized pipe insulation, fallen on ground - outside	NAD
ASB 48.	Pipe insulation in boiler room	30% Amosite 20% Chrysotile
ASB 49.	Corrugated fibreboard insulation on floor	2% Chrysotile
ASB 50.	Roof panel in corner office	NAD
ASB 51.	Preformed pipe insulation - white, on furnace	40% Amosite 30% Chrysotile

Applied Environmental Technology, Inc.

a subsidiary of WAVETECH inc.

316 Cooper Center
Pennsauken, N.J. 08109 (609) 486-9200

August 2, 1989

Hart Environmental
530 Fifth Avenue
New York, NY 10036

ATTEN: Karl Boldt

RE: Lab #: L070701
Project No. 00265-02-00035-01
Bulk Sample Analyses

Dear Mr. Boldt:

Applied Environmental Technology, Inc., located at 316 Cooper Center, Pennsauken, New Jersey, analyzed the following samples on June 29, 1989

DATA SUMMARY BULK SAMPLE ANALYSIS

<u>Sample No.</u>	<u>Sample Description</u>	<u>Approximate Percentage Asbestos Composition</u>
1-8766-47	Trowled on tank Insulation	69% Chrysotile
2-8766-48	Black outer cover on tank	05% Chrysotile
3-8766-49	Insulation block on tank	45% Amosite
4-8766-50	Corrugated pipe insulation	No Asbestos Detected (NAD)
5-8766-51	Pipe joint	60% Chrysotile
6-8766-52	Floor dust	(NAD)
7-8766-53	Loose pipe insulation (pre-formed)	60% Amosite
8-8766-54	White (pre-formed) pipe insulation	60% Chrysotile

Applied
Environmental
Technology, Inc.

<u>Sample No.</u>	<u>Sample Description</u>	<u>Approximate Percentage Asbestos Composition</u>
9-8766-55	White (pre-formed) block insulation	30% Amosite 20% Chrysotile 02% Crocidolite
10-8766-56	Asphalt wall coating	10% Chrysotile
11-8766-57	Wallboard	(NAD)
12-8766-58	Trowled on tank insulation	(NAD)
13-8766-59	(Pre-formed) block insulation	(NAD)
14-8766-60	Wall plaster	(NAD)
15-8766-61	Plaster board	(NAD)
16-8766-62	(Pre-formed) block insulation	20% Amosite 20% Chrysotile
17-8766-63	Fallen white debris	(NAD)
18-8766-64	Furnace insulation	25% Amosite 25% Chrysotile
19-8766-65	Plaster board	(NAD)
20-8766-66	Ceiling tile	(NAD)
21-8766-67	Pipe insulation	20% Amosite 35% Chrysotile 02% Crocidolite
22-8766-68	Pipe insulation	30% Amosite 30% Chrysotile 15% Crocidolite
23-8766-69	Pipe insulation	25% Amosite 30% Chrysotile 05% Crocidolite

Applied
Environmental
Technology, Inc.

<u>Sample No.</u>	<u>Sample Description</u>	<u>Approximate Percentage Asbestos Composition</u>
24-8766-70	Cellulose wallboard	(NAD)
25-8766-71	Safe insulation	(NAD)
26-8766-72	Pipe insulation	25% Chrysotile
27-8766-73	Fallen white debris	40% Amosite 15% Chrysotile
28-8766-74	Refractory cement	(NAD)
29-8766-75	Mineral wool	(NAD)
30-8766-76	White (pre-formed) pipe insulation	35% Amosite 20% Chrysotile
31-8766-77	Tank coating	30% Chrysotile
32-8766-78	Pipe insulation	(NAD)
33-8766-79	Refractory	(NAD)
34-8766-80	Refractory debris	<1% Amosite
35-8766-81	Fallen debris (HH)	<1% Chrysotile
36-8766-82	Wall board	(NAD)
37-8766-83	White (pre-formed) insulation	20% Chrysotile 40% Amosite
38-8766-84	Trowled on cement	45% Chrysotile
39-8766-85	Pipe insulation	35% Amosite 20% Chrysotile
40-8766-86	Fiber board	(NAD)
41-8766-87	Refractory	(NAD)

Applied
Environmental
Technology, Inc.

<u>Sample No.</u>	<u>Sample Description</u>	<u>Approximate Percentage Asbestos Composition</u>
42-8766-88	White (pre-formed) insulation	40% Amosite 10% Chrysotile 05% Crocidolite
43-8766-89	Wall board	(NAD)
44-8766-90	Wall board	(NAD)
45-8766-91	Slag	(NAD)
46-8766-92	Deteriorated wall board	(NAD)
47-8766-93	Deteriorated insulation	(NAD)
48-8766-94	White (pre-formed) pipe insulation	30% Amosite 20% Chrysotile
49-8766-95	Corrugated pipe insulation	02% Chrysotile
50-8766-96	Roof panel	(NAD)
51-8766-97	White (pre-formed) pipe insulation	40% Amosite 30% Chrysotile

ANALYTICAL TECHNIQUES

Analyses of bulk samples are performed according to Environmental Protection Agency Interim Method 600/M4-82-020. Each bulk sample undergoes both a gross examination under low power magnification to establish the presence and percentage of fibrous and non-fibrous components, and an examination under high power magnification to provide positive identification of these fibrous and some non-fibrous components.


The first examination is performed with a stereo microscope and an external illuminator. Each bulk sample is emptied onto a weighing paper and examined for layering, homogeneity and the presence of fibrous and non-fibrous materials. An estimation of the percentage of each component relative to the whole sample is made.

The second examination is performed with a polarizing light microscope (PLM). A sub-sample of the bulk sample is selected at the conclusion of the first examination, mounted onto a slide, treated with a fluid having an appropriate index of refraction, and examined using the PLM. The polarizing light microscopy procedure identifies the characteristics of the sub-sample components with transmitted polarizing light, crossed polars, slightly uncrossed polars, crossed polars plus the first order red compensator, and the central stop dispersion staining objective. The observations obtained using the various techniques are used to identify fibrous and some non-fibrous components on the basis of morphology, sign of elongation, and refractive index/dispersion staining colors.

QUALITY CONTROL

The Industrial Hygiene Services Laboratory conducts general quality control procedures as recommended by the National Institute for Occupational Safety and Health, the Environmental Protection Agency and the American Industrial Hygiene Association.

Additionally, the laboratory is a successful participant in both the American Industrial Hygiene Association/National Institute for Occupational Safety and Health Proficiency Analytical Testing (PAT) Program (Identification Number 08104-001), and the Environmental Protection Agency/Research Triangle Park Bulk Asbestos Quality Assurance Program (Identification Number 2180).



Joseph Mandrino,
Managing Director



Name: KARL GOLDT
 Affiliation: F. C. HART ASSOC.
 Phone: (212) 840-3770
 Address: 530 FIFTH AVE. NEW YORK, NY 10036
 Client/Job No: 00265-02 00035-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 1	8766-42	6/26/89	1150	BULK	1	TROWELED-ON TANK INS.
ASB 2	8766-48					BLK. OUTER COVER ON TANK
ASB 3	8766-49					INS. BLOCK ON TANK
ASB 4	8766-50					CORRUGATED PIPE INS.
ASB 5	8766-51					PIPE JOINT INS.
ASB 6	8766-52					FLOOR DUST
ASB 7	8766-53					LOOSE PIPE INS. (PRE-FORMED)
ASB 8	8766-54					WHITE PRE FORMED PIPE INS.
ASB 9	8766-55					WHITE PRE-FORMED INS. BLOCK
ASB 10	8766-56					ASPHALT WALL COATING

Comments: ALL SAMPLES ANALYZED FOR ASBESTOS (PLM)

Relinquished by: Karl Goldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643707070

Received by: [Signature] Date: 6-29-89 Relinquished by: _____ Date: _____
 Time: 9:45 AM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____

Name: KARL BOLDTAffiliation: F.C. HART ASSOC.Phone: (212) 840-3990Address: 530 FIFTH AVE., NEW YORK, NY, 10036Client/Job No: 00265-02-00035-01Job Name: LI TUNGSTENLocation: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 11	8766-57	6/26/89	1233	BULK	1	WALL BOARD
ASB 12	8766-58					TROWELED-ON TANK INS.
ASB 13	8766-59					PRE-FORMED BLOCK INS.
ASB 14	8766-60					WALL PLASTER
ASB 15	8766-61					PLASTER BOARD
ASB 16	8766-62					PRE-FORMED BLOCK INS.
ASB 17	8766-63					FALLEN WHITE DEBRIS
ASB 18	8766-64					FURNACE INS.
ASB 19	8766-65					PLASTER BOARD
ASB 20	8766-66	↓	↓	↓	↓	CEILING CEILING TILE

Comments: ALL SAMPLES ANALYZED FOR ASBESTOSRelinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
Time: 5 PM Airbill No.: 9643704070Received by: John L. Hume Date: 6-29-89 Relinquished by: _____ Date: _____
Time: 9:45 AM Time: _____Received by: _____ Date: _____ Relinquished by: _____ Date: _____
Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____



Name: KARL BOLDT
 Affiliation: F. C. HART ASSOC
 Phone: (212) 840-3390
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Client/Job No: 00265-02 00035-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 21	8766-67	6/24/89	1350	BULK	1	PIPE INS.
ASB 22	8766-68					PIPE INS.
ASB 23	8766-69					PIPE INS.
ASB 24	8766-70		↓			CELLULOSE WALLBOARD
ASB 25	8766-71		1612			SAFE INS.
ASB 26	8766-72					PIPE INS.
ASB 27	8766-73					FALLEN WHITE DEBRIS
ASB 28	8766-74					REFRACTORY CEMENT
ASB 29	8766-75		↓			MINERAL WOOL
ASB 30	8766-76		1850	↓	↓	WHITE PRE-FORMED PIPE INS.

Comments: ALL SAMPLES ANALYZED FOR ASBESTOS

Relinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704070

Received by: [Signature] Date: 6-29-89 Relinquished by: _____ Date: _____
 Time: 9:45 AM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____



Name: KARL BOLDT
 Affiliation: F.C. HART ASSOC
 Phone: (212) 840-3710
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Client/Job No: 00265-02-00035-01
 Job Name: L1 TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 31	8766-77	6/26/89	1850	BULK	1	TANK COATING
ASB 32	8766-78					PIPE INS. (FG)
ASB 33	8766-79					REFRACTORY
ASB 34	8766-80					REFRACTORY DEBRIS
ASB 35	8766-81		↓			FALLEN DEBRIS (HH)
ASB 36	8766-82		1745			WALLBOARD
ASB 37	8766-83					WHITE PRE-FORMED INS. FALLEN DEBRIS (HH)
ASB 38	8766-84					TROWELED-ON CEMENT
ASB 39	8766-85	↓	↓	↓		PIPE INS.
ASB 40	8766-X6	6/27/89	1004	↓	↓	FIBERBOARD

Comments: ALL SAMPLES ANALYZED FOR ASBESTOS

Relinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704070

Received by: [Signature] Date: 6-29-89 Relinquished by: _____ Date: _____
 Time: 9:45 AM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____



Name: KARL BOLDT
 Affiliation: F.C. HART ASSOC.
 Phone: (212) 840-3990
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Client/Job No: 00265-02-00035-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 41	8766-87	6/27/89	1008	BULK	1	REFRACTORY
ASB 42	8766-88					WHITE PRE-FORMED INS.
ASB 43	8766-89					WALLBOARD
ASB 44	8766-90					WALLBOARD
ASB 45	8766-91					SLAG
ASB 46	8766-92					DETERIORATED WALL BOARD
ASB 47	8766-93					DETERIORATED INS.
ASB 48	8766-94		1045			WHITE PRE-FORMED PIPE INS.
ASB 49	8766-95					CORRUGATED PIPE INS.
ASB 50	8766-96					ROOF PANEL

Comments: ALL SAMPLES ANALYZED FOR ASBESTOS

Relinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704070

Received by: John W. Krum Date: 6-29-89 Relinquished by: _____ Date: _____
 Time: 9:45 AM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____



Name: KARL BOLDT
 Affiliation: F.L. HART ASSOC.
 Phone: (212) 840-3790
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Client/Job No: 00265-02-00035-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ASB 57	8766-97	6/27/89	11:12	BULK	1	WHITE PRE-FORMED PIPE INS.

Comments: ALL SAMPLES ANALYZED FOR ASBESTOS


Relinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704070

Received by: Steven Whelan Date: 6-29-89 Relinquished by: _____ Date: _____
 Time: 9:45am Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____



Received by: _____ Date: _____ Time: _____



104121

32/22/7

WIDE DEPT AREA



104122

VOC CONCENTRATION SUMMARY

	ug/sample (ug/m ³)			
	VOC-2	VOC-3	VOC-4	ACGIH
	Lab NW	Lab E	Blank	TLV
Chloromethane	<1.0	<1.0	<1.0	
Bromomethane	<1.0	<1.0	<1.0	
Vinyl chloride	<1.0	<1.0	<1.0	
Chloroethane	<1.0	<1.0	<1.0	
Methylene chloride	0.6B(5.7B)	0.6 (5.9)	2.6	(175,000)
Acetone	<1.0	<1.0	<1.0	
Carbon disulfide	<0.5	<0.5	<0.5	
1,1-Dichloroethene	<0.5	<0.5	<0.5	
1,1-Dichloroethane	<0.5	<0.5	<0.5	
Total-1,2-Dichloroethene	<0.5	<0.5	<0.5	
Chloroform	<0.5	0.2J(2.0J)	0.3J	(50,000)
1,2-Dichloroethane	<0.5	<0.5	<0.5	
2-Butanone	<1.0	<1.0	<1.0	
1,1,1-Trichloroethane	<0.5	0.3J(2.9J)	0.3J	(1,900,000)
Carbon tetrachloride	<0.5	0.1J(1.0J)	0.2J	(30,000)
Vinyl acetate	<0.1	<0.1	<0.1	
Bromodichloromethane	<0.5	<0.5	<0.5	
1,1,2,2-Tetrachloroethane	<0.5	<0.5	<0.5	
1,2-Dichloropropane	<0.5	<0.5	<0.5	
Trans-1,3-Dichloropropene	<0.5	<0.5	<0.5	
Trichloroethene	<0.5	<0.5	<0.5	
Benzene	<0.5	<0.5	<0.5	
cis-1,3-Dichloropropene	<0.5	<0.5	<0.5	
2-Chloroethylvinylether	<1.0	<1.0	<1.0	
Bromoform	<0.5	<0.5	<0.5	
2-Hexanone	<1.0	<1.0	<1.0	
4-Methyl-2-Pentanone	<1.0	<1.0	<1.0	
Tetrachloroethene	<0.5	<0.5	<0.5	
Toluene	<0.5	<0.5	<0.5	
Chlorobenzene	<0.5	<0.5	<0.5	
Ethylbenzene	<0.5	<0.5	<0.5	
Styrene	<0.5	<0.5	<0.5	
Total Xylenes	<0.5	<0.5	<0.5	
Total Dichlorobenzene	<3.0	<3.0	<3.0	

B - also found in lab blank

J - estimated value

Laboratory Testing Services

RESULTS - continued:

TEM RESULTS SUMMARY FORM

PROJECT NAME: 00265-02-00035-01

DATE: July 7, 1989

CLIENT: Fred C. Hart Associates

PROJECT NO.:

ATTENTION: Karl Boldt

LAB. NO.: 89-02534

SAMPLING AGENCY: Fred C. Hart Associates

SAMPLING SITE: Li Tungsten, Glen Cove, New York

SAMPLING DATE: June 26, 1989-June 27, 1989

NO. OF SAMPLES SUBMITTED: Five (5)

RESULTS:

Sample	LTS ID#	Sample Volume (liters)	Sensitivity (Structures/cm ³)	Filter Concentration (Structures/mm ²)	Air Concentration (Structures/cm ³)
01	T-00304	1170	0.0047	<14.29	<0.0047
02	T-00305	936	0.0049	<11.90	<0.0049
03	T-00306	1058	0.0047	12.99	0.0047
04	T-00307	933	0.0049	<11.90	<0.0049
05	T-00308	904	0.0051	11.90	0.0051

< = LESS THAN

Transmission electron microscopy analysis was conducted in accordance with the analytical procedures described in 40 CFR Part 763 appendix A to subpart E.

Edward R. D. Smith
ANALYST(S)

(3)

Mark Young
MARK YOUNG
TEM DIRECTOR


0, 14/89 12:46:00
SAMPLE: FRED C. HART, VOC-4/N9-9560, REC'D 7/7/89, LOGIN 1874
CONDS.: TUBE/2MLS, 100UL/5ML INSTD
RANGE: G 1,1300 LABEL: N 0, 4.0 QUAN: A 0, 1.0 J 0 BASE: U 20, 3


DATA: D8947 #101

SCANS 25 TO 1300

CALI: D8947 #2

194304.





Name: KARL BOLDT
 Affiliation: HART FRED C. HART ASSOC., INC.
 Phone: 520 FIFTH AVE. (212) 840-3990
 Address: NEW YORK NY 10036
 Client/Job No: 00265-02-00003-01
 Job Name: LITUNESTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
IOA-2		7/7/89	4 PM	SORBENT TUBE	1	INORGANIC ACIDS NIOSH METHOD 7300
IOA-3						
IOA-4						
VOC-2						VOCs NEI METHOD
VOC-3						
VOC-4						

Comments: _____

Relinquished by: Karl Boldt Date: 7/7/89 Shipment Method: By Hand
 Time: 5 PM Airbill No.: _____

Received by: Christa Sygel Date: 7/7/89 Relinquished by: _____ Date: _____
 Time: 5 PM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____

Laboratory Testing Services

LAB. NO.: 89-02534

**REPORT OF TRANSMISSION ELECTRON
MICROSCOPY TESTS
FOR
AIRBORNE ASBESTOS FIBER DETERMINATION
FOR**

F.C. HART ASSOCIATES

**530 5th STREET
NEW YORK, NEW YORK 10036**

JULY 7, 1989

Laboratory Testing Services

LAB. NO.: 89-02534

CLIENT: Fred C. Hart Associates
530 5th Street
New York, New York 10036
Attention: Karl Boldt

MATERIAL: Room Air

CLIENT'S ORDER NO.: 20663

TEST FOR: Detection and Identification of suspected
Asbestos in Five (5) air samples as
determined by Transmission Electron
Microscopy (TEM) with Selected Area Electron
Diffraction (SAED) and Energy Dispersive
X-Ray Microanalysis (EDX).

1.0 BACKGROUND:

F.C. Hart Associates, Inc. collected five (5) air samples for airborne asbestos fiber determination at Li Tungsten, Glen Cove, New York. The samples were received on June 19, 1989.

2.0 PROCEDURE:

Transmission Electron Microscopy (TEM) with Selected Area Electron Diffraction (SAED) and Energy Dispersive X-Ray Microanalysis (EDX) were employed to detect and identify suspected asbestos in the above referenced air samples. The analytical method was conducted in accordance with analytical procedures described in 40 CFR Part 763 Appendix A to Subpart E.

(1)

Laboratory Testing Services

LAB. NO.: 89-02534

3.0 APPLICABLE QUALIFICATIONS:

Laboratory Testing Services, Inc. maintains an interim accreditation for Transmission Electron Microscopy by the New York State Department of Health (NYSDOH) Environmental Laboratory Approval Program (ELAP Identification #10837).

Laboratory Testing Services, Inc. is an American Industrial Hygiene Association accredited (#333) laboratory.

4.0 RESULTS:

Enclosed are an electron micrograph, selected area electron diffraction pattern, and elemental composition report of a representative chrysotile and non-asbestos structure.

The following results were obtained:

(2)

Laboratory Testing Services

RESULTS - continued:

TEM RESULTS SUMMARY FORM

PROJECT NAME: 00265-02-00035-01

DATE: July 7, 1989

CLIENT: Fred C. Hart Associates

PROJECT NO.:

ATTENTION: Karl Boldt

LAB. NO.: 89-02534

SAMPLING AGENCY: Fred C. Hart Associates

SAMPLING SITE: Li Tungsten, Glen Cove, New York

SAMPLING DATE: June 26, 1989-June 27, 1989

NO. OF SAMPLES SUBMITTED: Five (5)

RESULTS:

Sample	LTS ID#	Sample Volume (liters)	Sensitivity (Structures/cm ³)	Filter Concentration (Structures/mm ²)	Air Concentration (Structures/cm ³)
01	T-00304	1170	0.0047	<14.29	<0.0047
02	T-00305	936	0.0049	<11.90	<0.0049
03	T-00306	1058	0.0047	12.99	0.0047
04	T-00307	933	0.0049	<11.90	<0.0049
05	T-00308	904	0.0051	11.90	0.0051

< = LESS THAN

Transmission electron microscopy analysis was conducted in accordance with the analytical procedures described in 40 CFR Part 763 appendix A to subpart E.

Edward R. D. Smith
ANALYST(S)

(3)

Mark Young
MARK YOUNG
TEM DIRECTOR

5.0 DISCUSSION OF RESULTS:

The Occupational Safety and Health Administration (OSHA) has established standards for airborne asbestos fiber concentrations in an occupational environment. The permissible exposure level (PEL) based on an eight hour Time Weighted Average (TWA) is 0.2 fibers per cubic centimeter (f/cc) of air. According to the standard, the employer shall ensure that no employee is exposed to an airborne asbestos fiber concentration above the PEL.

Additionally, OSHA has established a TWA action level of 0.1 asbestos f/cc. Asbestos air concentrations at or above the action level require the employer initiate procedures to periodically monitor employee exposure.

New York State has established an air concentration of 0.01 f/cc as an acceptable clearance level for post abatement air quality. In "Guidance for Controlling Asbestos-Containing Materials in Buildings" as measured by Transmission Electron Microscopy (TEM), 0.005 f/cc has been referenced as a typical outdoor ambient airborne asbestos concentration in urban areas (Chatfield, 1983). It would be impractical to expect indoor air asbestos concentrations to be less than outdoor concentrations. Therefore, outdoor levels would appear to be the most appropriate baseline for comparison to indoor concentrations.

It must be noted that air monitoring measures only current conditions and provides no information about fiber release potential and future air levels. The EPA recommends a building survey be conducted to evaluate the degree of risk from asbestos-containing materials in buildings.

Laboratory Testing Services


LAB. NO: 89-02534

6.0 CERTIFICATION AND SIGNATURES:


We certify this report is a true and authentic report of results obtained from our tests.

Respectfully submitted,

LABORATORY TESTING SERVICES, INC.



Brian Heneveld
Vice President



David C. Harvey
President

CS

(5)

Report on sample by client applies only to sample.

Report on samples by us applies only to lot sampled.

Information contained herein is not to be used for reproduction except by special permission.

Samples retained for thirty days maximum after date of report unless specifically requested otherwise by client. The liability of the Laboratory Testing Services, Inc. with respect to the services charged for herein, shall in no event exceed the amount of the invoice.

laboratory Testing Services

LAB NO: 89-02534

APPENDIX A
RESULTS OF TEM ANALYSIS

laboratory Testing Services

RESULT SHEET FOR TEM ASBESTOS AIR SAMPLE

CLIENT: Fred C. Hart Associates

DATE: July 7, 1989

SAMPLE NO.: 01

LTS NO.: T-00304

NO. OF GRID OPENINGS ANALYZED: 10

LAB. NO.: 89-02534

AVG. GRID OPENING AREA: 0.0070 mm²

VOLUME: 1170 liters

TOTAL AREA ANALYZED: 0.070 mm²

SENSITIVITY: 0.0047 Structure/cm³

MANUFACTURER: Nucleopore

FILTER SIZE: 385 mm²

LOT NO.: 81C3A/710/A8

COMPOSITION: Polycarbonate (.4um)

TOTAL NUMBER OF STRUCTURES: 8

TOTAL NUMBER OF ASBESTOS STRUCTURES: 0

MICROGRAPH #'S

1101-1102

STRUCTURE CLASSIFICATION

1) CHRYSOTILE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

2) AMPHIBOLE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

3) NON-ASBESTOS STRUCTURES

FIBERS	7	BUNDLES	0	CLUSTERS	0	MATRICES	1	TOTAL	8
--------	---	---------	---	----------	---	----------	---	-------	---

	<u>.5< STRUCTURES <5um</u>	<u>>5um</u>	<u>TOTAL</u>
--	----------------------------------	----------------	--------------

ASBESTOS CONC. ON FILTER
(STRUCTURES/mm²)

--

--

<14.29

ASBESTOS CONC. IN AIR
(STRUCTURES/cm³)

--

--

<0.0047

(A1)

laboratory Testing Services

RESULT SHEET FOR TEM ASBESTOS AIR SAMPLE

CLIENT: Fred C. Hart Associates

DATE: July 7, 1989

SAMPLE NO.: 02

LTS NO.: T-00305

NO. OF GRID OPENINGS ANALYZED: 12

LAB. NO.: 89-02534

AVG. GRID OPENING AREA: 0.0070 mm²

VOLUME: 936 liters

TOTAL AREA ANALYZED: 0.084 mm²

SENSITIVITY: 0.0049 Structure/cm³

MANUFACTURER: Nucleopore

FILTER SIZE: 385 mm²

LOT NO.: 81C3A/710/A8

COMPOSITION: Polycarbonate (.4um)

TOTAL NUMBER OF STRUCTURES: 16

TOTAL NUMBER OF ASBESTOS STRUCTURES: 0

MICROGRAPH #'S: 1103-1104

STRUCTURE CLASSIFICATION

1) CHRYSOTILE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

2) AMPHIBOLE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

3) NON-ASBESTOS STRUCTURES

FIBERS	13	BUNDLES	0	CLUSTERS	1	MATRICES	2	TOTAL	16
--------	----	---------	---	----------	---	----------	---	-------	----

<u>.5< STRUCTURES</u>	<u><5um</u>	<u>>5um</u>	<u>TOTAL</u>
--------------------------	----------------	----------------	--------------

ASBESTOS CONC. ON FILTER
(STRUCTURES/mm²)

--

--

<11.90

ASBESTOS CONC. IN AIR
(STRUCTURES/cm³)

--

--

<0.0049

(A2)

laboratory Testing Services

RESULT SHEET FOR TEM ASBESTOS AIR SAMPLE

CLIENT: Fred C. Hart Associates

DATE: July 7, 1989

SAMPLE NO.: 03

LTS NO.: T-00306

NO. OF GRID OPENINGS ANALYZED: 11

LAB. NO.: 89-02534

AVG. GRID OPENING AREA: 0.0070 mm²

VOLUME: 1058 liters

TOTAL AREA ANALYZED: 0.077 mm²

SENSITIVITY: 0.0047 Structure/cm³

MANUFACTURER: Nucleopore

FILTER SIZE: 385 mm²

LOT NO.: 81C3A/710/A8

COMPOSITION: Polycarbonate (.4um)

TOTAL NUMBER OF STRUCTURES: 8

TOTAL NUMBER OF ASBESTOS STRUCTURES: 1

MICROGRAPH #'S

1105-1108

STRUCTURE CLASSIFICATION

1) CHRYSOTILE STRUCTURES

FIBERS	1	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	1
--------	---	---------	---	----------	---	----------	---	-------	---

2) AMPHIBOLE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

3) NON-ASBESTOS STRUCTURES

FIBERS	4	BUNDLES	0	CLUSTERS	1	MATRICES	2	TOTAL	7
--------	---	---------	---	----------	---	----------	---	-------	---

.5< STRUCTURES <5um

>5um

TOTAL

ASBESTOS CONC. ON FILTER
(STRUCTURES/mm²)

12.99

--

12.99

ASBESTOS CONC. IN AIR
(STRUCTURES/cm³)

0.0047

--

0.0047

(A3)

laboratory Testing Services

RESULT SHEET FOR TEM ASBESTOS AIR SAMPLE

CLIENT: Fred C. Hart Associates

DATE: July 7, 1989

SAMPLE NO.: 04

LTS NO.: T-00307

NO. OF GRID OPENINGS ANALYZED: 12

LAB. NO.: 89-02534

AVG. GRID OPENING AREA: 0.0070 mm²

VOLUME: 933 liters

TOTAL AREA ANALYZED: 0.084 mm²

SENSITIVITY: 0.0049 Structure/cm³

MANUFACTURER: Nucleopore

FILTER SIZE: 385 mm²

LOT NO.: 81C3A/710/A8

COMPOSITION: Polycarbonate (.4um)

TOTAL NUMBER OF STRUCTURES: 15

TOTAL NUMBER OF ASBESTOS STRUCTURES: 0

MICROGRAPH #'S

1109-1110

STRUCTURE CLASSIFICATION

1) CHRYSOTILE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

2) AMPHIBOLE STRUCTURES

FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0	TOTAL	0
--------	---	---------	---	----------	---	----------	---	-------	---

3) NON-ASBESTOS STRUCTURES

FIBERS	9	BUNDLES	0	CLUSTERS	5	MATRICES	1	TOTAL	15
--------	---	---------	---	----------	---	----------	---	-------	----

<u>.5< STRUCTURES</u>	<u><5um</u>	<u>>5um</u>	<u>TOTAL</u>
--------------------------	----------------	----------------	--------------

ASBESTOS CONC. ON FILTER
(STRUCTURES/mm²)

--

--

<11.90

ASBESTOS CONC. IN AIR
(STRUCTURES/cm³)

--

--

<0.0049

(A4)

laboratory Testing Services

RESULT SHEET FOR TEM ASBESTOS AIR SAMPLE

CLIENT: Fred C. Hart Associates

DATE: July 7, 1989

SAMPLE NO.: 05

LTS NO.: T-00308

NO. OF GRID OPENINGS ANALYZED: 12

LAB. NO.: 89-02534

AVG. GRID OPENING AREA: 0.0070 mm²

VOLUME: 904 liters

TOTAL AREA ANALYZED: 0.084 mm²

SENSITIVITY: 0.0051 Structure/cm³

MANUFACTURER: Nucleopore

FILTER SIZE: 385 mm²

LOT NO.: 81C3A/710/A8

COMPOSITION: Polycarbonate (.4um)

TOTAL NUMBER OF STRUCTURES: 6

TOTAL NUMBER OF ASBESTOS STRUCTURES: 1

MICROGRAPH #'S 1111-1112

STRUCTURE CLASSIFICATION

1) CHRYSOTILE STRUCTURES							
FIBERS	1	BUNDLES	0	CLUSTERS	0	MATRICES	0
							TOTAL 1
2) AMPHIBOLE STRUCTURES							
FIBERS	0	BUNDLES	0	CLUSTERS	0	MATRICES	0
							TOTAL 0
3) NON-ASBESTOS STRUCTURES							
FIBERS	5	BUNDLES	0	CLUSTERS	0	MATRICES	0
							TOTAL 5

	<u>.5< STRUCTURES <5um</u>	<u>>5um</u>	<u>TOTAL</u>
ASBESTOS CONC. ON FILTER (STRUCTURES/mm ²)	11.90	--	11.90
ASBESTOS CONC. IN AIR (STRUCTURES/cm ³)	0.0051	--	0.0051

(A5)

Laboratory Testing Services

LAB. NO.: 89-02534

APPENDIX B

CHAIN of CUSTODY RECORDS

Laboratory Testing Services

75 URBAN AVENUE, WESTBURY, NEW YORK 11590 • (516) 334-7770 • (800) 433-0008 • FAX NO. 516-334-7720

CLIENT: F.C. Hart Assoc.

CHAIN OF CUSTODY RECORD

Lab No.		Sample Location (Address)		ANALYSIS										REMARKS		
Outside Services Project Name		Sample Identification		Volume Of Air Collected	ASBESTOS-PCM	ASBESTOS-PLM	ASBESTOS-TEM	WETCHEM (spec/ly)	GC (spec/ly)	GC/MS (spec/ly)	AA (spec/ly)	B/C (spec/ly)	I.P. (spec/ly)	OHSAT (spec/ly)	OTHER (spec/ly)	ADDITIONAL REQUIREMENTS
01	6/26	1	TEM 1	1170		✓										
02	1	1	TEM 2	936		✓										
03	↓	↓	TEM 3	1050		✓										
04	6/27	↓	TEM 4	933		✓										
05	6/27	↓	TEM 5	904		✓										
Shipped Via: Federal Express # 9643704081																
Retrieved by (Signature)		Date/Time		Agent of		Rec'd by (Signature)		Date/Time		Agent of						
Printed Name						Claire Steppan		6/29/01 am		LTS						
Retrieved by (Signature)		Date/Time		Agent of		Rec'd by (Signature)		Date/Time		Agent of						
Claire Steppan		6/29/01 am		LTS		Claire Steppan										
Retrieved by (Signature)		Date/Time		Received for Laboratory by (Signature)		Date/Time		Remarks								
Printed Name				Printed Name		6/29/01 11:50 am										
Sampler (Signature)		Samplers Name (Print)														
		Em. D. Milrator														

104140

Laboratory Testing Services

LAB.NO.: 89-02534

APPENDIX C

PRINTS OF ELECTRON PHOTOMICROGRAPHS

104141

Laboratory Testing Services

**MICROGRAPH #1106
ELECTRON MICROGRAPH OF A REPRESENTATIVE
NON-ASBESTOS STRUCTURE
(ORIGINAL MAGNIFICATION = 19,000X)**



**MICROGRAPH #1105
SELECTED AREA ELECTRON DIFFRACTION (SAED) PATTERN OF A
NON-ASBESTOS STRUCTURE
(CAMERA CONSTANT = 22.54 mmÅ)**



Laboratory Testing Services

S306A6A Micrograph #1106

AUS/ON

S306A6A

CA LL

CUR:


0.0

0CNTS

2000FS

51 T

Energy Dispersive X-ray
Analysis (EDXA) of a
Non-Asbestos Structure




07-JUL-89 18:10

Laboratory Testing Services

**MICROGRAPH #1108
ELECTRON PHOTOMICROGRAPH OF A REPRESENTATIVE
CHRYSTILE ASBESTOS STRUCTURE
(ORIGINAL MAGNIFICATION = 19,000X)**



**MICROGRAPH # 1107
SELECTED AREA ELECTRON DIFFRACTION (SAED) PATTERN OF
A CHRYSTILE ASBESTOS STRUCTURE
(CAMERA CONSTANT = 22.54 mmÅ)**



Laboratory Testing Services

9306B7A Micrograph #1108

40840N

9306B7A

MG K α

CUR:


0.0

0CNTS

60FS

400

T



07-JUL-89 18:17

104145

RIC

07/14/89 10:48:00

SAMPLE: F.C.HART,UOC-2/N9-9558,REC'D 7/7/89


COND5.: TUBE/2MLS,100UL/5ML INSTD

RANGE: G 1,1300 LABEL: N 0, 4.0 QUAN: A 0, 1.0 J 0 BASE: U 20, 3

DATA: D8945 #1070

CALI: D8945 #2

SCANS 25 TO 1300



APPENDIX A

SCOPE OF WORK

**INTERIM ACTIONS
AT THE
LI TUNGSTEN SITE
63 HERB HILL ROAD
GLEN COVE, NEW YORK**

Prepared by:

**FRED C. HART ASSOCIATES, INC.
530 FIFTH AVENUE
NEW YORK, NEW YORK 10036-5166**

July 17, 1989

HYDROGEOLOGIC INVESTIGATION
AT THE LI TUNGSTEN FACILITY
GLEN COVE, NEW YORK

April 1988

Geraghty & Miller, Inc.
Ground-Water Consultants
125 East Bethpage Road
Plainview, New York 11803

TABLE OF CONTENTS

	<u>Page</u>
INTRODUCTION	1
BACKGROUND	2
METHODOLOGY	5
Installation of Monitoring Wells	5
Sampling of Monitoring Wells	9
Soil Survey	10
EXPANDED SCOPE OF WORK	12
Additional Wells	12
Well-Head Protection	13
Laboratory Analyses	14
Surveying	14
HYDROGEOLOGY	14
WATER QUALITY	17
VOCs	17
Inorganics	19
Metals	19
Nonmetals	20
Hydrocarbons	21
SOIL QUALITY	21
REMEDIATION	23
Ground-Water Remediation	23
FINDINGS AND CONCLUSIONS	27
REFERENCES	32

TABLE OF CONTENTS (Continued)

TABLES

1. Summary of Monitoring Well Construction Details, Li Tungsten Facility, Glen Cove, New York.
2. Summary of Ground-Water Elevation Data for Monitoring Wells at Li Tungsten Facility, Glen Cove, New York.
3. Concentration of Volatile Organic Compounds Detected in Ground-Water Samples Collected in Spring 1987 and Spring 1988 at Li Tungsten Facility, Glen Cove, New York.
4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.
5. Concentrations of Selected Volatile Organic Compounds Tested for During Soil Survey of Parcels II, III, and IV.

FIGURES

1. Site Location, Li Tungsten Facility, Glen Cove, New York.
2. Location of Monitoring Wells, Li Tungsten Facility, Glen Cove, New York.
3. Soil Survey Locations, Li Tungsten Facility, Glen Cove, New York.
4. Configuration of Water Table on April 26, 1988.
5. Inferred Extent of Plume of VOCs in Shallow Ground-Water System in the Vicinity of Li Tungsten Facility, Glen Cove, New York.

APPENDICES

- A. Sample Core Logs.
- B. Well Construction Diagrams.
- C. Health and Safety Plan.

TABLE OF CONTENTS (Continued)

APPENDICES (Continued)

- D. Water Sampling Logs.
- E. Laboratory Reports: Water Samples Collected Spring 1987 and Spring 1988.
- F. Laboratory Reports: Soil Sample from Well GM-14A.

HYDROGEOLOGIC INVESTIGATION
AT THE LI TUNGSTEN FACILITY
GLEN COVE, NEW YORK

INTRODUCTION

Geraghty & Miller, Inc. (G&M) was retained by RTP Environmental Associates, Inc. (RTP) in March 1988 to conduct a hydrogeologic investigation of the Li Tungsten facility in Glen Cove, New York. The purpose of this investigation was to determine ground-water quality of the shallow ground-water system beneath the site and to determine whether sources of volatile organic compounds (VOCs) were present beneath the unpaved areas of the site. One particular objective of this investigation was to delineate a VOC plume that had been indicated by a previous G&M investigation in the spring of 1987. This report describes the most recent G&M investigation (March to April 1988), which was conducted concurrently with investigations by other environmental consultants who had been retained by RTP to assess other environmental aspects of the Li Tungsten site.

The possible regulatory implications of ground-water and soil-quality conditions of the site (as determined by the G&M soil survey) are discussed in this report, and remedial alternatives are addressed in a preliminary fashion. Cost estimates and time frames for the remedial alternatives

are also included. It must be stressed, however, that regulatory review and approval of remedial alternatives must be obtained in advance of specifying a recommended set of remedial options. Since actions by regulators cannot be predicted with a high degree of confidence, the scope of ground-water and other environmental clean-up activities may differ from that which is discussed in this report.

The scope of work for G&M's investigation included the following: installation of 13 shallow monitoring wells; collection of soil samples from selected well borings; collection of ground-water quality samples from 21 monitoring wells; surveying of monitoring wells and waste piles; collection of water-level data; and performing a soil survey.

BACKGROUND

The Li Tungsten facility is located in northern Nassau County, Glen Cove, New York, in an industrial area. Consisting of approximately 20 acres, the site is situated on the north bank of Glen Cove Creek, which drains west into Hempstead Harbor (Figure 1). From the 1940s to the early 1980s, tungsten ores, imported from mainland China, were smelted at this facility. Recently, it has been inactive and now alternatives are being considered to develop the properties.

For the purposes of this investigation, the site has been divided into four parcels: I, II, III, and IV. A site map showing the individual parcels is presented in Figure 2. Parcel IV, which is not part of Li Tungsten, adjoins Parcel II and at RTP's request, was included in this investigation. The total area being investigated is comprised of approximately 24 acres.

This hydrogeologic investigation of the Li Tungsten facility was preceded by at least two previous investigations. The first investigation was not conducted by G&M and is reported to have taken place in the early 1980s when five monitoring wells were installed. Data collected during this first investigation were not available to G&M for review. However, G&M inspected and tested these wells as part of the second investigation and judged them to be in adequate condition for water-level and general water-quality monitoring, despite the lack of well-head protection and information about their installation. Therefore, these five monitoring wells were used as monitoring points for the G&M investigation.

The second investigation was conducted by G&M in the spring of 1987 for RTP and Old Stone Development Corporation. G&M supervised the installation of five additional wells during this investigation and used four of the five existing monitoring wells as monitoring points (the fifth

well had not been discovered until the most recent investigation in the spring of 1988). Ground-water samples were collected from the existing wells for analyses for VOCs and for selected inorganic compounds before the new wells were sampled. As a result of the spring 1987 sampling, high concentrations of VOCs (approximately 20 parts per million [ppm] total) were detected in Well EMW-1, one of the original monitoring wells. Since VOCs were reportedly not used at the site, this discovery became the focus of the investigation and five monitoring wells were then installed at locations which would better define the VOC contamination.

One of the new locations, Well GM-3D, was installed as a cluster well (two wells) to Well EMW-1 to monitor the zone 10 ft below the bottom of Well EMW-1. The other wells (GM-1, GM-2, GM-4, and GM-5) were installed to obtain more information about the ground-water quality conditions at the site. Upon completion, the five new monitoring wells were sampled and the existing monitoring wells were resampled and analyzed for VOCs and selected inorganics. High concentrations of VOCs were confirmed in Well EMW-1 and were also detected in Well GM-3D, thus indicating a VOC plume with a depth greater than 20 feet. VOCs were either not detected or were detected in relatively low concentrations in the other wells sampled. G&M's second site investigation in the


spring of 1987 was discontinued after these preliminary findings.

This most recent investigation involved the installation of 13 new monitoring wells and utilizes the two prior investigations and the ten existing monitoring wells to provide a more extensive evaluation of the ground-water quality conditions beneath the three parcels comprising the Li Tungsten site, as well as beneath a fourth parcel (Parcel IV), which is adjacent to Parcel II. The results of this investigation confirm and expand the ground-water flow and chemistry data collected by G&M during the spring 1987 work.

METHODOLOGY

Installation of Monitoring Wells

The hollow-stem auger drilling method was used for the 18 monitoring wells installed under G&M's supervision. Wells GM-1 through GM-5 were installed between April 9, 1987 and April 21, 1987 by Slacke Test Borings, Inc., Kings Park, New York, and Wells GM-6 through GM-17 were installed between March 31, 1988 and April 15, 1988 by Empire Soils Investigations, Inc., Highland Park, New Jersey. The locations of these wells and the five wells installed during a previous investigation are shown on Figure 2.



EXPLANATION

II

PARCEL NUMBER
 PROPERTY/PARCEL BOUNDARY



MONITORING WELL LOCATION




INFERRED EXTENT OF VOC PLUME WITH CONCENTRATION OF 100 ppb OR GREATER


NOTE: REFER TO TABLE 3 FOR CONCENTRATIONS OF VOCs DETECTED IN MONITORING WELLS SAMPLED IN SPRING 1987 AND SPRING 1988

INFERRED EXTENT OF PLUME OF VOCs IN SHALLOW GROUND-WATER SYSTEM IN THE VICINITY OF LI TUNGSTEN, GLEN COVE, NEW YORK

104157

FIGURE
5





Prepared by RTP Environmental Associates, Inc.

Figure 2. Li Tungsten Facility Site Plan.

Split-spoon samples of the formation were collected at 5-ft intervals in each borehole during the two G&M investigations. Split-spoon samplers were decontaminated either by steam cleaning or by using a MicroTM solution followed by a distilled water rinse. The samples collected from each borehole were described by an on-site G&M hydrogeologist. Sample core logs are presented in Appendix A.

Soil samples from selected boreholes were retained for laboratory analysis. Soil samples from Wells GM-9, GM-10, and GM-11 were submitted to Enviropact Northeast, Inc., (Enviropact) Yonkers, New York, another consultant to RTP, for VOC analyses. Samples of the drill cuttings from Well GM-14A were sent to EcoTest Laboratories, Inc., North Bellmore, New York, for analysis of VOCs, polychlorinated biphenyls (PCBs), total petroleum hydrocarbons (TPHC), and selected metals using extraction procedure (EP) testing methods.

Upon completion of the borehole, 2-inch diameter PVC screen and casing was installed inside the augers with the 10-ft long screen extending partially above the water table. An artificial gravel filter pack was emplaced around the well screen through the inside of the augers from the bottom of the borehole to at least 1 ft above the top of the screen. A layer of bentonite pellets was emplaced above the

7

gravel pack to seal the screen zone from potential contamination from the surface. The remaining annular space was filled with a cement/bentonite grout mixture.

All the wells were completed with locking, protective well-head assemblies. Wells located in active areas were completed with flush-mounted, curb box assemblies. The remaining wells were completed with aboveground protective casings. Well construction details for the G&M wells and the five previously installed wells (EMW wells) are presented in Table 1. Well construction diagrams are presented in Appendix B.

As mentioned above, all the monitoring wells were installed with the well screens extending partially above the water table, except Wells GM-3D and GM-14A. Well GM-3D was installed as a cluster well to Well EMW-1 where high concentrations of VOCs had been found during the first G&M investigation (spring 1987).

Well GM-14A was installed downgradient of a reported fuel spill on Parcel II; however, the nature of formation materials made the water table difficult to locate without waiting an extended period of time for water-level stabilization. The well screen was set entirely below the stabilized water level, and this observation was used to

construct another well, GM-14B, approximately 10 ft north of Well GM-14A to monitor for a possible floating phase.

As a health and safety measure, air monitoring equipment (HNU and OVA) was used by the on-site hydrogeologist to monitor the breathing zone for volatile compounds. VOCs were not encountered at any time during the drilling program as indicated by the above monitoring. The Health and Safety Plan (HASP) followed by G&M and its subcontractors is presented in Appendix C.

Most of the wells were developed by using a centrifugal pump to evacuate several volumes of water or until the water pumped was relatively clear and sediment-free. This procedure ensures good hydraulic interconnection between the well screen and the surrounding formation. Well GM-10 was developed by bailing because the water level was beyond the suction limit of a centrifugal pump. Although the water level was at the surface (within suction limit), Well GM-16 was also developed by bailing because this well was installed on the same day it was sampled. The elevation of the measuring point of the 23 new and existing monitoring wells was surveyed to the nearest 0.01 ft and the horizontal location of the wells were measured by Baldwin & Cornelius, Engineers and Surveyors, Freeport, New York. Well GM-17, had not been installed when surveying occurred and since the surveying could not be delayed, this well was not surveyed.

Sampling of Monitoring Wells

A total of 21 monitoring wells was sampled between April 7, 1988 and April 15, 1988. On April 7 and 8, 1988, the nine wells which had been installed during the most recent investigation and the five wells from the first site investigation were sampled. The remaining seven wells were sampled on April 15, 1988, following installation. The only on-site wells not sampled were GM-14B, which is being used to monitor for a floating liquid phase downgradient of a reported oil spill, and Well GM-17 which was installed after sampling took place. Samples were collected according to USEPA guidelines.

Prior to collection of ground-water samples, between three and five well volumes were evacuated from each well by bailing or by pumping. Samples were collected from each well by means of a TeflonTM bailer which was lowered into the well using new, polypropylene rope. All bailers were decontaminated using a MicroTM solution followed by a distilled water rinse. For wells evacuated by means of a centrifugal pump, new polyethylene tubing was used.

Samples were collected for the following analyses: VOCs and selected inorganic parameters (metals and nonmetals). The selection of the analytical parameters was based on

plant uses and processing of materials at Li Tungsten and on preliminary testing by Enviropact, Inc.

All samples collected for metals analyses were field-filtered through an 0.45-mm filter membrane and preserved with nitric acid (HNO_3). At the end of each day of sampling, samples were hand-delivered to EcoTest Laboratories, Inc., North Babylon, New York. Water sampling logs for the 21 wells sampled are presented in Appendix D.

Soil Survey

On April 21 and 22, 1988, G&M conducted a survey of the surficial soils at the Li Tungsten facility using a portable gas chromatograph (GC) to determine whether VOCs were present in soils at the site. The survey was focused on the unpaved areas (portions of Parcels II, III, and IV) where dumping or spilling of VOCs would most likely have occurred.

The Photovac (Model 10S50) GC used for this survey has the capability to identify and quantify VOCs in the field. Based on data that had been previously gathered at the Li Tungsten site, the portable GC was calibrated for three specific compounds: 1,2-dichloroethene, trichloroethylene, and tetrachloroethene. Prior to any analysis, the GC was calibrated with a 1-ppm standard of these three compounds. Next, a distilled water blank was tested. The technique

104164

used by G&M to test the soil samples facilitates measurement of VOCs even at low concentrations and is described below.

Soil samples were collected from the upper 0.5 ft of the soil and transferred to 40 milliliter (ml) glass vials. Each vial was filled halfway with soil and capped and returned to the station where the GC was set up. Prior to analysis, 20 ml of distilled water was added to each sample. The sample was then agitated for 1 minute. Next, a 300-microliter (ul) sample of the headspace above the soil/water mixture was injected into the GC for analysis.

The soil samples were collected from shallow holes excavated with a hand trowel. Between each use, the hand trowel was cleaned using a MicroTM solution followed by a distilled water rinse. A new pair of disposable vinyl gloves was used for handling each sample. Parcel III was studied in the greatest detail since this parcel is unpaved and covered mostly by woods, except for a cleared area along Herb Hill Road formerly used for parking. Buried drums and piles of solid residues were observed in this area.

A grid system, consisting of 21 sample locations, was established for Parcel III. The sampling locations are shown on Figure 3. Additional samples were collected along the fence separating Parcel III from a former dry cleaning facility.

104165

A total of nine soil samples was collected along a dirt road in Parcel IV where dumping would most likely have taken place. This road was overgrown with weeds and other secondary growth and had to be cleared in order to install Wells GM-10, GM-11, and GM-12. Aerial photographs of the site (circa 1960) reveal this road to be clear and free of vegetation, indicating that it was once being used regularly.

A total of five soil samples was also collected from Parcel II immediately north of the Reduction Building. This area drains runoff from topographically higher areas in the vicinity of the propane tank where piles of solid residue are located. VOCs that may have been disposed of near or with the solid residues would most likely be transported by runoff to the drainage area north of the Reduction Building on Parcel II where the samples were collected.

EXPANDED SCOPE OF WORK

Additional Wells

During the most recent investigation at the site, the scope of work was expanded at the request of Campon Realty Corporation and RTP to include the installation of three additional monitoring wells on Parcel I. These wells were planned in the vicinity of two proposed canals included in

the planned residential development on this parcel. The purpose of this additional work was to obtain more information on the subsurface environment with respect to bulkheading structures and disposal of materials which may be dredged from the canals.

Of the three proposed monitoring wells, only Well GM-17 was installed. The other two proposed wells were not installed because of concern that contamination in the shallow ground-water system would potentially be introduced to deeper hydrogeologic zones during drilling operations. Since there was insufficient time for adequate site preparation to eliminate this new concern, the additional drilling was cancelled.

Ground-water samples were not collected from Well GM-17; however, this well was developed and used for water-level measurements.

Well-Head Protection

Protective, locking, well-head assemblies were installed on four of the five unprotected wells (EMW-2, EMW-3, EMW-4, and EMW-5) installed during the first site investigation. This was done to protect against vandalism as these wells had been previously unprotected. Also, a locking curb box assembly was installed at Well GM-4 because

the original curb box was apparently destroyed during snow removal operations near the new warehouse on Parcel II.

Laboratory Analyses

The list of analytical parameters for ground-water samples was expanded to include compounds detected by Enviropact's analyses of soil and solid residues. Additionally, at the request of RTP, soil samples from well borings GM-14A and GM-17 were sent to EcoTest for analyses of VOCs, TPHC, PCBs, and metals using EP testing methods.

Surveying

During the surveying of the monitoring wells, RTP, in conjunction with Enviropact, requested that piles of solid residues on Parcels II and III be surveyed so that volumes of these materials could be calculated. This information would be used by Enviropact to estimate costs for removal and disposal of these materials.

HYDROGEOLOGY

The Li Tungsten facility is underlain by unconsolidated deposits of sand, silt, and clay, totaling more than 500 ft thick, which overlie the crystalline bedrock surface (Swarzenski, 1963). The uppermost stratigraphic unit is of

Upper Pleistocene age and is part of the Harbor Hill ground moraine. This deposit is thin in the Li Tungsten vicinity and ranges from 5 ft to as much as 40 ft in thickness and consists of a heterogeneous mixture of sand, silt, clay, and boulders. Boulders were not encountered during the field program except during the drilling of Well GM-15 just below the concrete slab. However, boulders with diameters of 1 ft to 3 ft were observed in the wooded areas of Parcels III and IV.

Beneath the Harbor Hill ground moraine lies another sequence of Upper Pleistocene deposits known as Harbor Hill drift, which comprises the Upper Glacial aquifer in the vicinity of the site. The thickness, of the Upper Glacial aquifer at the site is approximately 150 ft to 200 ft (Kilburn, 1987).

Geologic logs for wells in the vicinity of the site indicate that the Magothy Formation is absent. The Upper Glacial aquifer rests unconformably on the clay member of the Raritan Formation, approximately 200 ft below the site. To the west and east, there is another confining unit known as the Port Washington Clay.

Between April 13, 1988 and April 18, 1988, Baldwin & Cornelius, P.C., Freeport, New York, surveyed the measuring points of 22 of the 23 monitoring wells to the nearest 0.01

ft. (GM-17 was not installed during surveying activities.) These data were used to calculate water-level elevations from measurements made on April 21 and April 26, 1988. A summary of water-level elevation data for these two dates is presented in Table 2. A contour map of the water-table surface was prepared from the water-level data collected on April 26, 1988 (see Table 2) and is presented on Figure 4.

This map indicates that ground water in the shallow ground-water system flows south toward Glen Cove Creek, which is consistent with published data (Kilburn, 1987). It is also apparent that perched-water conditions exist at the site. Perched water is observed in the northern half of the plant in Wells GM-4, GM-5, GM-11, GM-12, GM-13, and GM-16 (Figure 4). The water-level elevation data also suggest that locally, perched ground water exists in the vicinity of Wells GM-9 and GM-14B. Perched water conditions are also recognized in the literature for the area (Swarzenski, 1963). When water percolating through surficial soils encounters a relatively-impermeable layer of silt or clay, its downward movement is stopped or impeded causing water to accumulate locally as perched ground water.

The water level in Well GM-14B was 3.61 ft higher in elevation than in Well GM-14A on April 26, 1988. Since both of these wells were adequately developed, the water-level difference must be the result of local perched water which

is intercepted by GM-14B. The elevation of perched water at GM-14B may also be increased by ponding of rainwater in the dike surrounding the fuel oil tank.

WATER QUALITY

VOCs

All analytical results of ground-water samples collected at Li Tungsten will be discussed in terms of the New York State Department of Environmental Conservation (NYSDEC), Division of Water Technical and Operational Guidance Series, dated July 24, 1985 (TOGS). TOGS references in this report are used solely as reference points for comparative purposes and are not to be construed as applicable clean-up standards.

The results of the VOC analyses for samples collected in spring 1987 and spring 1988 are summarized in Table 3. Laboratory reports for the VOC analyses are presented in Appendix E. These results identify two areas with high concentrations of VOCs in the shallow ground-water system.

The first area where high concentrations of VOCs occur (from 78 ppb to more than 22,000 ppb total) were detected in monitoring wells on the southern portion of Parcel III (Wells EMW-1, GM-3D, GM-8, and GM-9) and in Monitoring Well GM-6 on the northern part of Parcel I, directly downgradient

of the wells mentioned above. These data indicate the presence of a plume of VOCs in the shallow ground-water system that appears to be emanating from an unknown source on the southeastern part of Parcel III between Wells GM-7 and GM-9. It is likely that the contamination is from an off-site source. The adjacent property is reported to have been occupied by a dry cleaning operation several years ago and dry cleaners commonly use tetrachloroethene in their cleaning operations. This compound was the VOC detected in the highest concentrations in the wells defining the plume. The other two VOCs detected in high concentrations are trichloroethene and 1,2-dichloroethene. Both of these compounds are produced during the decomposition of tetrachloroethene.

High concentrations of VOCs were also detected in Well GM-10 (360 ppb total). This well is located in the southernmost part of Parcel IV on the edge of a steep drop-off approximately 30 ft north of the fence separating the Mattiace property to the south (Superfund site) from Parcel IV to the north. The compound occurring in highest concentrations in this well was 1,1,1-trichloroethane. Tetrachloroethene and its decomposition products were also detected in this well. The extent, and source of, the contamination detected in this well is not known.

VOCs were not detected in the wells installed in the perched ground-water zone in the northern part of the site, except in Well GM-13 in a low concentration totaling 13 ppb. This well is installed in an area where solid residues from the smelting operation were disposed.

VOCs were either not detected or detected in relatively low concentrations (less than 100 ppb) in the remaining wells at the site. The inferred extent of the VOC plume (with total VOC concentrations of 100 ppb or greater) is shown on Figure 5.

Inorganics

Metals

A summary of the results of the metals analyses for the monitoring wells sampled in spring 1987 and spring 1988 are presented in Table 4. Laboratory reports for the metals analyses are presented in Appendix E.

Of the 13 metals analyzed, four were found to exceed and/or equal the TOGS values (lead, chromium, cadmium, and arsenic). The TOGS value for lead (0.025 ppm) was exceeded in Wells EM-3 (0.060 ppm), EMW-4 (0.075 ppm), and GM-14A (0.070). Chromium was only detected in Well GM-14A in a concentration equal to the TOGS value (0.050 ppm). Cadmium was detected in concentrations exceeding the TOGS value

(0.010 ppm) in Wells EMW-1 (0.040 ppm), EMW-3 (0.029 ppm), EMW-5 (0.017 ppm), GM-3D (0.020 ppm), and GM-8 (0.013 ppm). Although there is no TOGS value for tungsten, this metal was found in monitoring wells throughout the site. Solid residues of spent tungsten ores are known to have been disposed of in at least two areas of the site: the center of Parcel III, and on Parcel II northwest of the Reduction Building. In addition, solid residues are stored in deteriorated drums and crates throughout the site. These practices are likely the source of the tungsten found in the ground water beneath the site.

Nonmetals

Of the three nonmetals analyzed for in spring 1987 and spring 1988, chloride and sulfate were found in concentrations exceeding the TOGS values. Nitrate was not found in concentrations exceeding the TOGS value in any of the wells sampled.

Chloride was detected in concentrations exceeding the TOGS value in five wells: EMW-3 (1,900 ppm), EMW-4 (2,700 ppm), EMW-5 (740 ppm), GM-6 (260 ppm), and GM-14A (700 ppm). All these wells are located in the southwestern area of the site in the vicinity of the wastewater treatment system.

Sulfate was detected in concentrations exceeding the TOGS values in eight wells: EMW-1 (400 ppm), EMW-3 (1,100 ppm), EMW-3 (3,300 ppm), EMW-5 (450 ppm), GM-3D (350 ppm), GM-6 (450 ppm), GM-13 (430 ppm), and GM-14A (11,000 ppm). Most of these wells are also located in the southwestern area of the site in the vicinity of the wastewater treatment system.

In summary, the detections of inorganics exceeding TOGS values for the respective parameters were concentrated in monitoring wells located in the vicinity of the wastewater treatment system in the southwestern part of the site. Tungsten detected in monitoring wells at the site most likely results from disposal and storage activities practiced at the site.

Hydrocarbons

No floating phase of hydrocarbons was found in monitoring Wells EMW-3, EMW-5, and GM-14B when measurements were made in these wells (which are located downgradient of two reported spills at the site).

SOIL QUALITY

On April 21 and 22, 1988, using a portable GC, G&M conducted a survey of the surficial soils in unpaved areas of

the site to determine whether VOCs were present. The results of the survey are summarized in Table 5.

In all, 36 soil samples were collected from Parcels II, III, and IV, and were analyzed for the targeted compounds (tetrachloroethene, trichloroethene, and 1,2-dichloroethene). The sample locations are shown on Figure 3. Tetrachloroethene was the only compound detected, and it occurred in two of the 36 samples analyzed. This compound was found at sample locations PS-1 and PS-2 in low concentrations of less than 10 ppb. Both of these samples were collected along the fence in the southeast part of Parcel III. No other VOCs were detected in any of the other samples collected at the site.

The results of this survey indicate that VOCs may not have been disposed of on the surficial soils in the areas studied. Since the focus of the survey was on areas where dumping of VOCs would most likely take place, it does not seem likely that dumping of VOCs has recently occurred. Two soil samples were collected from the drill cuttings from Well GM-14A, which is located downgradient of a reported fuel spill on Parcel II. The two samples were composited by EcoTest Laboratories, Inc. and analyzed for VOCs, PCBs, total petroleum hydrocarbons (TPHC), and metals using EP testing methods. The results of these analyses are summa-

rized in Table 6, and the laboratory report is presented in Appendix F.

VOCs and PCBs were not detected in any of the samples analyzed. Arsenic was the only metal detected (0.041 ppm) which is below the federal standard of 5 ppm (40 CFR Section 261.24, Table 1, Section B). However, TPHC was detected in a concentration of 330 ppm. Although there is no standard in the State of New York for this parameter, the detection represents a high concentration and the regulatory response is uncertain.

REMEDIATION

Ground-Water Remediation

The plume of VOCs in the ground water which extends from Parcel III to Parcel I under Herb Hill Road will probably require remediation in accordance with New York State law. Although the plume does not appear to have the potential to affect any potable water source, it is moving in the direction of Glen Cove Creek and, therefore, will represent a long-term contaminant discharge to the environment if left unabated. Remediation of this VOC plume is technically feasible by employing a ground-water pumping-and-treatment system whereby contaminated water is pumped from the aquifer, the contaminants removed by air stripping or carbon adsorption, and the treated water is returned to the aquifer

or discharged to surface water. The pump-and-treat system may be enhanced by source removal, soil vapor stripping, and the installation of hydraulic barriers to reduce water pumping rates.

The sediments which comprise the water-table aquifer in the VOC plume area at Li Tungsten are not permeable enough to permit continuous pumping with vertical wells. For this reason, a series of horizontal collector trenches with gravel-packed, perforated pipes might be a better choice for ground-water recovery. The system would require collection of ground water on Parcel I between the Carbide and Dice buildings to prevent further southward plume migration. The remediation would be enhanced by intercepting ground water on both sides of Herb Hill Road where the plume is most concentrated and by excavating the most contaminated sediments in the area of Wells EMW-1 and GM-3D. It might also be possible to remove additional VOCs by soil venting or soil vapor stripping under vacuum, but it would be necessary to conduct pilot testing of soil from these areas to determine whether induced vapor removal would work under the relatively low permeability conditions known to exist at the site. Likewise, it is difficult to estimate the time for plume cleanup without pilot testing; however, a 5- to 10-year period of operation is considered the minimum under comparable circumstances. Installation of a soil vapor recovery system in the area of highest VOC concentrations

would be between \$25,000 and \$30,000 in capital cost, plus an annual operation and maintenance cost of \$3,000 to \$5,000.

The cost of constructing a similar pump-and-treat system in Nassau County, Long Island, is approximately \$250,000 in capital costs, plus an approximate \$75,000 annual operation and maintenance cost. Monitoring the effectiveness of the system in accordance with New York State Department of Environmental Conservation (NYSDEC) guidelines would most probably require an additional \$10,000 per year. Summarizing the above costs over the 5 to 10 year operating period results in a remedial cost between \$675,000 and \$1.1 million.

It is not possible to predict the cost of soil excavation for source control because the area of high VOC concentrations extends beneath Herb Hill Road and disruption of the roadway and underground utilities would have to be estimated on the basis of a detailed structural engineering study. Our experience with similar situations leads us to conclude that this work would exceed the other capital costs for ground-water remediation. For this same reason, the cost of installing a hydraulic barrier, such as a clay slurry wall around the outside of the plume would be increased to the point where its feasibility would be questionable.

The preliminary assessment of remedial options and costs must be viewed from the perspective of ground-water contamination problems and possible future remediation on properties adjoining Li Tungsten. VOC contamination from the Mattiace property immediately west of Li Tungsten is being investigated as a Superfund site, and a former dry cleaning operation east of Li Tungsten may have created a VOC plume which crosses Li Tungsten property. If a pump-and-treat system is operated at Li Tungsten with no action on the adjoining VOC plumes, the Li Tungsten pumping system could cause off-site VOC contamination to migrate to Li Tungsten. This would extend the remediation time for an undetermined period. It would also be necessary to analyze the environmental impact of air discharges from the pump-and-treat system. If VOC emissions to the atmosphere are judged to be unacceptable, it may be necessary to add an additional stage of treatment by activated carbon. The issue of air emissions must also be considered in light of similar treatment activities which may take place on the adjoining properties.

The ground-water chemistry data collected during the investigation do not indicate contamination by dissolved metals, which would require active ground-water remediation. Elevated concentrations of lead, cadmium, arsenic, and chromium near the mud pond are only slightly above the TOGS

standards. High sulfate concentrations in wells near the mud pond indicate that the mud pond has leached into the ground water, and water-quality results from nearly all of the monitoring wells installed for the various investigations show elevated dissolved tungsten concentrations. The regulatory implications of the inorganic water-quality data are uncertain because the dissolved metals and sulfate do not pose a serious environmental or health hazard and because there is no ground-water standard for tungsten as yet. It is probable, however, that, at a minimum, a long-term ground-water monitoring program for substances resulting from Li Tungsten's operations would be required. The cost of long-term ground-water monitoring would most likely range between \$15,000 and \$20,000 per year, provided the existing monitoring wells can be retained. The period of monitoring cannot be predicted at this time; however, a minimum of 5 years of data would ordinarily be required before a petition for relief from monitoring would be considered by New York State.

FINDINGS AND CONCLUSIONS

1. Water-level data from monitoring wells at the site revealed the presence of two ground-water systems: (1) the shallow water-table system in the southern part of the site; and (2) a perched ground-water system in the northern section of the site.

2. Ground water flows southward toward Glen Cove Creek in both the shallow water-table system and the perched ground-water system.
3. The site is underlain by unconsolidated glacial deposits consisting of sand, silt, clay, and boulders that occur with a high degree of variability. In general, relatively low permeability deposits occur beneath the site as indicated by slow recovery of water levels during well development and ground-water sampling.
4. Analyses of ground-water samples collected in spring 1987 and spring 1988 indicate the presence of a VOC plume with maximum concentrations greater than 20 ppm. The plume is delineated by monitoring wells in the southern part of Parcel III and the northern part of Parcel I.
5. The principal VOC contaminant in the plume is tetrachloroethene, which is a chemical used by dry cleaners. The source of the plume is unknown. However, given the close proximity of a dry cleaning facility formerly located adjacent to Parcel III, it seems likely that the source of contamination is off-site.

6. High concentrations of VOCs were also detected in Well GM-10, located in the southern part of Parcel IV, approximately 30 ft north of the Mattiace property. The principal VOC contaminant detected in this well was 1,1,1-trichloroethene and it represents a separate problem from the VOC plume discussed above. The extent and source of the contamination detected in this well is unknown.
7. Analytical results indicate that the TOGS values for lead, cadmium, and arsenic were exceeded in monitoring wells located in the vicinity of the wastewater treatment system in the southwestern area of the site, the area most likely to be the source of the contamination observed.
8. Tungsten was detected in monitoring wells throughout the site. Although there are no TOGS values for this metal, the widespread presence of tungsten in the ground-water systems (water table and perched water) indicates that contamination was caused by past disposal practices.
9. Analytical results of the soil survey at the site indicate that VOCs may not have been dumped on the surficial soils in unpaved areas of the site.

Only one compound, tetrachloroethene, was detected in low concentrations in two of the 36 samples collected for analyses. These samples were taken along a fence that separates the lower portion of Area III where high concentrations of VOCs were detected, and an adjacent property to the west which was formerly occupied by a dry cleaning firm.

10. The drill cuttings from Well GM-14A were analyzed for VOCs, PCBs, TPHC, and metals (using EP testing methods) indicate that petroleum hydrocarbons were detected in a concentration of 330 ppm. VOCs and PCBs were not detected. The only metal detected was arsenic in a concentration of 0.041 ppm, which is below the federal standard of 5 ppm (40 CFR Section 261.24, Table 1, Section B). The results of this analysis suggest that soil excavated from this area may be suitable for certain disposal options. One such option would be to send the soil to an asphalt company which can use soils contaminated with petroleum hydrocarbons.


11. No floating phase of hydrocarbons was found in monitoring Wells EMW-3, EMW-5, and GM-14B when measurements were made in these wells (which are located downgradient of two reported spills at the site).

Respectfully submitted,

GERAGHTY & MILLER, INC.



Vincent J. Glasser
Staff Scientist



Michael J. McEachern
Associate

April 29, 1988
VJG/MJM:vk

REFERENCES

Kilburn, C., and R.R. Krulikas. 1987. Hydrogeology and Ground-Water Quality of the Northern Part of the Town of Oyster Bay, Nassau County, New York. U.S. Geological Survey Water-Resources Investigations Report 85-4051, 61 pp.

Swarzenski, W.W. 1963. Hydrogeology of Northwestern Nassau and Northeastern Queens Counties, Long Island, New York. U.S. Geological Survey Water-Supply Paper 1657, 90 pp.

TABLES

Table 1. Summary of Monitoring Well Construction Details, Li Tungsten Facility, Glen Cove, New York.

=====								
			-----Feet Below Land Surface-----					Height of
Well	Installation	Well	Total	Screened	Gravel	Bentonite	Cement	Measuring P
Designation	Date	Diameter	Depth	Interval	Pack	Seal	Grout	(Rel. to l

First Investigation								
Wells 1)								

EMW-1	NA	4	14.1	4.1 - 14.1	NA	NA	NA	+1.40
EMW-2	NA	4	5.5	0.0 - 5.5	NA	NA	NA	+0.0
EMW-3	NA	4	9.9	+0.1 - 9.9	NA	NA	NA	+0.40
EMW-4	NA	4	18.6	8.6 - 18.6	NA	NA	NA	+1.60
EMW-5	NA	4	9.0	0.0 - 9.0	NA	NA	NA	0.0
Second Investigation								
Wells								
Spring 1987								

GM-1	4/09/87	2	14.8	4.8 - 14.8	2.0 - 4.8	0.8 - 2.0	0.0 - 0.8	+0.60
GM-2	4/14/87	2	12.4	2.4 - 12.4	1.1 - 2.4	0.8 - 1.1	0.55 - 0.8	+0.15
GM-30	4/14/87	1.5	23.5	13.5 - 23.5	7.0 - 13.5	5.0 - 7.0	0.0 - 5.0	+0.40
GM-4	4/15/87	1.5	15.4	5.4 - 15.4	2.5 - 5.4	1.0 - 2.5	0.7 - 1.0	+0.30
GM-5	4/21/87	1.5	22.0	12.0 - 22.0	10.0 - 12.0	7.0 - 10.0	0.0 - 7.0	+0.90
Third Investigation								
Wells								
Spring 1988								

GM-6	3/31/88	2	12.2	2.2 - 12.2	1.0 - 2.2	0.5 - 1.0	0.0 - 0.5	+0.4
GM-7	4/01/88	2	12.9	2.9 - 12.9	1.0 - 2.9	0.5 - 1.0	0.0 - 0.5	+3.10
GM-8	4/04/88	2	12.9	2.9 - 12.9	2.0 - 2.9	1.0 - 2.0	0.0 - 1.0	+2.50
GM-9	4/04/88	2	12.1	2.1 - 12.1	1.5 - 2.1	1.0 - 1.5	0.0 - 1.0	+2.40
GM-10	4/06/88	2	54.1	44.1 - 54.1	42.0 - 44.1	40.0 - 42.0	0.0 - 40.0	+3.30
GM-11	4/07/88	2	14.2	4.2 - 14.2	3.0 - 4.2	2.0 - 3.0	0.0 - 2.0	+2.07
GM-12	4/11/88	2	14.0	4.0 - 14.0	3.0 - 4.0	2.0 - 3.0	0.0 - 2.0	+2.53
GM-13	4/11/88	2	16.8	6.8 - 16.8	5.0 - 6.8	3.0 - 5.0	0.0 - 3.0	+2.30
GM-14A	4/12/88	2	17.8	7.8 - 17.8	5.0 - 7.8	4.0 - 5.0	0.0 - 4.0	+2.50
GM-14B	4/14/88	2	11.3	1.3 - 11.3	0.5 - 1.3	0.2 - 0.5	0.0 - 0.2	+1.15
GM-15	4/13/88	2	14.3	4.3 - 14.3	2.0 - 4.3	1.0 - 2.0	0.0 - 1.0	+0.20
GM-16	4/16/88	2	9.0	+0.6 - 9.0	0.0 - 9.0	----	----	+0.60
GM-17 2)	4/18/88	2	10.5	0.5 - 10.5	0.5 - 10.5	----	0.0 - 0.5	+0.3

1) These wells were reportedly installed in the early 1980s by another consultant. Well construction details are deduced from field measurements and observations.

2) Well GM-17 was installed at the request of RTP as part of an expanded scope of work to obtain more information on subsurface conditions for proposed canals. Two other wells were proposed for this expanded scope of work but were cancelled due to constraints and uncertainties.

NA Not available.

Table 2. Summary of Ground-Water Elevation Data for Monitoring Wells at Li Tungsten Facility, Glen Cove, New York.

-----April 21, 1988-----						-----April 26, 1988-----					
Well Designation	Measuring Point Elevation	Depth to Water *	Water Level Elevation **			Depth to Water *	Water Level Elevation **				
EMW-1	16.75	5.78	10.97			5.86	10.89				
EMW-2	6.96	0.35	6.61			0.41	6.55				
EMW-3	9.64	2.95	6.69			3.19	6.45				
EMW-4	12.56	5.36	7.20			5.53	7.03				
EMW-5	9.62	3.05	6.57			3.19	6.43				
GM-1	18.02	7.50	10.52			7.25	10.77				
GM-2	6.64	----	----			1.21	5.43				
GM-3D	16.02	5.15	10.87			5.23	10.79				
GM-4	26.06	1.56	24.50			1.76	24.30				
GM-5	61.94	15.50	46.44			15.98	45.96				
GM-6	13.29	2.75	10.54			2.85	10.44				
GM-7	21.55	10.81	10.74			10.90	10.65				
GM-8	18.49	7.60	10.89			7.70	10.79				
GM-9	20.60	5.47	15.13			5.64	14.96				
GM-10	59.46	47.13	12.33			47.33	12.13				
GM-11	67.47	7.60	59.87			7.71	59.76				
GM-12	49.83	7.68	42.15			7.68	42.15				
GM-13	44.09	13.40	30.69			13.53	30.56				
GM-14A	17.25	8.15	9.10			8.20	9.05				
GM-14B	16.16	3.15	13.01			3.40	12.76				
GM-15	17.50	7.73	9.77			7.88	9.62				
GM-16	36.44	0.69	35.75			0.67	35.77				
GM-17	----	0.78	----			0.94	----				

* Feet below measuring point.

** Feet above mean sea level.

Table 3. Concentrations of Volatile Organic Compounds Detected in Ground-Water Samples Collected Spring 1987 and Spring 1988, at Li Tungsten Facility, Glen Cove, New York.

Page 1 of 5

Well Designation: Date Sampled:	TOG 1) (ppb)	Rep.			Rep.			EMW-3 3/12/87
		EMW-1 3/12/87	EMW-1 4/7/87	EMW-1 4/8/88	EMW-1 4/8/88	EMW-2 3/12/87	EMW-2 3/12/87	EMW-2 4/7/88
Chloroethane		--	NA	--	--	--	--	--
Bromomethane		--	NA	--	--	--	--	--
Dichlorodifluoromethane		--	NA	--	--	--	--	--
Vinyl chloride	5	51	42	52	52	--	--	--
Chloroethane		--	NA	--	--	--	--	--
Methylene chloride	.3	--	NA	--	--	--	--	--
Trichlorofluoromethane		--	NA	--	--	--	--	--
1,1-Dichloroethene	0.07	2,000	NA	6	6	--	--	--
1,1-Dichloroethane	50	--	NA	--	--	--	--	--
1,2-Dichloroethene		--	920	2,100	2,100	--	--	--
Chloroform	100	--	NA	--	--	1	--	--
1,2-Dichloroethane	0.8	--	NA	--	2	--	--	--
1,1,1-Trichloroethane	50	--	NA	--	--	--	--	--
Carbon tetrachloride	5	--	NA	--	--	--	--	--
Bromodichloromethane	50	--	NA	--	--	--	--	--
1,2-Dichloropropane	50	--	NA	--	--	--	--	--
trans-1,3-Dichloropropene		--	NA	--	--	--	--	--
Trichloroethylene	10	1,900	950	1,600	1,800	4	--	--
Chlorodibromomethane		--	NA	--	--	1	--	--
1,1,2-Trichloroethane	0.6	--	NA	--	--	--	--	--
cis-1,3-Dichloropropene		--	NA	--	--	--	--	--
2-Chloroethvinylether		--	NA	--	--	--	--	--
Bromoform		--	NA	--	--	--	--	--
1,1,2,2-Tetrachloroethane	0.2	--	NA	--	--	--	--	--
Tetrachloroethene	0.7	18,000	10,200	16,000	19,000	50	5	7
Chlorobenzene		--	NA	--	--	--	--	--
1,3-Dichlorobenzene		--	NA	--	--	--	--	--
1,2-Dichlorobenzene		--	NA	--	--	--	--	--
1,4-Dichlorobenzene		--	NA	--	--	--	--	--
Benzene		--	NA	6	4	--	--	--
Toluene	50	--	NA	--	2	--	--	--
Ethyl benzene	50	--	NA	--	--	--	--	--
m Xylene		NA	NA	--	--	NA	NA	NA
o-p Xylene	50	NA	NA	--	--	NA	NA	NA
Total VOCs:		21,951	12,112	19,764	22,966	55	6	7

All results in parts per billion (ppb).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104190

Table 3. Concentrations of Volatile Organic Compounds Detected in Ground-Water Samples Collected Spring 1987 and Spring 1988, at Li Tungsten Facility, Glen Cove, New York.

Page 2 of 5

Well Designation:	EMW-3	EMW-4	EMW-4	EMW-5	GM-1	GM-1	GM-2	GM-2
Date Sampled:	4/8/88	4/20/87	4/8/88	4/8/88	4/22/87	4/7/88	4/22/87	4/7/88
TOG 1)								
Volatile Organic Compound (ppb)								
Chloroethane	--	--	--	--	--	--	--	--
Bromomethane	--	--	--	--	--	--	--	--
Dichlorodifluoromethane	--	--	--	--	--	--	--	--
Vinyl chloride	5	2	--	--	--	--	--	--
Chloroethane	--	--	--	--	--	--	--	--
Methylene chloride	50	--	--	--	--	--	--	--
Trichlorofluoromethane	--	--	--	--	--	--	--	--
1,1-Dichloroethene	0.07	--	--	--	--	--	--	--
1,1-Dichloroethane	50	--	--	--	--	--	--	--
1,2-Dichloroethene	--	--	--	--	--	4	6	--
Chloroform	100	--	--	--	--	--	--	--
1,2-Dichloroethane	0.3	--	--	--	--	5	--	--
1,1,1-Trichloroethane	50	--	--	--	--	--	--	--
Carbon tetrachloride	5	--	--	--	--	--	--	--
Bromodichloromethane	50	--	--	--	--	--	--	--
1,2-Dichloropropane	50	--	--	--	--	--	--	--
trans-1,3-Dichloropropene	--	--	--	--	--	--	--	--
Trichloroethylene	10	1	--	--	3	5	2	--
Chlorodibromomethane	--	--	--	--	--	--	--	--
1,1,2-Trichloroethane	0.6	--	--	--	--	--	--	--
cis-1,3-Dichloropropene	--	--	--	--	--	--	--	--
2-Chloroethylether	--	--	--	--	--	--	--	--
Bromoform	--	--	--	--	--	--	--	--
1,1,2,2-Tetrachloroethane	0.2	--	--	--	--	--	--	--
Tetrachloroethene	0.7	--	--	--	27	16	2	--
Chlorobenzene	--	--	--	--	--	--	--	--
1,3-Dichlorobenzene	--	--	--	--	--	--	--	--
1,2-Dichlorobenzene	--	--	--	--	--	--	--	--
1,4-Dichlorobenzene	--	--	--	--	--	--	--	--
Benzene	--	9	--	--	--	--	--	--
Toluene	50	--	--	--	--	--	--	--
Ethyl benzene	50	--	--	--	--	--	--	--
m Xylene	--	NA	--	--	NA	--	NA	--
o+p Xylene	50	--	NA	--	NA	--	NA	--
Total VOCs:	12	--	1	1	30	30	10	--

All results in parts per billion (ppb).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104191

Table 3. Concentrations of Volatile Organic Compounds Detected in Ground-Water Samples Collected Spring 1987 and Spring 1988, at Li Tungsten Facility, Glen Cove, New York.

Page 3 of 5

Well Designation:	GM-3D	GM-3D	GM-4	GM-4	GM-5	GM-5	GM-6	Rep.
Date Sampled:	4/22/87	4/8/88	4/20/87	4/7/88	4/22/87	4/7/88	4/7/88	GM-6
TOG 1)								
Volatile Organic Compound (ppb)								
Chloroethane	--	--	--	--	--	--	--	--
Bromomethane	--	--	--	--	--	--	--	--
Dichlorodifluoromethane	--	--	--	--	--	--	--	--
Vinyl chloride	5	81	36	--	--	--	12	12
Chloroethane	--	--	--	--	--	--	1	2
Methylene chloride	50	--	--	--	--	--	--	--
Trichlorofluoromethane	--	--	--	--	--	--	--	--
1,1-Dichloroethene	0.07	--	3	--	--	--	--	--
1,1-Dichloroethane	50	--	--	--	--	--	--	--
1,2-Dichloroethene		1,500	860	--	--	--	430	400
Chloroform	100	--	--	--	--	--	--	--
1,2-Dichloroethane	0.8	--	--	--	--	--	--	--
1,1,1-Trichloroethane	50	--	--	--	--	--	--	--
Carbon tetrachloride	5	--	--	--	--	--	--	--
Bromodichloromethane	50	--	--	--	--	--	--	--
1,2-Dichloropropane	50	--	--	--	--	--	--	--
trans-1,3-Dichloropropene	--	--	--	--	--	--	--	--
Trichloroethylene	10	910	710	--	--	--	780	730
Chlorodibromomethane	--	--	--	--	--	--	--	--
1,1,2-Trichloroethane	0.6	--	--	--	--	--	--	--
cis-1,3-Dichloropropene	--	--	--	--	--	--	--	--
2-Chloroethvinylether	--	--	--	--	--	--	--	--
Propoform	--	--	--	--	--	--	--	--
1,1,2,2-Tetrachloroethane	0.2	--	--	--	--	--	--	--
Tetrachloroethene	0.7	9,000	7,400	--	--	1	1,800	1,800
Chlorobenzene	--	--	--	--	--	--	--	--
1,3-Dichlorobenzene	--	--	--	--	--	--	--	--
1,2-Dichlorobenzene	--	--	--	--	--	--	--	--
1,4-Dichlorobenzene	--	--	--	--	--	--	--	--
Benzene	--	--	2	--	--	--	--	--
Toluene	50	--	--	--	--	--	--	--
Ethyl benzene	50	--	--	--	--	--	--	--
m Xylene	--	NA	--	NA	--	NA	--	--
o-p Xylene	50	NA	--	NA	--	NA	--	--
Total VOCs:	11,491	9,011	--	--	1	--	3,023	2,944

All results in parts per billion (ppb).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104192

Table 3. Concentrations of Volatile Organic Compounds Detected in Ground-Water Samples Collected Spring 1987 and Spring 1988, at Li Tungsten Facility, Glen Cove, New York.

Page 5 of 5

		Field		Field	Field	Trip	Trip	Decon
Well Designation:		GM-15	GM-16	Blank	Blank 1	Blank 2	Blank	Water
Date Sampled:		4/15/88	4/15/88	3/12/87	4/7/88	4/8/88	3/12/87	4/8/88
		TOG 1)						Tank
Volatile Organic Compound		(ppb)						
Chloroethane		--	--	--	--	--	--	--
Bromomethane		--	--	--	--	--	--	--
Dichlorodifluoromethane		--	--	--	--	--	--	--
Vinyl chloride	5	--	--	--	--	--	--	--
Chloroethane		--	--	--	--	--	--	--
Methylene chloride	50	--	--	--	--	--	--	--
Trichlorofluoromethane		--	--	--	--	--	--	--
1,1-Dichloroethene	0.07	--	--	--	--	--	--	--
1,1-Dichloroethane	50	--	--	--	--	--	--	--
1,2-Dichloroethene		--	--	--	--	--	--	--
Chloroform	100	--	--	--	--	--	--	--
1,2-Dichloroethane	0.8	--	--	--	--	--	--	--
1,1,1-Trichloroethane	50	--	--	--	--	--	--	1
Carbon tetrachloride	5	--	--	--	--	--	--	--
Bromodichloromethane	50	--	--	--	--	--	--	--
1,2-Dichloropropane	50	--	--	--	--	--	--	--
trans-1,3-Dichloropropene		--	--	--	--	--	--	--
Trichloroethylene	10	--	--	--	--	--	--	--
Chlorodibromomethane		--	--	1	--	--	1	--
1,1,2-Trichloroethane	0.6	--	--	--	--	--	--	--
cis-1,3-Dichloropropene		--	--	--	--	--	--	--
2-Chloroethvinylether		--	--	--	--	--	--	--
Bromoform		--	--	--	--	--	--	--
1,1,2,2-Tetrachloroethane	0.2	--	--	--	--	--	--	--
Tetrachloroethene	0.7	--	--	2	--	--	--	--
Chlorobenzene		--	--	--	--	--	--	--
1,3-Dichlorobenzene		--	--	--	--	--	--	--
1,2-Dichlorobenzene		--	--	--	--	--	--	--
1,4-Dichlorobenzene		--	--	--	--	--	--	--
Benzene		--	--	--	--	--	--	--
Toluene	50	--	--	--	--	--	--	--
Ethyl benzene	50	--	--	--	--	--	--	--
m Xylene		--	--	--	NA	--	--	NA
o-p Xylene	50	--	--	--	NA	--	--	NA
Total VOCs:		--	--	3	--	--	1	1

All results in parts per billion (ppb).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104193

Table 4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.

Page 1 of 5

Well Designation:		EMW-1	EMW-1	EMW-1	Rep. EMW-1	EMW-2	Rep. EMW-2	EMW-2	EMW-3
Date Sampled:		3/12/87	4/7/87	4/8/88	4/8/88	3/12/87	3/12/87	4/7/88	3/12/87
Metals		TOG 1) (ppm)							
Calcium as Ca		90	NA	90	90	65	NA	70	110
Cobalt as Co		0.11	NA	0.27	0.32	0.005	NA	--	0.12
Nickel as Ni		0.35	NA	0.45	0.40	--	NA	--	0.10
Sodium as Na		40	NA	34	34	88	NA	100	140
Mercury as Hg	.002	NA	NA	--	--	NA	NA	--	NA
Lead as Pb	.025	NA	NA	--	--	NA	NA	--	NA
Chromium as Cr	.050	NA	NA	--	--	NA	NA	--	NA
Cadmium as Cd	.010	NA	NA	0.034	0.040	NA	NA	--	NA
Arsenic as As	.025	NA	NA	0.002	0.002	NA	NA	0.004	NA
Tantalum		0.3	NA	0.09	0.34	0.3	NA	0.27	0.2
Tungsten		--	NA	--	--	2.4	NA	4.69	4.3
Copper as Cu	1.0	0.30	NA	NA	NA	--	NA	NA	--
Molybdenum as Mo		--	NA	NA	NA	0.21	NA	NA	0.07
Chloride as Cl	250.0	56	NA	65	65	100	NA	91	200
Nitrate as N	10.0	--	NA	--	--	--	NA	--	--
Sulfate as SO ₄	250.0	440	NA	400	350	--	NA	8.0	110
Specific conductance (umhos/cm)		1,000	NA	1,050	1,050	1,000	NA	1,000	1,400
pH (units)		5.4	NA	5.5	5.5	6.2	NA	6.75	6.3

All results in parts per million (ppm).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104194

Table 4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.

Page 2 of 5

Well Designation:		EMW-3	EMW-4	EMW-4	EMW-5	GM-1	GM-1	GM-2	GM-2
Date Sampled:		4/8/88	4/20/87	4/8/88	4/8/88	4/22/87	4/7/88	4/22/87	4/7/88
Metals		TOG 1) (ppm)							
Calcium as Ca		340	NA	620	190	NA	85	NA	65
Cobalt as Co		3.5	NA	0.40	0.72	NA	--	NA	0.008
Nickel as Ni		0.45	NA	0.35	0.25	NA	--	NA	--
Sodium as Na		1,000	NA	2,000	320	NA	30	NA	100
Mercury as Hg	.002	--	NA	--	--	NA	--	NA	--
Lead as Pb	.025	0.060	NA	0.075	--	NA	--	NA	--
Chromium as Cr	.050	0.006	NA	--	--	NA	--	NA	--
Cadmium as Cd	.010	0.029	NA	--	0.017	NA	--	NA	--
Arsenic as As	.025	0.14	NA	0.39	0.069	NA	--	NA	0.011
Tantalum		1.76	NA	3.91	0.52	NA	0.075	NA	0.28
Tungsten		154.0	NA	1.63	42.8	NA	0.38	NA	--
Copper as Cu	1.0	NA	NA	NA	NA	NA	NA	NA	NA
Molybdenum as Mo		NA	NA	NA	NA	NA	NA	NA	NA
Chloride as Cl	250.0	1,900	NA	2,700	740	NA	50	NA	110
Nitrate as N	10.0	--	NA	--	--	NA	--	NA	--
Sulfate as SO ₄	250.0	1,100	NA	3,300	450	NA	130	NA	32
Specific conductance (umhos/cm)		4,000	NA	5,000	2,000	NA	975	NA	1,200
µmhos/cm		6.17	NA	5.64	6.51	NA	6.57	NA	6.90

All results in parts per million (ppm).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104195

Table 4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.

Page 3 of 5

Well Designation:		GM-3D	GM-3D	GM-4	GM-4	GM-5	GM-5	GM-6	Rep.
Date Sampled:		4/22/87	4/8/88	4/20/87	4/7/88	4/22/87	4/7/88	4/7/88	GM-6 4/7/88
Metals	TOG 1) (ppm)								
Calcium as Ca		NA	90	NA	19	NA	26	150	150
Cobalt as Co		NA	0.10	NA	--	NA	--	--	--
Nickel as Ni		NA	0.15	NA	--	NA	--	--	--
Sodium as Na		NA	44	NA	14	NA	26	120	130
Mercury as Hg	.002	NA	--	NA	--	NA	--	--	--
Lead as Pb	.025	NA	--	NA	--	NA	--	0.008	0.005
Chromium as Cr	.050	NA	--	NA	--	NA	--	--	--
Cadmium as Cd	.010	NA	0.020	NA	0.0014	NA	--	--	--
Arsenic as As	.025	NA	--	NA	--	NA	--	0.003	0.002
Tantalum		NA	0.33	NA	0.053	NA	0.051	0.14	0.14
Tungsten		NA	--	NA	0.51	NA	0.20	--	0.29
Copper as Cu	1.0	NA	NA	NA	NA	NA	NA	NA	NA
Molybdenum as Mo		NA	NA	NA	NA	NA	NA	NA	NA
Chloride as Cl	250.0	NA	65	NA	7	NA	59	260	260
Nitrate as N	10.0	NA	--	NA	--	NA	3.8	--	--
Sulfate as SO ₄	250.0	NA	350	NA	16	NA	40	450	450
Specific conductance (umhos/cm)		NA	875	NA	200	NA	475	1,600	1,600
pH (units)		NA	5.90	NA	6.61	NA	5.30	6.20	6.20

All results in parts per million (ppm).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

104196

Table 4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.

Page 4 of 5

Well Designation:		GM-7	GM-8	GM-9	GM-10	GM-11	GM-12	GM-13	GM-14A
Date Sampled:		4/8/88	4/8/88	4/8/88	4/15/88	4/15/88	4/15/88	4/15/88	4/15/88
Metals	TOG 1) (ppm)								
Calcium as Ca		26	36	55	21	25	110	120	370
Cobalt as Co		--	0.005	--	0.024	--	--	0.40	0.40
Nickel as Ni		--	--	--	--	--	--	--	0.20
Sodium as Na		28	18	34	12	14	29	96	6,600
Mercury as Hg	.002	--	--	--	--	--	--	--	--
Lead as Pb	.025	--	--	--	--	--	--	--	0.070
Chromium as Cr	.050	--	--	--	--	--	--	--	0.050
Cadmium as Cd	.010	--	0.013	--	--	--	--	--	--
Arsenic as As	.025	--	--	--	--	--	--	0.002	0.78
Tantalum		0.07	0.27	0.11	--	--	--	--	2.26
Tungsten		--	--	--	0.40	0.11	--	--	39.40
Copper as Cu	1.0	NA	NA	NA	NA	NA	NA	NA	NA
Molybdenum as Mo		NA	NA	NA	NA	NA	NA	NA	NA
Chloride as Cl	250.0	14	26	43	14	22	65	25	700
Nitrate as N	10.0	--	0.6	1.0	26	3.5	--	--	1.0
Sulfate as SO4	250.0	68	230	150	48	50	150	430	11,000
Specific conductance (umhos/cm)		400	575	625	260	240	790	1,060	20,200
pH (units)		6.58	4.99	6.16	5.6	6.2	6.2	6.1	7.4

All results in parts per million (ppm).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

Table 4. Concentrations of Metals in Ground-Water Samples Collected Spring 1987 and Spring 1988, Li Tungsten Facility, Glen Cove, New York.

Page 5 of 5

Well Designation:	GM-15	GM-16	Field Blank	Field Blank 1	Field Blank 2	Trip Blank	Trip Blank	Decon Water Tank
Date Sampled:	4/15/88	4/15/88	3/12/87	4/7/88	4/8/88	3/12/87	4/8/88	4/13/88
TOG 1)								
(ppm)								

Calcium as Ca	48	14	NA	NA	NA	NA	NA	NA
Cobalt as Co	0.030	0.010	NA	NA	NA	NA	NA	NA
Nickel as Ni	--	--	NA	NA	NA	NA	NA	NA
Sodium as Na	48	7.9	NA	NA	NA	NA	NA	NA
Mercury as Hg	.002	--	NA	NA	NA	NA	NA	NA
Lead as Pb	.025	--	NA	NA	NA	NA	NA	NA
Chromium as Cr	.050	--	NA	NA	NA	NA	NA	NA
Cadmium as Cd	.010	--	0.007	NA	NA	NA	NA	NA
Arsenic as As	.025	0.002	--	NA	NA	NA	NA	NA
Tantalum	--	--	NA	NA	NA	NA	NA	NA
Tungsten	0.16	--	NA	NA	NA	NA	NA	NA
Copper as Cu	1.0	NA	NA	NA	NA	NA	NA	NA
Molybdenum as Mo	NA	NA	NA	NA	NA	NA	NA	NA

Chloride as Cl	250.0	120	8	NA	NA	NA	NA	NA
Nitrate as N	10.0	--	--	NA	NA	NA	NA	NA
Sulfate as SO4	250.0	48	200	NA	NA	NA	NA	NA

Specific conductance (umhos/cm)	640	140	NA	NA	NA	NA	NA	NA
pH (units)	6.2	6.2	NA	NA	NA	NA	NA	NA

All results in parts per million (ppm).

-- Not detected.

FB Field blank.

TB Trip blank.

Detection limits presented in Appendix D.

Samples analyzed via USEPA Method 601, 602 by EcoTest Laboratories, Inc., North Babylon, New York.

1) TOG references in this report are used solely as reference point for comparative purposes and are not to be construed as applicable clean-up standards.

NA Not analyzed.

Table 5. Concentrations of Selected Volatile Organic Compounds Tested for During Soil Survey of Parcels II, III, and IV.

Sample Location		Concentration of 1,2-Dichloroethene (ppb)	Concentration of Trichloroethene (ppb)	Concentration of Tetrachloroethene (ppb)
Parcel II	Stream	--	--	--
	1	--	--	--
	2	--	--	--
	3	--	--	--
	4	--	--	--
	5	--	--	--
Parcel III	1A	--	--	--
	1B	--	--	--
	1C	--	--	--
	2A	--	--	--
	2B	--	--	--
	2C	--	--	--
	3A	--	--	--
	3B	--	--	--
	3C	--	--	--
	4A	--	--	--
	4B	--	--	--
	4C	--	--	--
	5A	--	--	--
	5B	--	--	--
	5C	--	--	--
	PS-1	--	--	5.6
	PS-2	--	--	5.1
	PS-3	--	--	--
	PS-3A	--	--	--
	PS-4	--	--	--
	PS-4A	--	--	--
Parcel IV	1	--	--	--
	2	--	--	--
	3	--	--	--
	4	--	--	--
	5	--	--	--
	6	--	--	--
	7	--	--	--
	8	--	--	--
	9	--	--	--

ppb Parts per billion.

-- Not detected.


WAH CHANG CORPORATION

Glen Cove, N. Y.

RADIATION SURVEY REPORT

Date Oct 15 1971

Thorium Storage Pit
(located outside the chem lab)



W1 < 10 DPM
 100 cm²
W2 < 10
W3 < 10
W4 < 10

M1 < 20 DPM
 100 cm²
M2 < 20
M3 < 20
M4 < 20

A Sample from the bottom of the pit shows 150 DPM
 100 cm²

Signed

adiation Officer

WAM OILING CORPORATION
Green Cove, N. Y.

RADIATION SURVEY REPORT

Date Oct 14 1971


Blending Room

Air Sampling By W. Ritchie

Meter Tests By F. H. Lee

WIPE SAMPLES

W1	<u>20</u>	DPM/100cm ²
W2	<u>25</u>	DPM
	<u>20</u>	DPM
W4	<u>20</u>	DPM
W5	<u>25</u>	DPM
W6	<u>20</u>	DPM
W7	<u>20</u>	DPM
	<u>25</u>	DPM
W9	<u>25</u>	DPM
W10		CPM



SANSON METER
READINGS

M2	<u>40</u>	DPM/100cm ²
M2	<u>80</u>	DPM
M3	<u>150</u>	DPM
M4	<u>300</u>	DPM
M5	<u>300</u>	DPM
M6	<u>100</u>	DPM
M7	<u>40</u>	DPM
M8	<u>150</u>	DPM
M9	<u>40</u>	DPM
M10		CPM

AIR SAMPLING STATIONS:

A1 (Loading) at 15CFM, Sampling Time 30 Min., Shows < 10 DPM/100cm²

A2 (Unloading) at 15 CFM, Sampling Time 30 Min., Shows < 10 DPM/100cm²

Signed

[Signature]
Radiation Officer

WAH CHANG CORPORATION

Glen Cove, N. Y.

RADIATION SURVEY REPORT

Date Oct 14 1971


Air Sampling By W. Ritchie

Reduction Furnace No. 8

Meter Tests By F.H. Lee

WIPE SAMPLES

W1 < 20 DPM/100cm²
 W2 < 20 DPM
 W3 < 20 DPM
 W4 < 20 DPM
 W5 < 20 DPM
 W6 < 20 DPM
 W7 < 20 DPM
 W8 < 20 DPM
 W9 < 20 DPM
 W10 < 20 DPM



SAMSON METER READINGS

M1 50 DPM/100cm²
 M2 25
 M3 25
 M4 100
 M5 25
 M6 50
 M7 25
 M8 25
 M9 50
 M10 100

AIR SAMPLING STATIONS:

A1 (Weighing) at 15 CFM, Sampling Time 30 Min., Shows < 10 DPM/100cm²
 A2 (Elevator) " " " 30 Min., Shows < 10 DPM "
 A3 (Unloading) " " " 30 Min., Shows < 10 DPM "
 A4 (Rotap) " " " 30 Min., Shows < 10 DPM "

Signed [Signature]
 Radiation Officer

August 12, 1971

Address Reply To:

Radiological Health Unit

Wah Chang Smelting & Refining Company
63 Herb Hill Road
Glen Cove, New York

Att: Mr. Henry Lee
Radiation Safety Officer

Dear Mr. Lee:

As per our telecon of August 10, 1971, I am enclosing a copy of our instruction sheet for the decon and release of radiation facilities and equipment, in case you have not been able to locate the copy previously left with you in March of this year. As you can see the instructions are quite explicit, however, I wish to clarify one point, namely, the term contamination. As used in the instruction sheet, it applies to both removable (loose) and fixed radioactive surface contamination. Table V specifies the limits for both types of contamination.

There are two known areas of your plant where a final survey will be required. These are:

1. The reduction building where Th NO₃ was used;
2. Thorium storage pit.

If there are any other areas of your facility where radioactive material was used, please include them in the survey.

If I may be of any further assistance to you in this matter, please contact me.

Very truly yours,



Alan H. Jones
Senior Radiophysicist

AHJ:pc
Enclosure

104203

SUPPLEMENTARY DATA

Firm	<i>Wah Chang - Clinton Des</i>
Installation #	<i>604641</i>

1. Personnel Dosimetry

a. Whole Body Exposure

Monitoring Period	Type of Dosimeter	Number Monitored	Number of Persons in Dose Range			Maximum Exposure in Rem
			min.det.	min-3 Rem	3-5 Rem	> 5 Rem
prev. year	<i>1200</i>					
year to date						

b. Extremity Exposure

Monitoring Period	Type of Dosimeter	Number Monitored	Number of Persons in Dose Range			Maximum Exposure in Rem
			min.det.	min-25 Rem	25-75 Rem	> 75 Rem
prev. year	<i>6600</i>					
year to date						

c. Internal Exposure

Nuclide of Int.	Bioassay Technique	Sample Freq.	Analyzed By	No. Mon.	Number of Persons in Exp. Range				Max. Exp.
					min. det.	0-25% of lim.	25-100% of lim.	> 100% of lim.	
	<i>2200</i>								

2. Surveys

Type	How often performed	Date of latest	Performed By	Results
Radiation Equipment	<i>NA</i>			
Radioactive Materials (Sealed)	<i>NA</i>			
Radioactive Materials (Unsealed)	<i>not as often as required after processing Th NCS</i>	<i>3/15/69</i>	<i>RSC</i>	<i>OK</i>
Sealed Source Leak Tests	<i>NA</i>			
Interlocks	<i>not</i>			

104204

3. Radioactive Material/Equipment Inventory Fluctuations

a. Radioactive Material

Nuclide	Rec'd in past 12 mons, activity	Removed from Facility in Past 12 Months			
		non-waste activity	waste activity	physical form	vendor/method
<i>Tb-190</i>	<i>1874 lbs =</i>	<i>in waste</i>	<i>None</i>		
	<i>109 lbs</i>	<i>in waste</i>			

b. Equipment

Received		Disposed of	
Type	Description (kVp, beam current)	Type	Where
	<i>None</i>		

4. Evaluation of Health Physics Program based on above data and attached instrument/smear survey with any general comment:

*I suggested to RSO that TLD are put
in disposal if it is not going to be used.*

*RSO assured that someone else would take
smears when the powder is processed. It was
pointed out to him that it is his
responsibility to see that it gets done.
He says he will do so.*

By *G. Jones*
Date *11/30/70*

SURVEY RESULTS

LR 368 30

Lab. Page 211

Firm Wab Chang

Chen Chen

Install # 20460

Sealed: ☒ Unsealed

of Samples 16

☐ Q tip; ☒ Filter; ☐ Other

Nuclides Th

Survey Date 11/30/10

Radiophysicist John

CLP B close X study of decay cont.

7318
204

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi)	REMARKS
			GROSS	NET		
1	21	5	4.70	4.05	9.61	Total α ~ Th ²³² = 131.51 pCi
2	3	5	0.60	0.45	1.07	
3	62	5	12.40	12.25	29.05	
4	69	5	13.80	13.65	32.40	Actually Std for α std @ 18% Efficiency Should actually be ~ 57% (loss due to cover on the Std) \therefore These results are probably a factor of 3 high R.F.B.
5	44	5	8.80	8.65	20.53	
6	7	5	1.40	1.25	2.97	
7	3	5	0.60	0.45	1.07	
8	22	5	4.40	4.25	10.09	
9	23	5	4.60	4.45	10.56	
10	1	5	0.20	0.05	0.12	
11	1	5	0.20	0.05	0.12	
12	3	5	0.40	0.25	0.59	
13	9	5	1.80	1.65	3.92	
14	8	5	1.60	1.45	3.44	
15	9	5	1.80	1.65	3.92	
16	5	5	1.00	0.85	2.02	

Count for Th vs Th²³² Std, Instrument A-157 4318 Detector 1" IC Geiger probe

Voltage 1200 Gain x 1.4 Date Counted 12/3/10 Radiochemist R.F.B.

Background 0.15 CPM; Factor 2.3178 pCi/cpm (net)

164.6/4

Robert F. Blair 12/3/20
SIGNATURE (UNIT REVIEW)

D. Edward Stein 12/4
SIGNATURE (SECTION REVIEW)

DIAGRAM OF SURVEYED AREA

Radiophysicist

Installation =

LO464

Date


11/30/70

Firm

Webb Perry

Address

Glenn Cove



(1) Can in
ph stamp
box

- (8) table in slurry area
- (9) floor at loader
- (10) hopper
- (11) loading table at #7 furnace
- (12) floor at loading area
- (13) wet screening table
- (14) dust " "
- (15) floor below #7 furnace
- (16) outside shipping container of the warehouse

H: Hard; S: Soft; a: Alpha; n: Neutron

Red Numerals: Radiation in MREM/HR

Green Numerals: Smear Numbers

Blue Circled Smear Numbers: Greater Than 3 x Background Standard Deviation or as Indicated

STATE OF NEW YORK - DEPARTMENT OF LABOR
DIVISION OF INDUSTRIAL HYGIENE
RADIOLOGICAL HEALTH UNIT
80 Centre Street
New York, N. Y. 10013



1 Date
2 Type Visit

1. Firm Name & Address			3. No. Employees Exposed Male Female	
2. Confines of Installation				
4. Registration No.	5. License No. (s)	6. Industrial Code	7. Radiation Safety Officer	

☐ A. No item of non-compliance found.

☐ B. The following paragraphs of Code Rule 38, or conditions of your license were found in violation:

(47 - 4)	(- 23)	(19 - 34.1)
(- 5.1)	(47 - 24)	(20 - 34.2)
(- 6.2)	(47 - 25)	(21 - 34.3)
(- 9.1)	(15 - 26.2)	(47 - 34.4)
(- 9.1)	(15 - 26.3)	(- 35.1)
(- 9.1)	(15 - 26.4)	(47 - 35.2)
(47 - 10)	(30 - 26.5)	(25 - 36.1a)
(47 - 11)	(47 - 26.6)	(9 - 35.1b)
(47 - 20)	(47 - 28)	(24 - 36.1c)
(10 - 21.1)	(16 - 30)	(47 - 36.2)
(11 - 21.2)	(- 31.2)	(28 - 37)
(13 - 22.1)	(18 - 32)	(31 - 39)
(14 - 22.2)	(18 - 33)	(-)
(-)	(-)	(-)

11. Remarks

104208

12 The violations indicated above should be removed with _____ days.

IN-317 : (8.1.5)

Signature of _____ Government Representative _____

FOR THE COMMISSIONER _____

14. DATE	15. REVIEWED BY	16. DISPOSITION

REPORT ON COMPLIANCE VISIT

17. DATE	18. PERSON CONTACTED	19. REASON FOR NON-COMPLIANCE
12/17/69	Henry Lee	<p>22.1 - Thiram nitrate was placed into dead lines low in "Xmas tree" area. (< 2 w/line)</p> <p> 21.4 } 31 } I.C. 26.1 } </p>

1. DATE CASE CLOSED

12/17/69

21. INITIALS

L. H. S.

104209

SUPPLEMENTARY DATA

9/3/69

Wah Chung Smith + Refg C-
L 0464 Jean Case, L.T.

1. Personnel Dosimetry

None

a. Whole Body Exposure

Monitoring Period	Type of Dosimeter	Number Monitored	Number of Persons in Dose Range				Maximum Exposure in Rem
			min. det.	min-3 Rem	3-5 Rem	> 5 Rem	
prev. year	None		(used film badges year ago when working with uranium oxide) (Ottawa Film badge - L.T.C.)				
year to date							

b. Extremity Exposure

Monitoring Period	Type of Dosimeter	Number Monitored	Number of Persons in Dose Range				Maximum Exposure in Rem
			min. det.	min-25 Rem	25-75 Rem	> 75 Rem	
prev. year	None						
year to date							

c. Internal Exposure

Nuclide of Int.	Bioassay Technique	Sample Freq.	Analyzed By	No. Mon.	Number of Persons in Exp. Range				Max. Exp.
					min. det.	0-25% of lim.	25-100% of lim.	> 100% of lim.	
	None								

(used to take blood tests when working with thorium oxide)

2. Surveys

Type	How often performed	Date of latest	Performed By	Results (in excess of limits, etc.)
Radiation Equipment	N.A.			
Radioactive Materials (Sealed)	N.A.			
Radioactive Materials (Unsealed)	when working with thorium 3/16/69 (wipes & air samples) previous 1/15/69		Henry Lee	O.K. (max. 4.5 dpm - 1000)
Sealed Source Leak Tests	N.A.			
Interlocks	N.A.			

3. Radioactive Material/Equipment Inventory Fluctuations

a. Radioactive Material

Nuclide	Rec'd in past 12 mos. activity	Removed from Facility in Past 12 Months		
		non-waste activity	activity	waste physical form vendor/method
Thorium	7/31/67 400 lb.	used in product		N-216
232	12/18/63 200	1965	460 lb	
	6/10/64 200	1967	430	
	6/12/65 460	(to date)	930	
	1760			
On hand at present date 250 lb. in original container				

b. Equipment

Received		Disposed of	
Type	Description (kVp, beam current)	Type	Where
N.A.			

4. Evaluation of Health Physics Program based on above data and attached instrument/smear survey with any general comment:

There is some Thorium Oxide (radioactive) found in a pit with a heavy concrete locked cover on it in the yard. Marked with a radiation warning sign. They have not used the oxide for several years. Now only Thorium Nitrate used in their process. Their Nucleon Chicago Model 2512 is presently not operating. However they also have a "El-Tronics" Scintillation Scaler Model LS 64-PS. 18 smears were taken to-day. Also to-days surveys showed < 1 mR/hr at ground level, < 2 mR/hr at 1 ft above the cover of the pit, but 5 mR/hr in the vicinity of the unopened containers of thorium nitrate stored in the warehouse. They will relocate these containers and post a radiation warning sign.

Listed by - Johnston
Date - Sept 3 1967

SURVEY RESULTS

LR - 224-69

Lab. Page 1995

Firm Wah Chang S & R, Glen Cove, N.Y.

Install # L0464

☐ Sealed; ☒ Unsealed

of Samples 18

☐ Q tip; ☒ Filter; ☐ Other

Nuclides ²³²Th

Survey Date 9/13/69

Radiophysicist L. Schuss

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) ± 3σ	REMARKS
			GROSS	NET ± σ		
55	1	535	15	35.67	31.27 ± 2.00	See diagram.
56	2	1,272	15	84.60	80.40 ± 2.99	
57	3	273	15	18.20	13.60 ± 1.50	
58	4	301	15	20.07	15.67 ± 1.56	
59	5	319	15	21.27	16.87 ± 1.60	
61	6	162	15	10.80	6.40 ± 1.23	
62	7	117	15	7.80	3.40 ± 1.10	
63	8	90	15	6.00	1.60 ± 1.02	
64	9	62	15	4.13	-0.27 ± 0.92	
65	10	119	15	7.93	3.53 ± 1.11	
66	11	99	15	6.60	2.20 ± 1.05	
67	12	54	15	3.60	-0.80 ± 0.89	
68	13	62	15	4.13	-0.27 ± 0.92	
69	14	92	15	6.13	1.73 ± 1.03	
71	15	98	15	6.54	2.14 ± 1.05	
72	16	28	5	5.60	1.20 ± 1.00	(In Furnace Room) Closed car with blended powder in Warehouse - Unopened shipping container with unblended Th. Nitrate Floor near containers.
3	1	38	5	7.60	3.20 ± 1.10	
4	18	30	7.5	4.00	-0.40 ± 0.92	

Count for $\alpha + \beta$ vs Po^{210} Std, Instrument 4318 S-104 Detector P-10, gas, prop. Windowless

Voltage 2000 Gain $\times 5.4$ uncorrected Date Counted 9/11-15/69 Radiochemist RFB/LSC

Background 4.40 of 10 CPM; Factor $\times 0.8925$ pCi/cpm (net) Total $\alpha + \beta$ no Po^{210} Std = 163.70 pCi $\alpha + \beta$

$3\sigma = 2.6774$

Robert F. Blair 10/6/69
SIGNATURE (UNIT REVIEW)

Edward Stern 10/6
SIGNATURE (SECTION REVIEW)

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880826/11

04/15/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/08/88 RECEIVED: 04/08/88

SAMPLE: Water sample, GM-9

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluomethane	ug/L	<1
Vinyl Chloride	ug/L	32
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluomethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	220
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	2
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	140
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	1600

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<2
12 Dichlorobenzene	ug/L	<2
14 Dichlorobenzene	ug/L	<2
Benzene	ug/L	<1
Toluene	ug/L	<2
Ethyl Benzene	ug/L	<1
m Xylene	ug/L	<2
o+p Xylene	ug/L	<4
Calcium as Ca	mg/L	55
Cobalt as Co	mg/L	<0.00
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	34
Mercury as Hg	mg/L	<0.00
Lead as Pb	mg/L	<0.00
Chromium as Cr	mg/L	<0.00
Cadmium as Cd	mg/L	<0.00
Arsenic as As	mg/L	<0.00
Tantalum	mg/L*	0.11
Tungsten	mg/L*	<0.10
Chloride as Cl	mg/L	43
Nitrate as N	mg/L	1.0
Sulfate as SO4	mg/L	150

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.

DIRECTOR

nn=

3089

104213

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C980099/1

04/27/88

Garaghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-10

ANALYTICAL PARAMETERS

Chloroethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethene	ug/L	11
11 Dichloroethane	ug/L	4
12 Dichloroethene	ug/L	65
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	200
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	58
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2-chloroethoxyethyl ether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethane	ug/L	<2
Tetrachloroethene	ug/L	30

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

cc:

REMARKS:

Page 1 of 2.

DIRECTOR

104214

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C0002997/1

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/19/88

SAMPLE: Water sample, GM-10

ANALYTICAL PARAMETERS

Calcium as Ca	mg/L	21
Cobalt as Co	mg/L	0.024
Nickel as Ni	mg/L	0.10
Sodium as Na	mg/L	12
Mercury as Hg	mg/L	0.00025
Lead as Pb	mg/L	0.005
Chromium as Cr	mg/L	0.005
Cadmium as Cd	mg/L	0.001
Arsenic as As	mg/L	0.002
Tantalum	mg/L*	0.01
Tungsten	mg/L*	0.40
Chloride as Cl	mg/L	14
Nitrate as N	mg/L	26
Sulfate as SO4	mg/L	48
Spec. Cond. umho/cm		260
pH	units	5.6

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

DIRECTOR

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C830099/2

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-11

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

CC1

REMARKS:

Page 1 of 2.

DIRECTOR

104216

1170

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880899/2

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainville, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/19/88

SAMPLE: Water sample, GM-11

ANALYTICAL PARAMETERS


Calcium as Ca	mg/L	20
Cobalt as Co	mg/L	<0.005
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	14
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	<0.005
Chromium as Cr	mg/L	<0.005
Cadmium as Cd	mg/L	<0.001
Arsenic as As	mg/L	<0.002
Tantalum	mg/L*	<0.01
Tungsten	mg/L*	0.11
Chloride as Cl	mg/L	22
Nitrate as N	mg/L	3.5
Sulfate as SO4	mg/L	50
Spec. Cond. umho/cm		240
pH	units	6.2

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

DIRECTOR



104217

ECOTEST LABORATORIES, INC.**ENVIRONMENTAL TESTING****377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777**

LAB NO. C830099/2

04/27/88

Geraghty & Miller, Inc.
 125 East Bethpage Rd.
 Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-11

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

CC1

REMARKS:

Page 1 of 2.

DIRECTOR

104218

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C800899/3

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainville, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342101

COLLECTED BY: Client DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-12

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethane	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethane	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropene	ug/L	<2
13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS


Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

cc:

REMARKS:

Page 1 of 2.

DIRECTOR



ECOTEST LABORATORIES, INC.**ENVIRONMENTAL TESTING****377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777**

LAB NO. C880899/3

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342L101

COLLECTED BY: Client DATE COL'D: 04/15/88 RECEIVED: 04/19/88

SAMPLE: Water sample, GM-12.

ANALYTICAL PARAMETERS

Calcium as Ca	mg/L	110
Cobalt as Co	mg/L	<0.005
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	29
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	<0.005
Chromium as Cr	mg/L	<0.005
Cadmium as Cd	mg/L	<0.001
Arsenic as As	mg/L	<0.002
Tantalum	mg/L*	<0.01
Tungsten	mg/L*	<0.01
Chloride as Cl	mg/L	65
Nitrate as N	mg/L	<0.5
Sulfate as SO ₄	mg/L	150
Spec. Cond. umho/cm		790
pH	units	6.2

ANALYTICAL PARAMETERS

cc:

REMARKS: Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

DIRECTOR

104220

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880899/4

24/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01
COLLECTED BY: Client DATE COL'D: 04/15/88 RECEIVED: 04/19/88

SAMPLE: Water sample, GM-13

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluomethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluomethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	13
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	5
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	11
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

cc:

REMARKS:

Page 1 of 2.

104221

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422;5777

LAB NO. C880879/4

04/27/80

Gonaghty & Miller, Inc.
125 East Rotherg Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01
COLLECTED BY: Client DATE COL'D:04/15/80 RECEIVED:04/18/80

SAMPLE: Water sample, GM-13

ANALYTICAL PARAMETERS		
Calcium as Ca	mg/L	120
Cobalt as Co	mg/L	0.040
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	96
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	<0.005
Chromium as Cr	mg/L	<0.005
Cadmium as Cd	mg/L	<0.001
Arsenic as As	mg/L	0.002
Tantalum	mg/L*	<0.01
Tungsten	mg/L*	<0.01
Chloride as Cl	mg/L	25
Nitrate as N	mg/L	<0.5
Sulfate as SO4	mg/L	430
Spec. Cond. umho/cm		1060
pH	units	6.1


ANALYTICAL PARAMETERS

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

104222

DIRECTOR



ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. 0880899/5

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glaszer

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-14A

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS


Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	3
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

CCL:

REMARKS:

Page 1 of 2.

DIRECTOR



104223

100

3302

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTS

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880899/5

24/27/89

Goraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01
COLLECTED BY: Client DATE COL'D:04/15/88 RECEIVED:04/19/89

SAMPLE: Water sample, GM-14A

ANALYTICAL PARAMETERS


Calcium as Ca	mg/L	370
Cobalt as Co	mg/L	0.40
Nickel as Ni	mg/L	0.20
Sodium as Na	mg/L	6,600
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	0.070
Chromium as Cr	mg/L	0.050
Cadmium as Cd	mg/L	<0.002
Arsenic as As	mg/L	0.78
Tantalum	mg/L*	2.26
Tungsten	mg/L*	39.40
Chloride as Cl	mg/L	700
Nitrate as N	mg/L	1.0
Sulfate as SO4	mg/L	11000
Spec. Cond. umho/cm		20,200
pH	units	7.4

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trouton N.J.; report enclosed.
Page 2 of 2.

DIRECTOR



104224

3436

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C28009976

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-15

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethane	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethane	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
1 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS


Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

CC:

REMARKS:

Page 1 of 2.

DIRECTOR



104225

1353

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880879/6

04/27/09

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainville, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342L101

COLLECTED BY: Client DATE COL'D: 04/15/09 RECEIVED: 04/19/09

SAMPLE: Water sample, GM-15

ANALYTICAL PARAMETERS

Calcium as Ca	mg/L	48
Cobalt as Co	mg/L	0.030
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	48
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	<0.005
Chromium as Cr	mg/L	<0.005
Cadmium as Cd	mg/L	<0.001
Arsenic as As	mg/L	0.002
Tantalum	mg/L*	<0.01
Tungsten	mg/L*	0.16
Chloride as Cl	mg/L	120
Nitrate as N	mg/L	<0.5
Sulfate as SO4	mg/L	48
Spec. Cond. umho/cm		640
pH	units	6.2

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

DIRECTOR

3437

104226

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C890877/7

04/27/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-16

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluoromethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluoromethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<1

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<1
12 Dichlorobenzene	ug/L	<1
14 Dichlorobenzene	ug/L	<1
Benzene	ug/L	<1
Toluene	ug/L	<1
Ethyl Benzene	ug/L	<1
m + p Xylene	ug/L	<2
o Xylene	ug/L	<1

cc:

REMARKS:

Page 1 of 2.

DIRECTOR

104227

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. CBB0899/7

04/27/88

Conaghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01
COLLECTED BY: Client DATE COL'D: 04/15/88 RECEIVED: 04/18/88

SAMPLE: Water sample, GM-16

ANALYTICAL PARAMETERS

Calcium as Ca	mg/L	14
Cobalt as Co	mg/L	0.010
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	7.9
Mercury as Hg	mg/L	<0.00025
Lead as Pb	mg/L	<0.005
Chromium as Cr	mg/L	<0.025
Cadmium as Cd	mg/L	0.007
Arsenic as As	mg/L	<0.002
Tantalum	mg/L*	<0.01
Tungsten	mg/L*	<0.01
Chloride as Cl	mg/L	8
Nitrate as N	mg/L	<0.5
Sulfate as SO4	mg/L	200
Spec. Cond. umho/cm		140
pH	units	6.2

ANALYTICAL PARAMETERS

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.
Page 2 of 2.

104228

DIRECTOR


FIGURES



COMPILED BY V. GLASSER
PREPARED BY G. SCHAFFNER
PROJECT NO. V. GLASSER

DATE: 4-88
SCALE: SHOWN
FILE NO.: N1342L2-1047

RTP ENVIRONMENTAL ASSOC., INC.
Glen Cove, New York



SUBJECT:

SITE LOCATION, LI TUNGSTEN FACILITY,
GLEN COVE, NEW YORK

FIGURE
1



GERAGHTY
& MILLER, INC.
Ground-Water Consultants

COMPILED BY V GLASSER

PREPARED BY S. SCHAFFNER

PROJECT FOR V GLASSER

DATE

4-88

SCALE


SHOWN

PREPARED FOR

RTP ENVIRONMENTAL ASSOC., INC.
Glen Cove, New York

FILE NO.

NI342LII-1047



EXPLANATION

II

PARCEL NUMBER



MONITORING WELL LOCATION



PROPERTY/PARCEL
BOUNDARY



DIRT ROAD

SUBJECT

LOCATION OF MONITORING WELLS, LI TUNGSTEN FACILITY,
GLEN COVE, NEW YORK

104231

FIGURE


2-



GERAGHTY
& MILLER, INC.
Ground-Water Consultants

COMPILED BY	V. GLASSER	DATE	4-88	SCALE	SHOWN
PREPARED BY	G. SCHAFFNER	FILE NO.			
PROJECT NO.	V. GLASSER	N1342LII-1047			

RTP ENVIRONMENTAL ASSOC., INC.
Glen Cove, New York



EXPLANATION

II

PARCEL NUMBER

●

SAMPLING LOCATION

PROPERTY/PARCEL
BOUNDARY

==

DIRT ROAD


SUBJECT:

SOIL SURVEY SAMPLING LOCATIONS, LI TUNGSTEN FACILITY,
GLEN COVE, NEW YORK

FIGURE

3

104232



EXPLANATION

- II** PARCEL NUMBER
- DIRECTION OF HORIZONTAL COMPONENT OF GROUND-WATER FLOW
- MONITORING WELL LOCATION
- (P)** MONITORING WELL INSTALLED IN PERCHED GROUND-WATER SYSTEM
- 6** LINE OF EQUAL WATER-TABLE ELEVATION IN FEET ABOVE MEAN SEA LEVEL (DASHED WHERE INFERRED)

NOTE: REFER TO TABLE 2 FOR WATER LEVEL ELEVATIONS MEASURED IN MONITORING WELLS ON 4-26-88

CONFIGURATION OF THE WATER TABLE ON APRIL 26, 1988

FIGURE

4

104233

SURVEY RESULTS

LR 224 6 9

Lab. Page 1996

Firm Wah Chang S & R Glen Cove, NY

Install # L-0464

Sealed: ☒ Unsealed

of Samples 18 ☐ Q tip; ☒ Filter; ☐ Other Nuclides ^{226}Ra

Survey Date 9/13/69 Radiophysicist LS

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 3\sigma$	REMARKS
			GROSS	NET ± 0		
1	179	10	17.90	17.25 ± 1.36	14.98 ± 3.54	Other 4318-ctg:
2	499	10	49.90	49.25 ± 2.25	42.77 ± 5.86	
3	86	10	8.60	7.95 ± 0.96	6.90 ± 2.50	Beta - roughly same
4	71	10	7.10	6.45 ± 0.54	5.60 ± 2.19	
5	68	10	6.80	6.15 ± 0.97	7.08 ± 2.53	becomes ~ 1/2 as much
6	38	10	3.80	3.15 ± 0.67	2.74 ± 1.75	
7	12	10	1.20	0.55 ± 0.78	0.48 ± 2.03	on P. 1995
8	26	10	2.60	1.95 ± 0.57	1.69 ± 1.49	
9	8	10	0.80	0.15 ± 0.38	0.13 ± 0.99	I mainl. SV/BO as
10	21	10	2.10	1.45 ± 0.52	1.26 ± 0.35	
11	8	10	0.80	0.15 ± 0.38	0.13 ± 0.99	th 1's too low in energy to effectively penetrate
12	18	10	1.80	1.15 ± 0.49	1.00 ± 1.28	
13	29	10	2.90	2.25 ± 0.60	1.95 ± 1.56	Shielding between detector & plastic
14	13	10	1.30	0.65 ± 0.44	0.56 ± 1.15	
15	14	10	1.40	0.75 ± 0.45	0.65 ± 1.17	B scintillator on 4318 system
16	6	10	0.60	-0.05 ± 0.35	-0.04 ± 0.91	
17	20	10	2.00	1.35 ± 0.51	1.17 ± 1.33	See also TMC data P. 1998
18	4	10	0.40	-0.25 ± 0.32	-0.22 ± 0.83	

Count for α vs Ra^{226} Std. Instrument 4318 A-104 Detector P-10 gas, Prop Windows

Voltage 1200 Gain α 5.4 inoperable Date Counted 9/16-17/69 Radiochemist RFR/LSC

Background 0.65 CPM: Factor 2 = 0.5855 pCi/cpm (net) Total α vs Ra^{226} = 7.09 pCi TL

of 10

$3F_2 = 2.6055$

Robert F. Pilais 10/6/69

SIGNATURE (UNIT REVIEW)

D. P. Howard 10/6

SIGNATURE (RECT. REVIEW)

SURVEY RESULTS

111.2 hours

LR 224 69

Lab. Page 1998

Firm Waa Chang STR W. Y. Waa Chang

Install # L-0464

Sealed: ☒ Unsealed# of Samples 18 ☐ Q tip; ☒ Filter; ☐ Other Nuclides Th^{232} Survey Date 9/3/69 Radiophysicist L.S.

SAMPLE #	GROSS COUNTS	T (MIN)	CPM		ACTIVITY (pCi) $\pm 3\sigma$	REMARKS
			GROSS	NET $\pm 3\sigma$		
<p>The 18 fgs assa groups were subjected to TMC analysis on 9/11/69 0-2.0 Mev in $1/2$, 1.0 min net, DT < 0.5%, 10^2 CRT appeared to be mainly a S.V.C. Low NIX on 3 phases on 5 $137Th$, 5 $170Ra$, 5 $199Th$ 0-2.0 Mev. Calcn from these data appear below:</p>						
					for Th^{232} ch 5 $137Th$	Bkgd = 114 cpm $F_2 = 1,8595$ $3F_2 = 5,5785$
18 fgs	126	126	126	12 ± 4.90	22.31 ± 27.33	pli Th^{232} / 18 fgs. gyp.
						for Ra^{226} area 5 $170Ra$ Bkgd = 158 $F_2 = 1502$ $3F_2 = 4,506$
18 fgs	171	1.0	171	13 ± 5.94	19.53 ± 25.86	pli Ra^{226} area / 18 fgs. gyp.
						for 0-2.0 Mev area 5 $199Th$ Bkgd = 194 $F_2 = 1,2603$ $3F_2 = 3,7808$
18 fgs	214	1.0	214	15 ± 6.43	18.90 ± 24.31	pli 0-2.0 Mev area / 18 fgs.
<p>Each value agrees fairly well, so activity ^{present} mainly due to Th^{232}</p>						

Count for Th^{232} vs Th^{232} Std, Instrument TALE 4000 $\pm 1\%$ Detector 3" NaI crystal
 Voltage 1000 Gain 216 0-2.0 Mev in $1/2$ in 200 cks Date Counted 9/11/69 Radiochemist R.F.F./L.S.C
 Background 100 ± 10 CPM; Factor 100 ± 10 pCi/cpm (net)

Robert F. Blair 10/6/69
SIGNATURE (UNIT REVIEW)Dr. Edward Stein 10/6
SIGNATURE (SECTION REVIEW)

224 6 9

DIAGRAM OF SURVEYED AREA

Radiophysicist

E. Schuster

Installation #

L 0464

Date

3/3/63


Firm

Nash Chang & R


Address

Klen Cove R. I.

BLENDING ROOM



FURNACE ROOM



H: Hard; S: Soft; a: Alpha; n: Neutron

Red Numerals: Radiation in MREM/HR

Green Numerals: Smear Numbers

Blue Circled Smear Numbers: Greater Than 3 x Background Standard Deviation or as Indicated

104236

WATER GROUND CONTAMINATION
GRANULAR, NO. 1

RADIATION SURVEY REPORT

Date Mar 15 1959


Air Sampling By B. K. Blair

Extending Room

Wipe Samples By _____

WIFE SAMPLES

W1	<u>60</u>	DPM
W2	<u>25</u>	DPM
W3	<u>52</u>	DPM
W4	<u>46</u>	DPM
W5	<u>49</u>	DPM
W6	<u>49</u>	DPM
W7	<u>46</u>	DPM
W8	<u>35</u>	DPM
W9	<u>18</u>	DPM
W10		DPM



SANSON METER
READINGS

M1	_____	CPM
M2	_____	CPM
M3	_____	CPM
M4	_____	CPM
M5	_____	CPM
M6	_____	CPM
M7	_____	CPM
M8	_____	CPM
M9	_____	CPM
M10	_____	CPM

AIR SAMPLING STATIONS:

A2 (Loading) at 2500M, Sampling Time 15 Min., Shows 7 DPM/100 cpm
A2 (Unloading) at 15 CPM, Sampling Time 15 Min., Shows 7 DPM

Signed

[Signature]

Radiation Officer

WAM CHANG COMBINATION

Glen Cove, N. Y.

RADIATION SURVEY REPORT

Date Mar 6 1959


Air Sampling By Paul Little

Reduction Formula No.

Notes Tests By

WIPE SAMPLES

W1	<u>49</u>	DFM/100 cm ²
W2	<u>28</u>	DFM
W3	<u>14</u>	DFM
	<u>11</u>	DFM
W5	<u>49</u>	DFM
W6	<u>42</u>	DFM
W7	<u>31</u>	DFM
W8	<u>46</u>	DFM
W9	<u>42</u>	DFM
W10	<u>25</u>	DFM



SAMSON METER READINGS

M1	_____
M2	_____
M3	_____
M4	_____
M5	_____
M6	_____
M7	_____
M8	_____
M9	_____
M10	_____

AIR SAMPLING STATIONS:


A1 (Weighing)	at 35 CFM, Sampling Time	<u>15</u> Min., Shows	<u>11</u> DFM/100 cm ²
A2 (Elevator)	" " "	<u>15</u> Min., Shows	<u>14</u> DFM
A3 (Unloading)	" " "	<u>15</u> Min., Shows	<u>21</u> DFM
A4 (Rotop)	" " "	<u>15</u> Min., Shows	<u>11</u> DFM

Signed

Paul Little

Radiation Officer

104238



STATE OF NEW YORK DEPARTMENT OF LABOR
BUREAU OF INDUSTRIAL HYGIENE
RADIOLOGICAL HEALTH UNIT
28 Centre Street
New York, N. Y. 10013

NOTICE OF INSPECTION FINDINGS

1. Date
2. Type Visit

3. Firm Name & Address			4. No. Employees Exposed Male Female	
5. Confines of Installation				
6. Registration No	7. License No.(s)	8. Industrial Code	9. Radiation Safety Officer	

10. Findings

- ☐ A. No item of non-compliance found.
☐ B. The following paragraphs of Code Rule 38, or conditions of your license were found in violation.

(47 <input type="checkbox"/> 4)	(<input type="checkbox"/> 23)	(19 <input type="checkbox"/> 34.1)
(<input type="checkbox"/> 5.1)	(47 <input type="checkbox"/> 24)	(20 <input type="checkbox"/> 34.2)
(<input type="checkbox"/> 6.2)	(47 <input type="checkbox"/> 25)	(21 <input type="checkbox"/> 34.3)
(<input type="checkbox"/> 9.1)	(15 <input type="checkbox"/> 26.2)	(47 <input type="checkbox"/> 34.4)
(<input type="checkbox"/> 9.1)	(15 <input type="checkbox"/> 26.3)	(<input type="checkbox"/> 35.1)
(<input type="checkbox"/> 9.1)	(15 <input type="checkbox"/> 26.4)	(47 <input type="checkbox"/> 35.2)
(47 <input type="checkbox"/> 10)	(30 <input type="checkbox"/> 26.5)	(25 <input type="checkbox"/> 36.1a)
(47 <input type="checkbox"/> 11)	(47 <input type="checkbox"/> 26.6)	(9 <input type="checkbox"/> 36.1b)
(47 <input type="checkbox"/> 20)	(47 <input type="checkbox"/> 28)	(24 <input type="checkbox"/> 36.1c)
(10 <input type="checkbox"/> 21.1)	(16 <input type="checkbox"/> 30)	(47 <input type="checkbox"/> 36.2)
(11 <input type="checkbox"/> 21.2)	(<input type="checkbox"/> 31.2)	(28 <input type="checkbox"/> 37.2)
(13 <input type="checkbox"/> 22.1)	(18 <input type="checkbox"/> 32)	(31 <input type="checkbox"/> 39)
(14 <input type="checkbox"/> 22.2)	(18 <input type="checkbox"/> 33)	(<input type="checkbox"/>)
(<input type="checkbox"/>)	(<input type="checkbox"/>)	(<input type="checkbox"/>)

11. Remarks

12. The violations indicated above should be removed within _____ days.

13. Signature of Department Representative

14. DATE	15. REVIEWED BY	16. DISPOSITION
10-13-67	JS	Compl. 1-68
2-28-68	JS	" 4-68
5-10-68	JS	" 6-68
7-11-68	JS	" 8-68
9-13-68	JS	" 10-68

REPORT ON COMPLIANCE VISIT

17. DATE	18. PERSON CONTACTED	19. REASON FOR NON-COMPLIANCE
5/16/68	H. Lee	26.4 - IC 26.1 - Firm looking into meeting, not complete. Technology is offered to purchasing officer - Firm to be non-compliance within 60 days.
7/1/68	H. Lee	26.4 - Firm has located a scale and is in process of purchasing an X scent detector. Should be in compliance by end of Aug.
1/17/68	H. Lee	26.4 - X Identification probe & X source ordered on 5/20/68. Should be received by end of July.
1/23/68	H. Lee	26.4 - X counter & X source received but equipment not functioning properly with old scale - equipment was sent to B/A for repair. Should be functioning properly by end of Sept.
1/25/68	H. Lee	26.4 - Necessary equipment now functioning properly

New York State Department of Labor

Radiation Survey

Compliance Information

(Note to Radiophysicist: Fill out in advance as much of the information as possible from company folder)

Date 9/26/67

Radiophysicist J. J. J.

License/Registration No. 1002000000

A. Administrative Information

1. Name of installation or plant

West Chong Smelting & Refining Co.

2. Address No. and Street 63 Hazel Rd.

City Chong Chong

County Yunnan

3. Person(s) interviewed:

Name

Title

a. H. Lee Chief Chemist

b. _____

c. _____

4. Type of industry

Metal Refining

b. Industrial Code Rule No. 38

Rule No.

1. All radiation sources in plant have been registered/licensed:

yes ☒ no _____

38-4, 38-5

2. Exempt quantities of radioactive material have not been combined or increased:

yes _____ no _____

38-6.1

3. If an exempt device (U.S. AEC general license) has been received

a. the Industrial Commissioner has been notified:

yes _____ no _____

38-6.2(a)

104241

b. it has been disposed of in approved manner:

yes ____ no ____

38-6.2(b)

c. it has affixed to it an approved label:

yes ____ no ____

38-6.2(c)

d. the conditions of exemption (USAEC general license) have been complied with:

yes ____ no ____

38-6.2(d)

e. the device has been leak tested and on/off mechanism checked every six months (or as provided in U.S. AEC/other agreement state general license) (Kr-85 no leak test required, H-3 no leak or operation required)

yes ____ no ____

i. the last test was _____

ii. results affixed to this report

yes ____ no ____

38-6.2(e)

f. testing and servicing of exempt (U.S. AEC generally licensed) device performed by duly licensed person or firm

yes ____ no ____

License No. _____

38-6.2(f)

g. any indication of possible leakage or damage to device has been investigated:

yes ____ no ____

(Action taken) _____

38-6.2(g)

4. Has there been any changes in proposed use, equipment, facilities, procedures, or personnel from those on registration/license:

yes ____ no X

38-8(a) &
(b)

New personnel

Title

a. _____

b. _____

c. _____

5. What licensed material has been received since last inspection

	Isotope	Activity (μ c, mc, c)	
a.	<u>Th. 150</u>	<u>about 1000</u>	
b.	_____	_____	
c.	_____	_____	38-9.1

6. What licensed material has been shipped off-site (other than as waste) (Use another sheet, if necessary.)

	Isotope	Activity	Sent To	License/Registration
a.	<u>Th.</u>	<u>shipped to</u>	<u>all</u>	<u>welding - etc.</u>
b.	_____	_____	_____	_____
c.	_____	_____	_____	_____
d.	_____	_____	_____	_____

38-9.2

7. Is special nuclear material (U-235, U-233, Pu-239) covered by this

license: Yes _____ No X

Has special nuclear material been produced under this license:

Yes _____ No X

How much: _____

38-10

8. Is this license still valid: Yes X No _____

Expiration Date on license until 1960

38-11

9. Has there been any violation(s) or failure(s) to observe the Industrial Code Rule 38 or any other applicable rule, regulation, code or order to your knowledge? Yes _____ No _____

Enumerate a. _____

b. _____

38-14

10. Has a license or permit been issued by N.Y.S. or N.Y.C. Dept. of

Health to you? Yes _____ No X

Have you transported and used radioactive material or radiation producing devices in another state: Yes _____ No X

State _____

38-18

104243

11. Is a U.S. Atomic Energy Commission License held?

Yes ☐No ☒

U.S. AEC Lic. No. _____

38-19

C. Radiation Protection Program

1. Personnel dosimetry

a. External Exposure (Whole Body)

No. of Persons Working with Ionizing Radiation	No. of Persons Wearing Film Badges (WB)	Number in Given Dose			
		0 or N.D.	0-3	3-5	5+
		rem y	rem y	rem y	rem y
115					

b. External Exposure (Extremities)

No. of Persons Working with Ionizing Radiation	No. of Persons Wearing Wrist or Finger Badges	Number in Given Dose		
		0 or N.D.	0-25	25-75
		rem y	rem y	rem y
115				

c. No. of Exposed Persons Under 18 years of Age NH

d. Are Cumulative Lifetime Dose Records maintained for exposed personnel:

Yes ☐No ☒

38-21.1

2. Is radiation dose, acquired by personnel at other place of employment,
maintained in this facility? Yes ☐ No ☒

38-21.1

3. Is the airborne activity in controlled areas monitored?

Yes ☒No ☐

38-21.2

4. If yes:

Nuclide (s)	Location	Concentration ($\mu\text{c}/\text{cm}^3$)
a. <u>radiation</u>	<u>sample contained with</u>	
b. <u>a</u>	<u>sample meter and machine</u>	
c. <u>sample</u>	<u>in the area</u>	
d.		
e.		

104244

5. Is there any potential exposure of persons in uncontrolled area?

Yes K

No

2000 00000 000000

If yes: a. External Exposure (copy of survey is adequate)

Nuclide(s)/Machine	Location	Dose Rate
a.		
b.		
c.		
d.		
e.		

38-22.1

b. Internal Exposure

not monitored

Nuclide(s)	Location	Concentration($\mu\text{C}/\text{cm}^3$)
a.		
b.		
c.		
d.		
e.		

38-22.2

6. Disposal of Radioactive waste

Solid

Date	Vendor	Activity
a.		
b.	<i>10000</i>	
c.		
d.		

Liquid

Date	Vendor or Sink Disposal	Activity
a.		
b.	<i>10000</i>	
c.		
d.		

Gas

D	Vendor or Atmospheric Disposal	Activity
a.		
b.	<i>1000</i>	
c.		
d.		

7. Has there been any human use of radioactivity under this license?

30-23

Yes _____ No X

8. Name of Radiation Safety Officer is H. Lee

38-24

His experience with ionizing radiation is (if not on application)

38-25

9. Survey Instruments (If not on application)

Mfg. Name	Model & Serial No.	How often Calibrated	Last Calibrated
a. <i>Samson</i>			<i>1964</i>
b. <i>New Chicago - G.H.</i>			<i>1964</i>
c.			
d.			

38-26.1

10. Surveys:

Radiation Equipment: How often NA Last _____

38-26.2

Radioactive Materials (sealed):
(How often) NA Last _____

38-26.3

38-26.5

Leak test of Sealed Sources: Date: NA

Result _____ μ c

Performed by: _____

11. Radioactive Materials (unsealed) Survey: How often _____ Last 5/1/6 3C-26.4

12. Are interlocks and timers in good shape?

Yes NA No _____

Last checked _____

By _____

33-26.6

13. Are instructions given to personnel re:

eating, drinking and smoking in controlled areas

Yes _____ No NA

Instructions Posted Yes _____ No _____

33-28

14. Has any controlled area been vacated or converted to other use?

Yes _____ No X

38-29

If yes, attach copy of final survey

15. Are all controlled areas marked with the proper radiation hazard symbol and clearly visible?

Yes _____ No _____

Location(s) marked with "Radiation Area" Signs _____

(5-100 mrem/hr)

Location(s) marked with "High Radiation Area" Signs _____

(>100 mrem/hr)

Location(s) marked with "Airborne Radioactivity Area" _____

Location(s) marked with "Radioactive Material(s) Sign 2

(normally in Radiation Areas)

38-31

16. Labels on container(s): Are all container(s) properly marked which contain (a) radioactive material in quantities greater than that listed in Table (4) other than U or Th and (b) U or Th in quantities 10 times greater than that listed in Table (4). Yes X NO

Are radioisotope storage containers marked with label which states activity and nuclide with date? Yes No X

38-32

17. Are all radiation producing machines other than Medical and Dental X-Ray Units marked with hazard symbol and appropriate cautionary wording? Yes No NA

38-33

18. Have all persons who work in control areas been instructed in (a) presence of radiation, (b) procedures to minimize exposure to radiation, (c) applicable provisions of Code Rule 36, and (d) personnel dosimetry including bioassay the need for, and his rights to foregoing information: Yes X No

38-34.1

19. Do you keep available for employees: Copies of Code Rule 38, license(s) or registration(s) covering radiation, and operation procedures? Yes X No

38-34.2

20. Is the "Notice to Employees" posted so that employees can read it on their way to or from controlled areas? Yes X No

38-34.3

21. How and where are radiation sources stored when not in use?

Location store room

Is there any flammable, toxic materials stored in same location: Yes No X

If yes, give description

38-35.1

In your opinion will this storage area provide reasonable protection against

Rule No.

loss, leakage or dispersion by fire effects, water, hose streams
or other means used to fight fire.

yes _____ no _____

If no; what is being done to improve storage? _____

33-35.2

22. Records:

a. Survey, check, and test records. yes X no _____

b. Transfer, receipt, and disposal of radioactive materials
records. yes _____ no X

c. Personnel Dosimetry records. yes _____ no X

d. Bio-assay and medical evaluation service records.

yes _____ no X

33-36.1

23. Dose, bio-assay and medical evaluation service records are
on approved forms. yes _____ no X

These records are preserved for how long: X year(s)

All other records are preserved for 2 years year(s)

33-36.2

24. Has there been:

a. Any theft or loss of any radiation source?

yes _____ no X

Date of last inventory check _____

b. Any incident involving such radiation source which may have
caused or threatens to cause any individual to receive a dose
that exceeds the limit permitted by this Rule.

yes _____ no X

If yes, give details:

104249

- c. Any level of radiation from, or release of, a concentration of radioactive material in any uncontrolled area that exceeds 10 times the limit permitted by this Rule or any applicable license:

yes _____ no ✓

If yes, give details:

- d. Was this reported to the Commissioner? yes _____ no _____

If yes:

Date _____ By _____

36-37

25. Has any employee(s) (present or past) requested information on the dose he has received? yes _____ no ✓

Note: Attach a copy of form on which this information is reported.

36-37.2

26. A meter and/or smear radiation survey was made at _____ by _____ and results are attached.

End of Report

Date 9/24/67

Time _____

By [Signature]

Note: Any person (firm) may petition the Board of Standards and Appeals: "If there shall be practical difficulties or unnecessary hardship in carrying out provisions of this rule".

1238 St

5500-6000 g/m² =

10,000 to 12,000 cfm

WAH CHANG CORPORATION

Glen Cove, N. Y.

RADIATION SURVEY REPORT

Date Sept 14 1966

Air Sampling By _____

Reduction Furnace No. 8

Meter Tests By F. H. Lee

WIPE SAMPLES		A4 rotap - W10		SAMSON METER READINGS	
W1	<u>None</u> CPM			M1	<u>1X325</u>
W2	<u>1X20</u> CPM			M2	<u>1X125</u>
W3	<u>1X20</u> CPM			M3	<u>5X200</u>
W4	<u>1X20</u> CPM			M4	<u>1X150</u>
W5	<u>1X10</u> CPM			M5	<u>1X25</u>
W6	<u>1X20</u> CPM			M6	<u>1X50</u>
W7	<u>1X30</u> CPM			M7	<u>1X50</u>
W8	<u>1X50</u> CPM			M8	<u>1X10</u>
W9	<u>1X40</u> CPM			M9	<u>1X50</u>
W10	<u>1X40</u> CPM			M10	<u>1X50</u>

AIR SAMPLING STATIONS:

A1 (Weighing) at 15 CFM, Sampling Time _____ Min., Shows _____ CPM
 A2 (Elevator) " " " _____ Min., Shows _____ CPM
 A3 (Unloading) " " " _____ Min., Shows _____ CPM
 A4 (Rotap) " " " _____ Min., Shows _____ CPM

to: No air sampling was
 taken since there was no
 production of thionated tungsten powder.

Signed _____

Radiation Officer

104251



DEPARTMENT OF INDUSTRIAL HYGIENE
RADIOLOGICAL HEALTH UNIT
80 Centre Street
New York, N. Y. 10013

NOTICE OF INSPECTION FINDINGS

1. Date	2/1/66
2. To: Visit	

3. Firm Name & Address <u>Wash. Cranes Smelting & Refining Co. 6-3/4th Hill Rd. Chubbuck</u>		4. No. Employees Exposed Male <u>10</u> Female <u>0</u>	
5. Confines of Installation <u>Wash. Cranes Smelting & Refining Co.</u>			
6. Registration No.	7. License No.(s) <u>743-0464</u>	8. Industrial Code <u>33</u>	9. Radiation Safety Officer <u>H. Lee</u>

10. Findings

- ☐ A. No item of non-compliance found.
☒ B. The following paragraphs of Code Rule 38, or conditions of your license were found in violation.

(47 <input type="checkbox"/> 4)	(<input type="checkbox"/> 23)	(19 <input type="checkbox"/> 34.1)
(<input type="checkbox"/> 5.1)	(47 <input type="checkbox"/> 24)	(20 <input type="checkbox"/> 34.2)
(<input type="checkbox"/> 6.2)	(47 <input type="checkbox"/> 25)	(21 <input type="checkbox"/> 34.3)
(<input type="checkbox"/> 9.1)	(15 <input type="checkbox"/> 26.2)	(47 <input type="checkbox"/> 34.4)
(<input type="checkbox"/> 9.1)	(15 <input type="checkbox"/> 26.3)	(<input type="checkbox"/> 35.1)
(<input type="checkbox"/> 9.1)	(15 <input checked="" type="checkbox"/> 26.4) <u>Unsealed Source</u>	(47 <input type="checkbox"/> 35.2)
(47 <input type="checkbox"/> 10)	(30 <input type="checkbox"/> 26.5)	(25 <input checked="" type="checkbox"/> 36.1a) <u>Records of Survey</u>
(<input type="checkbox"/> 11)	(47 <input type="checkbox"/> 26.6)	(<input type="checkbox"/> 9 <input type="checkbox"/> 36.1b)
(47 <input type="checkbox"/> 20)	(47 <input type="checkbox"/> 28)	(24 <input type="checkbox"/> 36.1c)
(10 <input type="checkbox"/> 21.1)	(16 <input type="checkbox"/> 30)	(47 <input type="checkbox"/> 36.2)
(11 <input type="checkbox"/> 21.2)	(<input type="checkbox"/> 31.2)	(28 <input type="checkbox"/> 37.2)
(13 <input type="checkbox"/> 22.1)	(18 <input checked="" type="checkbox"/> 32) <u>Radio Material Signs</u>	(31 <input type="checkbox"/> 39)
(14 <input type="checkbox"/> 22.2)	(18 <input type="checkbox"/> 33)	(<input type="checkbox"/>)
(<input type="checkbox"/>)	(<input type="checkbox"/>)	(<input type="checkbox"/>)

11. Remarks

104252

12. The violations indicated above should be removed within 30 days.

13. Charles J. Jones
Signature of Department Representative

11 DATE	12 REVIEWED BY	13 ACTION
7-22-66	ET	Compl Sept. 66 Reg.
10-13-66	ET	

REPORT ON COMPLIANCE VISIT

17 DATE	18 PERSON CONTACTED	19 REASON FOR NON-COMPLIANCE
9/23/66	H. Lee	Complied - sent copy of response survey Made visit to clear up question as to survey report (Re. meter calibration.)
9/28/66	H. Lee	

9/29/66

GJR



Name: KARL BOLDT
 Affiliation: F. C. HART ASSOC.
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Phone: (212) 840-3990
 Client/Job No: 00265-02-00035-01
 Job Name: L1 TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
TEM 1		6/26/89		FILTER	1	ASBESTOS (TEM)
TEM 2		↓		↓	↓	↓
TEM 3		↓		↓	↓	↓
TEM 4		6/27/89		↓	↓	↓
TEM 5		↓		↓	↓	↓
ICP 1		6/26/89		↓	↓	METALS (ICP) ^{NIOSH} 7300
ICP 2		↓		↓	↓	↓
ICP 3		↓		↓	↓	↓
ICP 4		6/27/89		↓	↓	↓
ICP 5		↓		↓	↓	↓

Comments: DETECTION LIMIT OF 1 MG PER NECESSARY FOR ICP METALS, PER NIOSH METHOD 7300.

Relinquished by: Karl Boldt Date: 6/28/89 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704081

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____

HART

Name: KARL BOLDT
 Affiliation: F. C. HART ASSOC.
 Phone: (212) 840-3990
 Address: 530 FIFTH AVE., NEW YORK, NY 10036
 Client/Job No: 00265-02-00035-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
ICP B		6/27/99		FILTER	1	METALS (ICP) NIOSH 7300

Comments: DETECTION LIMIT OF 1 MG NECESSARY FOR ICP METALS, PER NIOSH METHOD 7300

Relinquished by: Karl Boldt Date: 6/28/99 Shipment Method: FED EXP
 Time: 5 PM Airbill No.: 9643704081

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____

APPENDIX E

EcoTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880826/10

04/15/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/08/88 RECEIVED: 04/08/88

SAMPLE: Water sample, GM-7

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluomethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluomethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	<2
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	<1
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	<2

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<2
12 Dichlorobenzene	ug/L	<2
14 Dichlorobenzene	ug/L	<2
Benzene	ug/L	<1
Toluene	ug/L	<2
Ethyl Benzene	ug/L	<1
m Xylene	ug/L	<2
o+p Xylene	ug/L	<4
Calcium as Ca	mg/L	26
Cobalt as Co	mg/L	<0.0
Nickel as Ni	mg/L	<0.1
Sodium as Na	mg/L	28
Mercury as Hg	mg/L	<0.0
Lead as Pb	mg/L	<0.0
Chromium as Cr	mg/L	<0.0
Cadmium as Cd	mg/L	<0.0
Arsenic as As	mg/L	<0.0
Tantalum	mg/L*	0.07
Tungsten	mg/L*	<0.1
Chloride as Cl	mg/L	14
Nitrate as N	mg/L	<0.5
Sulfate as SO4	mg/L	68

CC:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.

104257

DIRECTOR 

EcoTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C880826/9

04/15/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Vince Glasser

SOURCE OF SAMPLE: Glen Cove, NY1342LI01

COLLECTED BY: Client

DATE COL'D: 04/08/88 RECEIVED: 04/08/88

SAMPLE: Water sample, GM-B

ANALYTICAL PARAMETERS

Chloromethane	ug/L	<1
Bromomethane	ug/L	<1
Dichlorodifluomethane	ug/L	<1
Vinyl Chloride	ug/L	<1
Chloroethane	ug/L	<1
Methylene Chloride	ug/L	<2
Trichlorofluomethane	ug/L	<2
11 Dichloroethene	ug/L	<2
11 Dichloroethane	ug/L	<2
12 Dichloroethene	ug/L	7
Chloroform	ug/L	<1
12 Dichloroethane	ug/L	<2
111 Trichloroethane	ug/L	<1
Carbon Tetrachloride	ug/L	<1
Bromodichloromethane	ug/L	<1
12 Dichloropropane	ug/L	<2
t 13 Dichloropropene	ug/L	<2
Trichloroethylene	ug/L	5
Chlorodibromomethane	ug/L	<1
112 Trichloroethane	ug/L	<2
c 13 Dichloropropene	ug/L	<2
2chloroethvinylether	ug/L	<2
Bromoform	ug/L	<2
1122Tetrachloroethan	ug/L	<2
Tetrachloroethene	ug/L	66

ANALYTICAL PARAMETERS

Chlorobenzene	ug/L	<1
13 Dichlorobenzene	ug/L	<2
12 Dichlorobenzene	ug/L	<2
14 Dichlorobenzene	ug/L	<2
Benzene	ug/L	<1
Toluene	ug/L	<2
Ethyl Benzene	ug/L	<1
m Xylene	ug/L	<2
o+p Xylene	ug/L	<4
Calcium as Ca	mg/L	36
Cobalt as Co	mg/L	0.005
Nickel as Ni	mg/L	<0.10
Sodium as Na	mg/L	18
Mercury as Hg	mg/L	<0.00
Lead as Pb	mg/L	<0.00
Chromium as Cr	mg/L	<0.00
Cadmium as Cd	mg/L	0.010
Arsenic as As	mg/L	<0.00
Tantalum	mg/L*	0.27
Tungsten	mg/L*	<0.10
Chloride as Cl	mg/L	26
Nitrate as N	mg/L	0.6
Sulfate as SO4	mg/L	230

cc:

REMARKS: *Analyzed for EcoTest by PTL Testing Laboratories,
Trenton N.J.; report enclosed.

DIRECTOR

rn=

3087

104258

LI TUNGSTEN SITE INVESTIGATION REPORT (Volume 2)

Prepared For:
Campon Realty Corp.
445 Fifth Avenue
New York, NY 10016

Prepared by:
RTP Environmental Associates, Inc.
400 Post Avenue
Westbury, NY 11590

May, 1988

DRAFT

TANK CLEANING PROPOSAL

PROPOSAL

AMERICAN ENVIRONMENT TECHNOLOGIES CORP

38-40 Oak Street
Norwood, New Jersey 07648
Telephone 201-787-8757 NJ
1-800-433-5837

PROPOSAL NO. 926

PROPOSAL SUBMITTED TO: R.T.P. Environmental Associates, Inc.	PHONE: 516-333-4526	DATE: 5/4/88
STREET: 400 Post Avenue	ATTENTION: Mr. Kenneth Skipka	
CITY, STATE & ZIP CODE: Westbury, New York 11590	JOB SITE: 11 Tungsten Site, Glen Cove, N.Y.	

SPECIFICATIONS:

WE HEREBY SUBMIT SPECIFICATIONS AND ESTIMATES FOR THE FOLLOWING:

The costs involved in supplying the manpower, equipment and materials necessary are as follows:

1. Tank will be entered, squeegee cleaned, and triple rinsed after pumping and removal of contents would be \$ 203,000.00.

NOTE: R.T.P. is responsible for the disposal of liquid or to designate an environmentally sound, on site tank for the transfer or liquid for later disposal by R.T.P.

NOTE: R.T.P. is responsible for providing roll-off containers for any solids removed for tank and for properly disposing of same.

NOTE: R.T.P. is responsible for supplying vac truck to assist in the tank cleaning.

NOTE: The above price is based on using heavy equipment that will be on site for the demolition and is covered in the demolition proposal.

THIS PROPOSAL IS MADE THIS 4th DAY OF May, 19 88

AUTHORIZED REPRESENTATIVE:

Tony Dalto
Tony Dalto

CONDITIONS: ALL MATERIAL AND WORKMANSHIP IS GUARANTEED TO MEET SPECIFICATIONS. ALL WORK TO BE COMPLETED IN A PROFESSIONAL WORKMANSHIP MANNER ACCORDING TO STANDARD PRACTICES. ALL WORK TO BE PERFORMED IN COMPLIANCE WITH OSHA REGULATIONS AND LOCAL, STATE AND FEDERAL RULES & REGULATIONS. ANY ALTERATIONS TO AND/OR DEVIATION FROM THE ABOVE OR ATTACHED SPECIFICATIONS, INVOLVING EXTRA COSTS, WILL BE EXECUTED ONLY UPON WRITTEN ORDERS AND WILL BE BILLED AS AN EXTRA CHARGE OVER AND ABOVE THIS ESTIMATE.

TERMS: 50% UPON SIGNING OF THIS CONTRACT
BALANCE-NET UPON COMPLETION OF WORK
INTEREST: 1 1/2% PER MONTH ON ANY UNPAID BALANCE.

After 30 days-1 1/2% interest.
After 60 days-all legal fees for collection
will be your responsibility.

ACCEPTANCE OF PROPOSAL: THE ABOVE PRICES, SPECIFICATIONS AND CONDITIONS ARE SATISFACTORY AND ARE HEREBY ACCEPTED. PAYMENT WILL BE MADE AS OUTLINED ABOVE. YOU ARE AUTHORIZED TO PROCEED WITH THE WORK AS SPECIFIED.

DATE _____ ORDER NO. _____ SIGNATURE _____

NOTE: THIS PROPOSAL MAY BE WITHDRAWN BY US IF NOT ACCEPTED WITHIN 30 DAYS

104261

AMERICAN ENVIRONMENT TECHNOLOGIES CORP.

38-40 OAK STREET
NORWOOD, NEW JERSEY 07648

NJ (201) 767-6757 USA 1-800-433-5937
FAX (201) 767-1889

April 7, 1988

RTP Environmental Associates Inc.
400 Post Avenue
Westbury, New York 11500

Attention: Mr. Ken Skipka

Reference: Li Tungsten Site
Glen Cove, New York

Dear Mr. Skipka:

Enclosed please find our inventory of known tanks at the Li Tungsten facility. All tanks with reasonable access were measured for quantity but there were some tanks that were sealed and our count is based on previous information provided by RTP.

Please note that before work commenced entire area, then specific tanks were tested for oxygen, toxicity and flammability with the Neotronics Exotox Portable Multi-Gas Monitor. Readings fell within safe guidelines except for obvious ammonia and acid tanks. As part of our normal operational procedures and especially because of large amount of asbestos, all our personnel wore full face respirator masks equipped with appropriate filter cartridges, full protective suits, boots, gloves and hard hats.

Due to the general run down condition of this abandoned facility, we recommend immediate measures be taken in order to protect against serious environmental problems:

1. Asbestos abatement should commence immediately. There are several areas of free falling asbestos.
2. Many of the storage tanks and associated piping are corroded, or linings collapsed and are not safe. All flowable liquids should be disposed of as soon as possible. If final disposal poses a logistics problem at this time, please consider the following. The most sound tank of each individual product may be used as a holding tank if a protective berm is constructed around perimeter of the tank. Then liquid from unsafe tank could be

104262

AMERICAN ENVIRONMENT TECHNOLOGIES CORP.


38-40 OAK STREET
NORWOOD, NEW JERSEY 07648

NJ (201) 767-6757 USA 1-800-433-5937
FAX (201) 767-1889

- pumped into holding tank, sludge and solids can be removed into approved containers, tank can then be cleaned and demolished.
3. The underground storage tanks should be cleaned, excavated and disposed of soon. Leaks are much more likely and environmental liability must be assessed.
 4. Structural damage due to neglect and corrosion throughout the buildings and especially ladders, catwalks etc. is extensive. If other work is going on at the site, probability of disturbance and damage to these structures could result. We recommend demolition work begin in conjunction with above mentioned phases in order that work can be completed in the safest, most expedient manner.

Thank you for using American Environment Technologies Corp.
If you have any questions or would like to schedule beginning of your project, please give me a call.

Sincerely,



Peter Melber

AMERICAN ENVIRONMENT TECHNOLOGIES CORP.

38-40 Oak Street
Norwood, New Jersey 07848
Telephone 201-787-8757 NJ
1-800-433-5837 USA

SUMMARY OF TANK INVENTORY

LOUNG BUILDING (OUTSIDE)

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
L-9E Steel Tank	5,800	1'	NH4WO4 solution
L-8A NH3 Scrubber Tank	12,000	Empty	
L-8 "	12,000	1'	
L-6 Steel Tank	12,000	1/2 full	APT Mother Liquor
L-5 "	12,000	3/4 full	"
L-9 "	"	Empty	"
L-10 "	"	Empty	"
L-13A "	12,000	1/2 full	ACR Leaching Sol.
L-13B "	"	1/2 full	"
L-550 "	2,000	full	water
L-550A "	"	3/4 full	
L-611 "	2,000	1000	solid
L-568 "	"	full	
*L-101 "	"		ammonia?
*L-102 "	"	empty	
*L-103 "	"	empty	
*L-104 "	"	empty	
*L-105 "	"	empty	
*L-106 "	"	empty	
*L-107 "	"	empty	
*old 9C "	"	empty	
*old 9D "	"	empty	
#85	unknown		
#86	unknown		

LOUNG BUILDING (INSIDE)

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
L-9A APT Crystallizer	2,400		
L-9B "	"		
L-9C "	"		
L9-D "	"	Empty	
L-9R-1 Steel Tank	1,000	Empty	
L-9R-2	5,000		
L-9F	2,800	Empty	
L-11	12,000		

* () designates unable to open

104264

EAST BUILDING (OUTSIDE)

Tank I.D. No.	Capacity	Current Condition	Description
233 Wooden Tank	20,000	18,000	Spent HCl Acid
231 "	20,000	15,000	"
232 "	"	15,000	"
235 Steel Tank	8,000	2,000	Aqua NH3
1213-1 Fiberglass Tank	17,000	(Empty) Gauge shows 1-1/2'	HCl Acid Stor. Tank
1213-2 "	"	"	"
1213-3 "	"	(Empty) Broken Gauge Indicates	"
1330 Lime Silo	64 ton	10% full	lime & water mixer
237 Steel Tank	8,500	empty	
1329 "	13,000	1/2 full dirt	solution & precipitate from neutraliz
1328 Thickener	19,000		
1332 Vertical Steel Tank	8,000	full	water
1333 "	7,000	(5,500)	water & scheelite
1334 "	3,500	(250)	spent HCl acid
1335 "	24,000	(Empty)	"
1345 "	12,000	(Empty)	"
E-3 Steel Tank		(Empty)	
245	16,000	12,000	FM residue
246 "	"	15,000	ACR Leaching sol.
1302 Aqua NH3	9,000	(1,700)	Aqua NH3
1303 Enrichment Tank		1'	
1306 Absorber Tank	1,000	3'	NH3 Solution
1307 "	"	3 1/2'	"
1308 "	"	4'	"
1336 Vertical tank	9,000	4,500	ACR Residue
244 Steel tank	16,000	8,000	water
248 "	5,500	2,500	P.D. Residue
249 "	23,000	full	P.D. Leaching sol.
242 Concial Tank	5,500	(100)	NaOH solution
*79 Fiberglass Tank		3'	
*80 "		6"	
#84 VAT		1'	
#9 Steel Tank		(Unknown)	

*() designates unable to open

104265

EAST BUILDING (INSIDE)

<u>Tank I.D. #</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
262 Steel Tank	17,000	70 g.	Stathetic Sheelite
263 "	"	"	"
264 "	"	"	"
265 "	"	"	"
266 "	"	36"	"
268 Haveg Tank	"	7"	
269 "	"	39"	
270 "	"	40"	
271 "	"	Empty	
274 "	"	28"	
275 "	"	Empty	
276 "	"	"	
277 "	"	"	
278 "	"	"	
279 "	"	"	
280 "	"	"	
281 "	"	"	
282 "	"	"	
1341 "		"	
1342 "		"	
1343 "		47"	
1344 "		51"	
285 R & B Lined Tank	6,000	Empty	
286 Steel Tank	16,000	3"	Tungsten Acid
287 "	16,000	2"	
616 Glass lined tank	4,000	10,000	P.D. Sol. & Residue
617 Rubber lined tank	6,000	2'	
618 Surge tank	1,100	Empty	
619 Rubber lined tank	5,000	(Empty)	
620 Residue Digester	4,000	(Empty)	
1337 Vertical Steel Tnk	1,700	2"	
1338 Rubber lined	3,000	40"	
1339 "	"	8"	
1340 "	"	8" solid	
255 Steel Tank 6'x3'		2,200	
*1 Underground 5' x 8'		(unknown)	
*2 By tank 555		full	
*3 9 x 5		(unknown)	
*4 underground pit 5' deep		(unknown)	
*5 sealed		full	
*6		(unknown)	
*78 sealed		empty	
		(unknown)	

* () designates unable to open

PRESSURE DIGESTER SYSTEM

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
#60 Jacketed Digester		Empty	
#64 "		Empty	
56 Dilution tank	4,000	2,000	P.D. Sol & Residue
58 "	4,000	1,000	"
P-1 Mixer		1/2 full	
83		full	
82		empty	
89		empty	
88		empty	
41 underground gasoline tank		contents unknown	
89A unknown.			

DICE BUILDING (OUTSIDE)

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
22			
23		empty	
24 550g. oil tank	6"	empty	
25 10,000g. oil tank	7"		
26 10,000g. oil tank	7"		
27			
31		empty	
19		empty	
20 outside boiler room	3"	empty	
21 "			
A underground storage tank		unknown	
B "	10,000 g.	4"	
30	1,000 g.	unknown	
32		empty	
33		full	
34		1/2 full	
35 NaOH Storage Tank	95,000	empty	
36 CaCl2 Storage Tank	95,000	3,000	50% NaOH
37		2,000	30% CaCl2
38		empty	
39		empty	
40		empty	
Ball Tank	13,000	empty	
Propane Tank	8,000	(Empty)	
Fuel Oil Tank	500,000	(Empty)	
Water Reservoir	150,000	(Empty)	
		1/4 full	

* () designates unable to open

DICE BUILDING (OUTSIDE) Con't

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
Oil Change Pit		Full of Liquid	
45-55 Warehouse Area		empty	
C 10,000 g. underground storage tank			
D 550 storage tank 1-1/2'			
41-44		empty	
2 acid trucks			
56-59			
59A			
underground gasoline tank - contents unknown			

DICE BUILDING INSIDE
A - Mixer Room Section

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
M-1-A Steel Tank	200	Empty	
M-1 Steel Tank	2,000	500	Residue & Leach.
Sol			
M-2 "	2,900	1,100	
M-3 "	1,500	Empty	
M-4 "	3,000	1,800	Cobalt Chloride Sol
M-5 "	3,000	1,800	
M-6 "	1,700	Empty	
M-7 "	"	Empty	
M-8 "	"	(Empty)	
M-9 "	"	Empty	
M-10 "	1,400	"	
M-11 "	"	700	Sodium Tungstate Solution & Residue

(B) K-Tanks Section

K-1 Steel Tank	12,000	7,000	Sodium Tungstate So
K-2 "	"	11,000	"
K-3 "	"	11,000	"
K-4 "	"	7,000	"
K-5 "	"	500 sludge	NF Residue
K-6 "	"	2,000	Sodium Tungstage So
K-7 "	"	6,000 solid	NF Residue
K-8 "	"	2'	
K-9 "	"	7,000 g.	
W-1 Underground Tank	"	full - sludge	
W-2 Steel Tank	"	600 g.	
W-3 "	"	full	

* () designates unable to open

DICE BUILDING INSIDE
(B) K-Tanks Section

<u>Tank I.D. No.</u>	<u>Capacity</u>	<u>Current Condition</u>	<u>Description</u>
W-4 Steel Tank		full	

(C) Cobalt Process Section

833 Brick lined	4,500	Empty	
832 Thickener	20,000	2,000	
840 Acid Tank	11,000	(Empty)	
C-1	3,000	Empty	
C-2	"	"	
C-3	1,200	full	Cobalt Sulfate
C-4			Sol. & FM Residue
C-5	5,500	full	Cobalt Sulfate Sol
C-6	"	full	"
C-7	3,000	700	"
C-8	"	2,500	"
C-9	6,000	Empty	"
C-10	"	Empty	"
C-11	3,000	full	"
C-12	"	full	"
C-13	"	full	"
C-14	"	1,500	"
C-15	"	full	
*16	"	Empty	
*17	Blg.	50% full	
*18	sealed	(unknown)	
*19		full	
*667	sealed	(unknown)	
	"	"	

Boiler Room

#120 oil tank -small
#121 oil tank - small
Far west end of Dice Bldg.
#28 Ball tank - empty
#29 " empty

* () designates unable to open

significant amount of chemical analysis took place in support of the facility's operations. Finally, scattered both throughout this parcel and in the Warehouse area are numerous stacked drums and crates of processed ores which were set aside in similar lots in the event that reprocessing would prove to be economically feasible.

The parcel north of Herb Hill Road and east of Dickson Lane was not used for processing activities. The southern portion of the parcel (south of the small natural pond) was used for parking by the site employees. A small portion of the area north of the pond was apparently used as a landfill and waste pile storage area for wastes generated from the main processing operations.

The parcel west of Dickson Lane has several distinctive features. The Reduction Building was utilized for high temperature processing of tungsten into tungsten carbide powder. Its furnaces were fed hydrogen enriched air, with hydrogen supplied by a bank of batteries in the eastern portion of the building. The large ball tank on the western side of the building was constructed to store hydrogen for the tungsten carbide production process, but was never utilized. Permits for its operation were never approved. The New Warehouse is the largest structure on this northwest parcel and was used for materials storage. Unlike the warehouse on the southeast parcel, there is very little storage of processed ores in this building. The 500,000 gallon fuel tank south of the New Warehouse was not used by the Li Tungsten facility. A nearby fuel oil facility utilized the tank for storage purposes. Finally, the Mud Pond on the southern portion of this parcel is a lined surface impoundment and settling basin. Processed wastewater from operations on the nearby southeast parcel were pumped into the Pond where natural settling of suspended solids and evaporation of water would be the end result.

Finally, a parcel that is included in the overall investigation was never owned by Li Tungsten. It is located to the north and west of the Reduction Building and this site was also audited for environmental concerns during the study.

2.2 Nearby Land Uses.

During the course of investigations at the Li Tungsten site, RTP conducted a brief survey of surrounding properties so that all possible pathways for contamination might be found. Land use in the area includes residential, commercial, and industrial (both light and heavy). The specific properties to be described either directly or indirectly border the subject property and do have the potential to impact the site.

Windsor Fuels.

Windsor Fuels is a small fuel oil (#2 distillate) distribution company. The company is located on the corner of Herb Hill Road and Charles Street and is bordered by Glen Cove Creek to the south and Bona-Fide Ready-Mix Corp. to the west. The company has been established for many years and has three large above ground storage tanks that are filled by barge and two smaller tanks. All tanks and piping are above ground and no other chemicals or solvents are kept on the property except the small quantities that are used for basic truck maintenance.

Bona-Fide Ready Mix Corporation.

The Bona-Fide Ready Mix Corporation is a small construction materials producer that deals strictly with concrete and associated materials such as bluestone, sand, gravel, screenings and blends. The company has been in

existence at the site for approximately 30 years. It is located on the south side of Herb Hill Road and is bordered by Windsor Fuels to the east, Glen Cove Creek to the south and Li Tungsten to the west. The owner is presently building office space for rent near the entrance to the plant area. One underground storage tank exists on site and contains diesel fuel for the cement mixer trucks. Truck maintenance is conducted on site, therefore, normal maintenance oils and solvents are kept on hand in small quantities.

Chemco Technologies.

Chemco Technologies is located on the north side of Herb Hill Road and is bordered by Flipse Autobody and Li Tungsten to the west, New Street and Charles Street to the east and The Place Street to the north. Generally, Chemco is a manufacturing company that produces photographic film and photographic chemicals. The company has been established for many years. The main office building was once occupied by Columbia Carbon and Ribbon Co. It was bought in 1978-1979 by Chemco. The Columbia site is known to have been partially remediated for hazardous waste and a full Remedial Investigation/ Feasibility Study is currently underway according to Region II DEC. Limited information was available other than that underground and above-ground tanks exist and are registered. Solvents and chemicals are onsite for product manufacturing and equipment maintenance. Information pertaining to accidental spills onsite was not made available.

Flipse Autobody.

Flipse Autobody is a small autobody repair shop located on the north side of Herb Hill Road and is bordered by Li Tungsten to the west and Chemco Technologies to the north and east. The repair shop has been in existence

for over three years and the property surrounding the Flipse building is occupied by a number of used automobiles of varying age, size, and condition. Flipse had been storing some of its vehicles on the Li Tungsten property until they were asked to remove them during the course of RTP's investigation.

Flipse autobody is classified as a small generator of hazardous wastes because of materials in use such as lacquers, paints and thinners. These materials and waste solvents are manifested according to applicable regulations prior to their removal from the site. The building housing the repair shop was once a commercial laundry. As a result, a number of underground tanks exist on the property for fuel storage (fuel oil or gasoline). Flipse autobody utilizes an underground tank and above-ground tank, both containing fuel oil, for heating purposes. Remediation of various spills at the autobody facility as well as the laundry have been performed according to Nassau County Department of Health (NCDOH) records.

S and W Laundry.

The S and W Laundry Company is a small commercial laundry occupying the rear section of the structure housing Flipse Autobody. Limited information was available from the company which claims to have been operating for approximately nine years. Dry-cleaning chemicals did not appear to be currently utilized at the facility. Normal operations consist of industrial washing, drying and pressing. NCDOH has reported some accidental spills of hazardous materials at this site and these were apparently remediated.

Northshore Sportswear.

The Northshore Sportswear company is a small sportswear storage and distribution facility located on the west side of Dickson Lane and it is bordered by Li Tungsten to the south and west and residential housing to the north along Janet Lane. Clothing production does not occur here and the facility is generally used for warehousing. The facility has been in existence since 1965 and deals strictly in sportswear products. No fuel tanks exist on site and no equipment related oils and solvents are stored on site.

Hawkins Fuel Oil.

The Hawkins Fuel Oil Company is a small petroleum distribution company located on the south side of Garvies Point Road and bordered on the east and north by Li Tungsten, and on the south by Glen Cove Creek. The company was established over 50 years ago and at one time utilized the 500,000 gallon fuel storage tank on the Li Tungsten property.

The company currently maintains three above-ground storage tanks for #2 distillate fuel oil, one underground storage tank for diesel fuel and one underground storage tank for gasoline. Only as-necessary truck maintenance occurs at this location because the company has another location that has a maintenance shop. Other chemicals or solvents are not utilized in substantial quantities at this facility.

A small oil spill occurred in January, 1988 at the Hawkins site when a valve seat froze, allowing approximately 100 gallons of fuel to leak. The spill was cleaned up under the supervision of state and county officials.

Town of Glen Cove Sewage Pumping Station.

A small parcel of land located to the west of Hawkins Fuel Oil and bordered by Garvies Point Road to the north, and Glen Cove Creek to the south houses a sewage pumping station for the City of Glen Cove. A locked fence surrounds the station and apparently the pumping station transfers sewage via a pipe under Glen Cove Creek to the Glen Cove Sewage Treatment plant directly across the creek.

LIMCO Manufacturing Corporation.

The LIMCO manufacturing corporation primarily engineers and manufactures sheet metal products for aerospace and industrial purposes. The U. S. military is a large buyer of LIMCO's products. The LIMCO plant occupies a large area located on the north side of Garvies Point Road and is bordered to the east and north by the Li Tungsten facility. LIMCO has occupied this location for over 40 years. One underground storage tank contains fuel oil for heating. Above-ground tanks contain mostly gases for welding and metal work. Solvents and related chemicals are used onsite for metal processing.

Mattiace Petrochemical Co.

Mattiace Petrochemical Co. is a now defunct chemical recycling and neutralization company that borders the western section of the Li Tungsten property (the parcel that is north of Garvies Point Road and west of Dickson Lane). This site is presently a Superfund cleanup site due to alleged chemical dumping and chemical storage in leaking tanks.

Residential

For the most part, the Li Tungsten property is bordered to the north and west by residential housing in areas other than those previously mentioned. Also, Glen Cove Creek borders the site to the south and is bordered on the extreme western portion by the Garvies Point Preserve.

2.3 Scope of Project.

Given the type of operations that were ongoing at the Li Tungsten facility, it is clear that several cleanup activities need to be performed prior to the development of the site for residential purposes. These are summarized as follows:

1. Testing, neutralization, removal and disposal of tankage and associated liquids.
2. Removal and disposal of analytical laboratory chemicals and related gas cylinders.
3. Identification, removal and disposal of asbestos containing materials.
4. Removal and disposal of stockpiled process residues, as necessary.
5. Demolition and cleanup of on-site structures.
6. Removal, cleanup or treatment of sources of any soil, groundwater or air contamination.
7. Removal and disposal of PCB containing transformers and articles.

The assessments undertaken by RTP were aimed at establishing the magnitude of these cleanup activities and their approximate costs. To accomplish

this, RTP utilized the services of several subcontractors performing the tasks indicated below:

- o Geraghty & Miller, Inc.
 - establishment of groundwater monitoring wells
 - soil gas survey
 - water quality sampling and analysis
 - estimation of groundwater cleanup methodologies and costs
- o Enviropact Northeast, Inc.
 - inventory and sampling of stored waste materials
 - soils sampling
 - estimation of onsite laboratory cleanup and disposal costs
 - hazardous materials determinations
 - estimation of liquid waste removal and disposal costs
 - estimation of solid waste removal and disposal costs
 - outfall sampling
 - estimation of cleanup and disposal costs for transformers
- o American Environment Technologies Corp.
 - inventory of tankage
 - estimation of tankage cleanup and removal costs
 - inventory of asbestos
 - estimation of asbestos cleanup and disposal costs
 - estimation of structural demolition and disposal costs
- o Levine & Robinson, P.C.
 - review of requirements for closure/remediation
 - review of potentially applicable environmental statutes
 - review of liability issues

In some cases, subcontractors retained their own subcontractors to address specific problems within their areas of responsibility. RTP's principal responsibilities included overall project management, supervision of site activities, liaison with Campon Realty Corp., integration and assimilation of subcontractor reports, and cost and remediation summaries.

During the course of RTP's investigations at the site, a number of hazards or potential hazards were identified that were thought to be in need of immediate remediation. These are conditions that, due to their severity, will be corrected to stabilize the site prior to the overall site cleanup activities associated with preparation of the site for development. Glen Cove Development Company has taken the initiative to investigate these conditions and arrange for any necessary remediation. The conditions being investigated are as follows:

- o Approximately 20 tanks are in poor condition and need to be drained and cleaned to eliminate the potential of rupture and spillage of their contents.
- o Approximately 23 gas cylinders have been found and need to be removed from the site to eliminate potential hazards from the release of pressurized and, in some cases, hazardous chemicals.
- o An estimated 131 drums of liquids have been found scattered throughout the site and need to be overpacked in secure containers to eliminate the potential for spillage.
- o The three analytical laboratories and related storage facilities need to be lab packed, secured and stored.

- o The liner under the site mud pond is broken and leaking. This has caused adverse effects on nearby soils and vegetation. This condition needs to be corrected so that further leakage is prevented.
- o Wastes from ore processing, stored in open piles contain high concentrations of heavy metals and, in some cases, may be classified as hazardous. These need to be properly contained.
- o Wastes stored within buildings are potentially hazardous and were put indoors to prevent exposure to the elements. Some areas of these buildings have flooded due to roof leakage and the wastes have come into contact with water creating a potential health hazard. The water on the floors needs to be removed and materials should be stored in areas that will remain dry.
- o Asbestos hazards exist in and near several buildings due to the deteriorating nature of structures and associated tanks and piping. These conditions are a small part of the total asbestos remediation needed for site cleanup/closure, but they should be immediately remediated for overall safety at the site.

Due to the conditions noted above, RTP and its subcontractors have prepared health and safety plans for conducting activities at the site. The RTP plan is provided in the Appendix to this report, while those of our subcontractors may be found integrated with the rest of their reports on

cleanup of the site. It should be stressed that the site is currently in an unstable condition and people performing work at the site must exercise appropriate caution.

The main purpose of this final report is to provide sufficient guidance on costs and schedules for each identified cleanup/remediation activity associated with getting a clean bill of health for the site. The seven activities summarized earlier in this section are separate from the immediate remediation activities described above. Information on the overall site cleanup is provided in the following sections, but it must also be recognized that two important constraints were in effect during the course of these investigations.

First, the sixty day schedule for the project meant that assessments were exploratory in nature and designed to provide an overview of contamination at the site and not a complete characterization for purposes of conducting the remediation. Second, RTP and its subcontractors conducted this study under a strict confidentiality agreement which restricted coordination with regulatory agencies unless reportable information was uncovered. Obviously, coordination with regulatory agencies will be necessary before the true extent and costs of remediation can be determined.

The following sections of this report contain the key findings of our subcontractors. Section 3 includes a review of regulatory issues related to cleanup as prepared by Levine & Robinson, P.C. Section 4 contains the report of Geraghty & Miller, Inc. on the groundwater, and soil gas investigation. Section 5 contains a report on site residues and special testing (soils, outfalls, PCBs, etc.) performed by Enviropact Northeast, Inc. Section 6 contains American Environment Technologies Corporation (AETC)

estimates of asbestos and tank removal costs as well as demolition costs. Finally, the Appendix contains the RTP health and safety plan as well as a detailed discussion of tungsten processing/refining.

SECTION 4.0

HYDROGEOLOGIC INVESTIGATION AND SOIL GAS SURVEY

SUMMARY OF METALS CONCENTRATION

	Concentrations in ug/m ³						ACGIH TLV
	ICP-1 Outdoors	ICP-2 Dice Bldg. Near Drums	ICP-3 Dice Bldg. Slag Pile	ICP-4 Warehouse	ICP-5 Benbow Bldg.	ICP-8 Blank*	
Cadmium	<0.01	<0.01	<0.01	<0.01	0.06	<0.01	50
Copper	0.05	0.09	0.12	0.06	0.07	0.02	1,000
Chromium	<0.01	<0.01	<0.01	<0.01	<0.01	0.03	500
Iron	0.18	22.17**	0.45	1.56	4.06	0.36	—
Nickel	<0.01	0.06	0.05	<0.01	0.11	<0.01	1,000
Zinc	0.15	0.14	<0.01	0.12	0.35	0.10	—
Lead	<0.15	<0.15	<0.15	<0.15	<0.15	<0.005	150
Silver	<0.01	0.76	<0.01	<0.01	<0.01	<0.01	100
Sodium	<0.01	1.97	<0.01	<0.01	<0.01	1.26	—
Aluminum	0.50	0.15	0.28	0.64	1.79	0.25	10,000
Manganese	<0.01	<0.01	<0.01	<0.01	2.83	0.09	5,000
Arsenic	<0.01	<0.01	<0.01	<0.01	<0.01	<0.50	200
Beryllium	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	2.0
Molybdenum	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	5,000
Phosphorus	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	100
Platinum	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	1,000
Selenium	0.13	<0.01	<0.01	0.12	<0.01	<0.50	200
Tellurium	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	100
Thallium	0.56	0.02	<0.01	<0.01	<0.01	0.03	100
Tin	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	2,000
Titanium	0.22	<0.01	<0.01	<0.01	<0.01	<0.01	10,000
Vanadium	<0.01	0.04	0.01	0.07	0.19	0.18	50
Yttrium	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	1,000
Zirconium	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	5,000

* units are ug/g.

** this elevated value is believed to have been caused by a particle of rust scale from the drums that had fallen on the filter during sampling.


Volumetric Techniques, LTD.

17 Bernice Drive • Bayport, New York 11705 • (516) 472-4848

To: Laboratory Testing Services
75 Urban Avenue
Westbury NY 11590
516-7004

Date: _____
Collected: _____
Received: 07/05/89
Completed: 08/10/89

Sample Taken By _____
Client _____

Reported By: 
Additional Lab No.: _____

Sample: F.C. Hart Associates
7300 Series (1 C F-1)
NY
334-7004

Sample Number 88898907

Parameters	Results ng/L	Parameters	Results ng/L
Cadmium	<0.01		
Copper	0.05		
Chromium, Total	<0.01		
Iron	0.10		
Nickel	<0.01		
Zinc	0.15		
Lead	<0.01		
Silver	<0.01		
Sodium	<0.01		
Aluminum	0.50		
Manganese	<0.01		
Arsenic	<0.01		
Beryllium	<0.01		
Molybdenum	<0.01		
Phosphorus	<0.01		
Platinum	<0.01		
Selenium	0.13		
Tellurium	<0.01		
Thallium	0.56		
Tin	<0.01		
Titanium	0.22		
Vanadium	<0.01		
Yttrium	<0.01		
Zirconium	<0.01		

Run Time : 24 Hours
Pump Rate : 1.26 L/M

Comments

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
• Sander R. Sternig • Director of Laboratories •

104284

Volumetric Techniques, LTD.

7 Bernice Drive • Bayport, New York 11705 • (516) 472-4848

To: Laboratory Testing Services
75 Urban Avenue
Westbury NY 11590
334-7004

Date:

Collected:

Received: 07/05/89

Completed: 08/10/89

Reported By:

Sample Taken By
Client

Additional Lab No.:

Sample: F.C. Hart Associates
7500 Series (1 C P-2)
NY
334-7004

Sample Number 88918907

Parameters	Results ng/L	Parameters	Results ng/L
Cadmium	<0.01		
Copper	0.09		
Chromium, Total	<0.01		
Iron	22.17		
Nickel	0.06		
Lead	0.14		
Mercury	<0.01		
Silver	0.76		
Sodium	1.97		
Aluminum	0.15		
Manganese	<0.01		
Arsenic	<0.01		
Beryllium	<0.01		
Molybdenum	<0.01		
Phosphorus	<0.01		
Platinum	<0.01		
Selenium	<0.01		
Tellurium	<0.01		
Thallium	0.02		
Vanadium	<0.01		
Titanium	<0.01		
Yttrium	0.04		
Zirconium	<0.01		

Run Time : 24.05 Hrs

Pump Rate : 1.183 L/M

Comments

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
• Sander R. Sternig • Director of Laboratories •

104285

Volumetric Techniques, LTD.

317 Bernice Drive • Bayport, New York 11705 • (516) 472-4848

Laboratory Testing Services
75 Urban Avenue
Westbury NY 11590
334-7004

Date:

Collected:

Received :07/05/89

Completed:08/10/89

Reported By:

Additional Lab No.:

Sample Taken By
Client

Sample:F.C. Hart Associates
7300 Series (1 C P-3)
NY
334 7004

Sample Number 88938907

Parameters	Results ng/L	Parameters	Results ng/L
Cadmium	<0.01		
Copper	0.12		
Chromium, Total	<0.01		
Iron	0.45		
Nickel	0.05		
Zinc	<0.01		
Lead	<0.15		
Silver	<0.01		
Sodium	<0.01		
Aluminum	0.28		
Manganese	<0.01		
Arsenic	<0.01		
Beryllium	<0.01		
Molybdenum	<0.01		
Phosphorus	<0.01		
Platinum	<0.01		
Selenium	<0.01		
Tellurium	<0.01		
Thallium	<0.01		
tin	<0.01		
titanium	<0.01		
Vanadium	0.01		
Yttrium	<0.01		
Zirconium	<0.01		

Run Time : 24 Hours
Pump Rate : 1.1764 L/M

Comments

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
•Sander R. Sternig•Director of Laboratories•

104286

Volumetric Techniques, LTD.

7 Bernice Drive • Bayport, New York 11705 • (516) 472-4848

To: Laboratory Testing Services

75 Urban Avenue

Westbury NY 11590

334-7004

Date:

Collected:

Received: 07/05/89

Completed: 08/10/89

Reported By:

Additional Lab No.:

Sample Taken By

Client

Sample: F.C. Hart Associates

7000 Series (1 C P-4)

NY

334-7004

Sample Number 88948907

Parameters	Results ng/L	Parameters	Results ng/L
Cadmium	<0.01		
Copper	0.06		
Chromium, Total	<0.01		
Iron	1.56		
Nickel	<0.01		
Zinc	0.12		
Lead	<0.15		
Silver	<0.01		
Sodium	<0.01		
Aluminum	0.64		
Manganese	<0.01		
Arsenic	<0.01		
Beryllium	<0.01		
Molybdenum	<0.01		
Phosphorus	<0.01		
Platinum	<0.01		
Selenium	0.12		
Tellurium	<0.01		
Thallium	<0.01		
Tin	<0.01		
Titanium	<0.01		
Vanadium	0.07		
Yttrium	<0.01		
Zirconium	<0.01		

Run Time : 23:35 Hrs

Pump Rate : 0.700 L/M

Comments

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
• Sander R. Sternig • Director of Laboratories •

104287

Volumetric Techniques, LTD.

317 Bernice Drive • Bayport, New York 11705 • (516) 472-4848


To: Laboratory Testing Services
75 Urban Avenue
Westbury NY 11590
334-7770

Date:

Collected:

Received : 07/05/89

Completed: 08/10/89

Reported By: 

Additional Lab No.:

Sample Taken By
Client

Sample: F.C. Hart Associates
7300 Series (I C P S)
Paul Calzolari 334-7770

Sample Number 88758907

Parameters	Results ng/L	Parameters	Results ng/L
Cadmium	0.06		
Copper	0.07		
Chromium, Total	<0.01		
Iron	4.06		
Nickel	0.11		
Zinc	0.35		
Lead	<0.15		
Silver	<0.01		
Sodium	<0.01		
Aluminum	1.79		
Manganese	2.83		
Arsenic	<0.01		
Beryllium	<0.01		
Molybdenum	<0.01		
Phosphorus	<0.01		
Platinum	<0.01		
Selenium	<0.01		
Tellurium	<0.01		
Thallium	<0.01		
tin	<0.01		
Titanium	<0.01		
Vanadium	0.19		
Yttrium	<0.01		
Zirconium	<0.01		

Run Time : 24 Hours
Pump Rate : 0.8530 L/M

Comments

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
• Sander R. Sternig • Director of Laboratories •

104288

Volumetric Techniques, LTD.

317 Bernice Drive • Bayport, New York 11705 • (516) 472-4848

To: Laboratory Testing Services
75 Urban Avenue
Westbury NY 11590
516-70004

Date:

Collected:

Received: 07/05/89

Completed: 08/10/89

Reported By:

Additional Lab No.:

Sample Number 88968907

Sample Taken By
Client

Sample: F.C. Hart Associates
7300 Series (1 C.F-Blank)
NY
516-70004

Parameters	Results ppm	Parameters	Results ppm
Cadmium	0.01		
Copper	0.02		
Chromium, Total	0.03		
Iron	0.36		
Nickel	0.01		
Zinc	0.10		
Lead	0.005		
Silver	0.01		
Sodium	1.26		
Aluminum	0.25		
Manganese	0.09		
Arsenic	0.50		
Beryllium	0.01		
Molybdenum	0.01		
Phosphorus	0.01		
Platinum	0.01		
Selenium	0.50		
Tellurium	0.01		
Thallium	0.03		
Tin	0.01		
Titanium	0.01		
Vanadium	0.18		
Yttrium	0.01		
Zirconium	0.01		

Comments

* Record For Blank: Not Mailed

• CONSULTING CHEMISTS • COMPLETE LABORATORY TESTING •
• Sander R. Sternig • Director of Laboratories •

104289

REFERENCE NO. 27

104290

CONTROL NO: 02-8907-28	DATE: 10/3/89	TIME: 9:15
DISTRIBUTION: TO FILE; LI TUNGSTON		
BETWEEN: CHARLIE FITZSIMMONS	OF: EPA, EDISON N.J.	PHONE: (201) 321-6608
AND: STEVEN OKULEWICZ, EDISON		
DISCUSSION: I ASKED MR. FITZSIMMONS ABOUT THE RECENT AIR TESTING FOR ASBESTOS, METALS, AND VOLATILE ORGANICS PERFORMED ON THE LI TUNGSTON SITE. HE SAID THAT THE RESULTS SHOWED LITTLE OR NO METALS AND VOLATILE ORGANICS. HE WAS UNSURE ABOUT THE TESTING PROCEDURES USED TO COLLECT THE ASBESTOS SAMPLES IN AIR, AS FAR AS THE NUMBER OF SAMPLES THAT SHOULD HAVE BEEN TAKEN AND OVER WHAT PERIOD OF TIME THE SAMPLES WERE TAKEN. HE SAID HE WOULD CHECK INTO THIS AND GET BACK TO ME ON THE RESULTS. ALSO, HE SAID THAT THE NUMBER OF ELECTRIC TRANSFORMERS ON SITE HAS NOW REACHED 27, BUT TO USE 23 AS THE REPORTED AMOUNT. LASTLY, HE SUGGESTED I CALL THE NASSAU COUNTY DEPARTMENT OF HEALTH AND CONTACT ROBERT THESSIFER ABOUT BACKGROUND RADIATION LEVELS ON THE LI TUNGSTON SITE. HE CAN BE REACHED AT 516-5353313		
ACTION ITEMS: COUNTY DEPARTMENT OF HEALTH AND CONTACT ROBERT THESSIFER ABOUT BACKGROUND RADIATION LEVELS ON THE LI TUNGSTON SITE. HE CAN BE REACHED AT 516-5353313		

REFERENCE NO. 28

104292



TOTAL ANALYTICAL SERVICES FOR A SAFE ENVIRONMENT

nytest environmental inc.

SEP 25 1989

September 21, 1989

Fred C. Hart Assoc.
530 5th Avenue
New York, N.Y. 10036

Attention: Karl Boldt

Nytest is pleased to submit our Project No. 89-15969
Log in No. 2224 on your sample (s) received: 8-17-89.

Test sample (s) associated with this project will be retained for a period of thirty (30) days, unless otherwise instructed.

My staff is available to answer any questions concerning our report and we look forward to serving your future analytical needs.

Very truly yours,

Nytest Environmental Inc.

Remo Gigante
Exec. VP

RG:gd
Enc.

104293



TOTAL ANALYTIC SERVICES FOR A SAFE ENVIRONMENT

nytest environmental inc.

Project No.: 89-15969

Log In No.: 1874

P.O. No.: 00265-02-00003-01

Date: July 21, 1989

ANALYTICAL DATA REPORT PACKAGE
FOR

Fred C. Hart Assoc.

530 5th Avenue

New York, N.Y. 10036

Attn: Karl Boldt

Ref: L1 Tungsten

SAMPLE
IDENTIFICATION

LABORATORY
NUMBER

TYPE OF
SAMPLE

DATE AND TIME OF
SAMPLE COLLECTION

SEE FOLLOWING PAGES FOR RESULTS

REPORT PREPARED BY:
PARAG K. SHAM, Ph. D.
ORGANIC LAB. MANAGER

DOUGLAS SHEELEY
LABORATORY DIRECTOR

bf

WE CERTIFY THAT THIS REPORT IS A
TRUE REPORT OF RESULTS OBTAINED
FROM OUR TESTS OF THIS MATERIAL.

RESPECTFULLY SUBMITTED,
NYTEST ENVIRONMENTAL INC.

REMO GIGANTE
EXECUTIVE V.P.

Report on sample(s) furnished by client applies to sample(s). Report on sample(s) obtained by us applies only to lot sampled. Information contained herein is not to be used for reproduction except by special permission. Sample(s) will be retained for thirty days maximum after date of report unless specifically requested otherwise by client. In the event that there are portions or parts of sample(s) remaining after Nytest has completed the required tests, Nytest shall have the option of returning such sample(s) to the client at the client's expense.

104294

box 1518 □ 60 seaview Blvd., port washington, ny 11050 □ (516) 625-5500

Page 1 of 1

REPORT TO: Client Name NYTEST
Address _____
Phone _____
Attn. _____

Special Instructions/Comments _____

Client Retains Yellow Copy Only



Name: KARL BOLDT
 Affiliation: FRED C. HART ASSOCIATES, INC.
 Phone: (212) 840-3990
 Address: 570 FIFTH AVE. NEW YORK, NY 10036
 Client/Job No: 00265-02-00003-01
 Job Name: LI TUNGSTEN Location: GLEN COVE, NY

CHAIN OF CUSTODY RECORD

Sample No.	Lab I.D. No.	Date	Time	Matrix	No. of Containers	Analysis Requested/Remarks
IOA 11		8/17/89	5:00PM	SORBENT TUBE	1	INORGANIC ACIDS NIOSH METHOD
IOA 12						
IOA 13						
IOA 14						

Comments: _____

Relinquished by: Karl Boldt Date: 8/17/89 Shipment Method: Hand
 Time: 6:15 PM Airbill No.: _____

Received by: Fred C. Hart Date: 8/17/89 Relinquished by: _____ Date: _____
 Time: 6:15 PM Time: _____

Received by: _____ Date: _____ Relinquished by: _____ Date: _____
 Time: _____ Time: _____

Final Disposition of Samples: _____

Received by: _____ Date: _____ Time: _____

Re: Inorganic Acids Air Monitoring Results
Li Tungsten

Jim,

Sample IOA-14 was the blank. Only fluoride (presumably HF) showed up higher than the blank. ACGIH TLV is 2.5 mg/m^3 ($2,500 \text{ ug/m}^3$). Concentrations measured were as follows.

<u>Sample No.</u>	<u>Location</u>	<u>(ug F)*</u>	<u>(ug/m³ F)</u>
IOA-11	Lab S	1.91	16.5
IOA-12	Lab NW	1.41	12.0
IOA-13	Lab E	0.12	1.07
IOA-14	Blank	1.37	--

* Blank value subtracted from total analytical result.

TABLE OF CONTENTS

1.0 Introduction	1
2.0 Purpose	3
3.0 Interim Actions	4
3.1 Site Security	4
3.1.1 Proposed Action	4
3.2 Radioactive Materials	5
3.2.1 Proposed Action	5
3.3 Laboratory Chemicals	6
3.3.1 Proposed Action	6
3.4 Drum Inventory and Removal	7
3.4.1 Proposed Action	7
3.5 Tank Characterization	7
3.5.1 Proposed Action	7
3.6 Asbestos	8
3.6.1 Proposed Action	8
3.7 Creek Sampling	9
3.7.1 Proposed Action	9
3.8 Transformer Oil Characterization	10
3.8.1 Proposed Action	10
3.9 Mercury Clean-up	10
3.9.1 Proposed Action	10

List of Figures

Figure 1 Site Map	2
-----------------------------	---

1.0 INTRODUCTION

The Li Tungsten facility (herein after referred to as the "Site") is located at 63 Herb Hill Road, Glen Cove, New York. The Site is 26 acres and consists of three separate parcels. The main operations at the Site were conducted on the parcel bordered by Glen Cove Creek to the south and Herb Hill Road to the north and a second parcel to the west of Dickson Lane. The parcel bordered by Herb Hill Road on the south and Dickson Lane on the west contains no facility structures. A map of the Site is provided in Figure 1.

Based on documents in the possession of the Glen Cove Development Company (GCDC) and obtained from records maintained at the Site the following background information was developed. The Site was operated from the 1940's to approximately 1985 by the Wah Chang Trading Company and its wholly owned subsidiary the Li Tungsten Corporation. The operation involved the processing of ore and scrap tungsten concentrates to ammonium paratungstate (APT) and subsequently formulating APT to metal tungsten powder and tungsten carbide powder. Other specialty products such as tungsten carbide powder plus cobalt and other material for plasma spraying; tungsten titanium carbide powder; tantalum carbide powder; tungsten spray powder; crystalline tungsten powder; and, molybdenum spray powder were also produced.

The property was acquired by GCDC in 1984 and leased to The Li Tungsten Corporation. The market for tungsten was apparently depressed by the 1980's and operations at the Li Tungsten facility had slowed by this time. The Li Tungsten operation declared bankruptcy in 1985.

GCDC is a New York State general partnership jointly owned by Old Court Joint Ventures, Inc. and Old Court Holdings Corporation, Inc., both of which in turn are wholly-owned subsidiaries of Old Court Savings and Loan, Inc. (in Receivership) located in Maryland.




Figure 1

Li Tungsten Facility

Fred C. Hart Associates, Inc. (HART) was retained by GCDC to coordinate implementation of interim actions to address certain environmental conditions at the Site. This scope of work (SOW) sets forth those proposed interim actions which were identified by the United States Environmental Protection Agency (USEPA) Region II pursuant to its authority under The Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) 42 U.S.C. Section 9601 et. seq. This scope of work is prepared as an attachment to the USEPA Administrative Order on Consent, Index No. II CERCLA-90215. The work proposed in this document will be consistent with practices described in:

"Characterization of Hazardous Waste Sites". NTIS PB87-120291, August 1985.

"Guidance Document for Clean-up of Surface Tank and Drum Sites". NTIS PB87-110672, May 1985.

"Drum Handling Practice at Hazardous Waste Sites". NTIS PB86-165362 OSHA, January 1986.

"29 CFR 1910.120 OSHA Regulations."

"EPA Standard Operating Safety Guidelines". OSWER 10/88.

All sampling and analyses performed by respondent shall conform to the USEPA quality assurance/quality control (QA/QC) and chain of custody procedures and in conformance with the USEPA publication entitled, Test Methods for Evaluating Solid Waste (SW-846 November 1986 as updated) and the USEPA document entitled, Guidance for Preparation of Combined Work/OA Project Plan for Environmental Monitoring (OAMS 005/80).

2.0 PURPOSE

This SOW outlines plans for interim actions at the Site. These interim actions were identified by the USEPA because of concerns regarding the stability and security of the Site. GCDC proposes to undertake

interim actions identified in this document pursuant to the aforementioned administrative order.

As stated during previous discussions with the USEPA, GCDC, through the Receivership, must comply with strict guidelines regarding the allocation of funds. To obtain approval for funding for one or more items, a fairly accurate cost estimate or range is required. The Circuit Court in Baltimore monitoring the Receivership must authorize expenditure of any funds. As a result, an order must be signed by the Circuit Court in Baltimore to formally allocate the funds to complete these interim actions. The court is expected to issue this order by June 12, 1989. GCDC through the receivership has obtained approval for a few of these items and has completed or is in the process of completing some of these actions.

3.0 INTERIM ACTIONS

The following interim actions were discussed at two meetings with the USEPA. Those interim actions which have already been completed (i.e. MEKP and cylinder removal) are not discussed or included on the schedule. The remaining interim actions and the plans for implementation are discussed in the following sections. A schedule for completion of these actions is also included.

3.1 Site Security

Based upon the USEPA reconnaissance of the Site, security was identified to be a major concern. Because of damage to the perimeter fence or the absence of a fence in some areas, access to the Site could not be controlled. Although one 24 hour guard is stationed and periodically patrols in a marked car outside the boundary of the Site, the USEPA believes that certain areas may not be readily accessible to a lone security patrol (northwestern boundary of the Site parcel just west of Dickson Lane). Therefore EPA requested that in addition to GCDC proceeding with fencing, the security patrol at the Site be upgraded.

3.1.1 Proposed Action. GCDC is proceeding with securing the Site perimeter with fencing. A priority will be given to installing a line of fence to impede access along the northwestern perimeter of the parcel located west of Dickson Lane. As of this date, all repairs have been made to the existing fence and gates. The fence posts along the northwestern parcel have been installed. Fencing in this area and between Chemco and the Site parcel north of Herb Hill Road is expected to be completed by June 23, 1989. Furthermore, GCDC has placed another security guard in a marked vehicle for the 8-hour shift from approximately 4:00 p.m. to midnight. This guard is stationed along the Site perimeter on Dickson Lane. A security presence in this area, for the period of time proposed, is intended to dissuade trespassers from entering the northwest Site parcel. During the course of implementing one or more of the interim actions, workers will be on-site during the day and it is less likely that unauthorized individuals will trespass. As certain interim actions are completed, (i.e. fencing completion etc.) GCDC would like the opportunity to downgrade the security force. Funds which do not have to be expended on guards can be targeted for additional stabilization and/or removal actions.

3.2 Radioactive Materials

USEPA has recommended the collection, staging and subsequent removal of isolated drums or containers of residual ore or slag that has exhibited elevated radioactivity readings. These drums or containers have been identified via preliminary radiological surveys conducted by Nassau County Department of Health (NCDOH) and listed in their status reports. The USEPA also did some preliminary radiological surveying and will provide maps depicting the location of the containers it identified to the extent it differs from those items in the NCDOH report.

3.2.1 Proposed Action. The NDL Organization has been contracted to undertake a comprehensive, real-time radiological survey both inside and outside the Site buildings. The purpose of this survey would be to identify any areas where on-site worker access needs to be restricted as a result of radioactivity levels and/or any special protective measures to

be taken while working in those areas. Since worker access to many areas of the Site will be required to complete other interim actions or future remedial work, this radiological survey is prudent and necessary. With the USEPA approval, this survey will include:

- 1) a gamma ray survey of the property and buildings on an approximate 25 foot x 25 foot grid;
- 2) Fixed and removable alpha radiation survey of buildings;
- 3) Collection and gamma spectral analysis of process material (and mud pond sediments);
- 4) Preparation of report summarizing the findings of the survey.

During the course of this radiological survey, readily accessible drums or containers which exhibit elevated readings will be moved to an agreed upon on-site location to which access can be restricted. Based on the results of the survey, up to fifteen (15) containers (including the ones previously identified at the Site) which are characterized as low level radioactive waste will be removed for disposal.

3.3 Laboratory Chemicals

Small quantities of identifiable laboratory chemicals have already been secured and placed in overpacks. In addition, small quantities of unidentified laboratory chemicals remain in some areas. USEPA has recommended characterization, overpacking and disposal, as needed, for all the laboratory chemicals.

3.3.1 Proposed Action. The existing laboratory overpacks will be removed for disposal. The chemicals in existing overpacks may have to be redistributed and placed in special containers. All existing laboratory overpacks which can be removed, as is, by ENSCO (the contractor who completed the overpacking) to its disposal facility will be done. Any remaining laboratory overpacks will be repackaged and reinventoried by the

selected disposal contractor. Any packing lists in compliance with the contractors packing guidelines will be spot checked for accuracy. The existing laboratory overpacks will be moved to a fully permitted transfer facility to await approval of the disposal site. The remaining unidentified laboratory chemicals will be characterized in the field. Up to 200 additional bottles, jars and/or containers will undergo a fingerprint analysis in an isolated area of the Site. This fingerprinting will be done under a portable fume hood. Based on these results, the chemicals will be appropriately packaged for off-site disposal.

3.4 Drum Inventory and Removal

USEPA has recommended the characterization and removal of drums containing chemicals (solid and liquid) at the Site. Specifically, USEPA referred to 50 to 100 units located in the Dickinson Warehouse area (northwest parcel).

3.4.1 Proposed Action. A number of drums containing liquids had been identified in the report prepared by RTP Environmental Associates, Inc. in May 1988. Based on the RTP report, approximately 108 drums of liquids were moved to inside the Dice Building (Main Facility Property). EPA's identification of 50 to 100 units (containers, drums, etc.) containing solid and liquids is in addition to the drums already placed in the Dice Building.

Based on this information, up to 250 drums of liquid/solid chemicals will be characterized for removal and disposal. The drummed contents will be screened for radioactivity in conjunction with the characterization for the purpose of bulking prior to detailed laboratory analysis for disposal. It is assumed that 125 drums will be characterized as waste water treatment candidates and 125 drums will be characterized as incineration candidates.

3.5 Tank Characterization

USEPA has recommended characterization of any liquids remaining in tanks at the Site. The purpose of this characterization would be to

determine if the contents of any tank warrants immediate removal; to identify the types of materials present in different locations so that the appropriate emergency services units are aware of materials on-site; and, ultimately, to ascertain the most practical treatment and disposal options for these liquids.

3.5.1 Proposed Action. Currently, the only inventory of the tanks on the Site and their contents is in the RTP report. According to the report, this inventory was based on a review of records at the Site and a walk-through with a former employee of Li Tungsten. In many instances the tank size and contents (as of May 1988) is indicated. This information does not preclude the need for a more definitive characterization. To accomplish this, representative on-site testing for parameters, including but not limited to, RCRA characteristics, metals and screening for radioactive materials may be the most practical approach. A request for bid (RFB) for this characterization will be solicited (see schedule). The approach and methodology to be used for this characterization will be provided to the USEPA prior to implementation. The results of the characterization will serve to identify the nature of the materials in tanks, their location and evaluate further actions.

3.6 Asbestos

USEPA stated its concern with the presence of large quantities of asbestos in certain areas of the Site. These concerns previously involved worker exposure.

3.6.1 Proposed Action. An asbestos abatement/removal project is more consistent when a long-term remedial program is implemented at the Site. The major concern regarding asbestos is to on-site workers during field activities. Therefore, in order to protect workers, access to areas which are known to contain large quantities of friable asbestos (Lounge Building Area) will be limited. These areas will be designated on a Site map in the Health and Safety Plan. Additional protective gear will be used by personnel working in these areas. Consistent with OSHA requirements, HART will set up ambient air sampling for a specific time period in the

vicinity of these areas to check whether fibers are being dispersed into the air stream. This work will be in addition to health and safety monitoring which will be implemented during the duration of on-site activities.

Two high volume air samples will be analyzed by phase contrast microscopy (PCM) to determine an eight hour time weighted average of asbestos concentration. PCM only determines the total number of fibers and does not distinguish between types of material. If OSHA standards are exceeded using PCM, another two air samples (taken at the same time) will be analyzed by transmission electron microscopy (TEM). In addition, between 25 to 50 bulk asbestos samples will be collected for analysis via polarized light microscopy with dispersion staining (PLMDS). Three to five samples will be collected of each homogeneous area and an estimate of the volume of material sampled, its percent asbestos, location and condition will be presented on a Site map.

3.7 Creek Sediment Sampling

USEPA has recommended that samples of sediment from the creek be obtained for analysis of appropriate radionuclides. The agency proposed these samples be obtained in the vicinity of the outfalls from the Site. According to available information, five (5) outfalls discharged from the Site to the creek when the facility operated. Therefore, five (5) sediment samples were requested.

3.7.1 Proposed Action. A creek sediment sampling program is premature and more in line with a long-term remedial study not a short, interim action. Nevertheless, five (5) creek sediment samples will be collected for radioactivity analysis only. The sampling and analysis will be done by personnel associated with New York University Medical Center, Institute of Environmental Medicine. The individuals will do the work as consultants to GCDC and not under the banner of the University. One sediment sample will be taken in the creek, east of the Site while three sediment samples will be collected in the vicinity of the outfalls and one sediment sample will be obtained from the western portion of the creek.

The samples will be placed in aluminum cans and assayed, (after one to two weeks), for gamma-emitting radionuclides (^{40}K , ^{137}Cs , ^{226}Ra -daughters, ^{228}Th -daughters and ^{228}Ra -daughters) using an intrinsic Ge detector. A portion of the sample will be removed and assayed radiochemically for ^{234}U , ^{238}U , ^{232}Th , ^{230}Th and ^{228}Th . Although the sample collection will be completed in a short period of time, the radionuclide analysis and report will require approximately 3 to 4 months.

3.8 Transformer Inventory and Characterization

USEPA has recommended the inventory of transformers at the Site and characterization of the oils inside the transformers. During its inspection, one transformer located outside a building on the main facility property appeared to have leaked onto the asphalt surface.

3.8.1 Proposed Action. HART has identified sixteen (16) transformers at the Site. The previous RTP report indicated twenty-one (21) transformers and two (2) oil circuit breakers. The contractor who completed the survey for RTP (Empire Environmental Services) will be contacted to account for these five (5) additional transformers and two (2) oil circuit breakers. In any event, a sample oil from the identified transformers will be collected for PCB analysis. Based on these analyses, arrangements for disposal and associated costs will be prepared.

3.9 Mercury Clean-up

An area inside the Benbow (Reduction) building was identified by the USEPA field reconnaissance team to have mercury on the floor. USEPA recommended this area be cleaned.

3.9.1 Proposed Action. Once the dimension of the area is defined, a field team in protective clothing will spread an absorbant lead based salt on the floor surface. The floor surface will be swept and the material placed in a plastic 55-gallon drum. All equipment used in the cleaning will also be placed in the drum. A representative sample (wipe or sweep) will be collected for mercury analysis after the clean-up is completed.

APPENDIX B
SCHEDULE OF COMPLIANCE

**INTERIM ACTIONS
AT THE
LI TUNGSTEN SITE
63 HERB HILL ROAD
GLEN COVE, NEW YORK**

Prepared by:

**FRED C. HART ASSOCIATES, INC.
530 FIFTH AVENUE
NEW YORK, NEW YORK 10036-5166**

July 17, 1989

TABLE OF CONTENTS

1.0 Estimated Schedule 1

List of Figures

Figure 1 Estimated Schedule of Interim Actions. . . 2

1.0 ESTIMATED SCHEDULE

An estimated schedule for the implementation of the interim actions described in this SOW is presented in Figure 2. The time lines include mobilization, field activities and necessary laboratory analysis. Footnotes for each of the listed items are also included. Although the estimated schedule indicates that work will start once an interim order is established, a number of items are ongoing or have already been completed. To the extent practical, interim actions will be completed in short time frames.

HART will provide a bi-monthly status report to the USEPA which summarizes the on-going or completed activities and transmits relevant documentation. The recipients of these status reports are indicated in the order on consent.




FIGURE 2

Estimated Schedule
Interim Actions at Li Tungsten

FRED C. HART ASSOCIATES, INC.

Notes:

- * Start date coincides with interim order

- 1: Fencing is ongoing. Estimated completion is June 23rd. Security guards (one 24 hr. and one 8 hr.) are also provided at the Site.
- 2: Radiological survey to be conducted by the HDL Organization. Currently scheduled to begin the week of June 19, 1989.
- 3: Previously identified containers exhibiting elevated radioactivity readings will be staged in the wire plant. Once survey is completed, up to fifteen containers, characterized as low level radioactivity waste, will be removed from the Site.
 - 3a: This time line reflects the staging of containers exhibiting elevated radioactivity levels in the wire plant building.
 - 3b: This time line reflects removal of up to fifteen containers characterized as low level radioactive waste once laboratory analysis and disposal site arrangements are completed.
- 4: Initiation of laboratory pack removal to immediately follow radiological survey time frame allows for mobilization, random checking of packing inventories against drum contents, repackaging if necessary, and removal to appropriate staging or disposal facility.
- 5: Unknown laboratory chemical characterizations will be completed in an isolated area using a fume hood.
- 6: Drum characterization assumes a total of 250 drums (125 for waste water treatment analysis and 125 for incineration analysis).
- 7: Drum removal (see 6) to begin following receipt of detailed laboratory analysis.
 - 7a: Time frame to review laboratory results of drums and arranging for appropriate disposal of up to 250 drums.
 - 7b: Time frame to remove up to 250 drums to an approved disposal facility.
- 8: Tank contents characterization includes identifying which tanks contain liquids and their approximate volumes.
 - 8a: Time frame to soliciting competitive bids, review and select contractor and notify USEPA prior to implementation.
 - 8b: Time frame to complete the tank characterization.
- 9: Time frame, to monitor/sample for asbestos. Includes two high volume air samples and between 25 and 50 bulk samples for laboratory analysis.

10: Creek Sampling will be scheduled.

10a: Radionuclide analysis and reporting to be completed in approximately 3 months

11: Characterization of transformer oils to follow radiological survey.

12: Mercury on floor of Benbow Building to be cleaned.

13: Summary Report of completed Interim Actions.

ORGANIC DATA REPORTING QUALIFIERS

- U Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g. 10U) based on necessary concentration dilution actions. (This is not necessarily the instrument detection limit.) The footnote should read U-Compound was analyzed for but not detected. The number is the minimum attainable detected limit for the sample.
- J Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g.: If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.)
- B This flag is used when the analyte is found in the blank as well as a sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.
- D This flag identifies all compounds identified in an analysis at a secondary dilution factor.

Note: Data on soil samples expressed on a dry weight basis.

Contractor: NYTEST ENVIRONMENTAL INC.

Lab Sample ID No: N9-9559

Sample Matrix: TUBE

Data Release Authorized By:

Project No: 89-15889

Date Sample Received: 07/7/89

VOLATILE COMPOUNDS

Concentration: Low Medium (Circle One)
Date Extracted/Prepared: NA
Date Analyzed: 07/14/89
Conc/Dil Factor: 0.1 pH:
Percent Moisture (Not Decanted): NA

CAS Number		Total ug	CAS Number		Total ug
74-87-3	Chloromethane	1.0 U	79-34-5	1,1,2,2-Tetrachloroethane	0.5 U
74-83-9	Bromomethane	1.0 U	78-87-5	1,2-Dichloropropane	0.5 U
75-01-4	Vinyl Chloride	1.0 U	10061-02-6	Trans-1,3-Dichloropropane	0.5 U
75-00-3	Chloroethane	1.0 U	79-01-6	Trichloroethane	0.5 U
75-09-2	Methylene Chloride	0.6	124-48-1	Dibromochloromethane	0.5 U
67-64-1	Acetone	1.0 U	79-00-5	1,1,2-Trichloroethane	0.5 U
75-15-0	Carbon Disulfide	0.5 U	71-43-2	Benzene	0.5 U
75-35-4	1,1-Dichloroethane	0.5 U	10061-01-5	cis-1,3-Dichloropropane	0.5 U
75-34-3	1,1-Dichloroethane	0.5 U	110-75-8	2-Chloroethylvinylether	1.0 U
540-59-0	Total-1,2-Dichloroethane	0.5 U	75-25-2	Bromoform	0.5 U
67-66-3	Chloroform	0.2 U	591-78-6	2-Hexanone	1.0 U
107-08-2	1,2-Dichloroethane	0.5 U	108-10-1	4-Methyl-2-Pentanone	1.0 U
78-93-3	2-Butanone	1.0 U	127-18-4	Tetrachloroethane	0.5 U
71-55-8	1,1,1-Trichloroethane	0.3 U	108-88-3	Toluene	0.5 U
56-23-5	Carbon Tetrachloride	0.1 U	108-90-7	Chlorobenzene	0.5 U
108-05-4	Vinyl Acetate	1.0 U	100-41-4	Ethylbenzene	0.5 U
75-27-4	Bromodichloromethane	0.5 U	100-42-5	Styrene	0.5 U
				Total Xylenes	0.5 U
				Total Dichlorobenzene	3.0 U

Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

VALUE If the result is a value greater than or equal to the detection limit, report the value.

U Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g. 10U), based on necessary concentration dilution actions. (This is not necessarily the instrument detection limit.) The footnote should read U-Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.

J Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g. 10U).

C This flag applies to pesticide parameters where the identification has been confirmed by GC/MS Single component pesticides greater than or equal to 10 ng/ul in the final extract should be confirmed by GC/MS.

B This flag is used when the analyte is found in the blank as well as a sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.

Other specific flags and footnotes may be required to properly define the results. If used, they must be fully described and such description attached to the data summary report.

ORGANICS ANALYSIS DATA SHEET

Contractor: NYTEST ENVIRONMENTAL INC.
Project No: 89-15969

SAMPLE NUMBER: VOC-3
LAB SAMPLE ID NO: N9-9559

Tentatively Identified Compounds

CAS Number	Compound Name	Fraction	RT	Total ug
1	UNKNOWN	VOA	2:54	3.7 J
2	UNKNOWN	VOA	3:34	2.3 J
3	UNKNOWN	VOA	6:04	4.6 J
4	TRICHLOROFLUOROMETHANE	VOA	10:20	1.9 J
5	2-METHYLBUTANE	VOA	14:28	0.8 J
6	FREON	VOA	16:50	1 J
7	UNKNOWN ALKANE	VOA	16:20	0.8 J
8	2,2-DIMETHYL 1,3-DIOXOLANE	VOA	19:20	1.6 J
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				

RIC

07/14/89 11:47:00

SAMPLE: F.C.HART,UOC-3/N9-9559,REC'D 7/7/89

CONDS.: TUBE/2MLS,100UL/5ML INSTD


RANGE: G 1,1300 LABEL: N 0, 4.0 QUAN: A 0, 1.0 J 0 BASE: U 20, 3

DATA: D8946 #1016

CALI: D8946 #2

SCANS 25 TO 1300

222976.



Contractor: NYTEST ENVIRONMENTAL INC.

Lab Sample ID No: N9-9550

Sample Matrix: TUBE

Data Release Authorized By:

Project No: 89-15989

Date Sample Received: 07/1/89

VOLATILE COMPOUNDS

Concentration: Low Medium (Circle One)
 Date Extracted/Prepared: NA
 Date Analyzed: 07/14/89
 Conc/Dil Factor: 0.1 pH:
 Percent Moisture (Not Decanted): NA

CAS Number		Total ug	CAS Number		Total ug
74-87-3	Chloromethane	1.0 U	79-34-5	1,1,2,2-Tetrachloroethane	0.5 U
74-83-9	Bromomethane	1.0 U	78-87-5	1,2-Dichloropropane	0.5 U
75-01-4	Vinyl Chloride	1.0 U	10061-02-6	Trans-1,3-Dichloropropane	0.5 U
75-00-3	Chloroethane	1.0 U	79-01-6	Trichloroethane	0.5 U
75-09-2	Methylene Chloride	2.6	124-48-1	Dibromochloromethane	0.5 U
67-64-1	Acetone	1.0 U	79-00-5	1,1,2-Trichloroethane	0.5 U
75-15-0	Carbon Disulfide	0.5 U	71-43-2	Benzene	0.5 U
75-35-4	1,1-Dichloroethane	0.5 U	10061-01-5	cis-1,3-Dichloropropane	0.5 U
75-34-3	1,1-Dichloroethane	0.5 U	110-75-8	2-Chloroethylvinylether	1.0 U
540-59-0	Total-1,2-Dichloroethane	0.5 U	75-25-2	Bromoform	0.5 U
67-66-3	Chloroform	0.3 U	591-78-6	2-Hexanone	1.0 U
107-06-2	1,2-Dichloroethane	0.5 U	108-10-1	4-Methyl-2-Pentanone	1.0 U
78-93-3	2-Butanone	1.0 U	127-18-4	Tetrachloroethane	0.5 U
71-55-6	1,1,1-Trichloroethane	0.3 U	108-88-3	Toluene	0.5 U
56-23-5	Carbon Tetrachloride	0.2 U	108-90-7	Chlorobenzene	0.5 U
108-05-4	Vinyl Acetate	1.0 U	100-41-4	Ethylbenzene	0.5 U
75-27-4	Bromodichloromethane	0.5 U	100-42-5	Styrene	0.5 U
				Total Xylenes	0.5 U
				Total Dichlorobenzene	3.0 U

Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used.
 Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

VALUE If the result is a value greater than or equal to the detection limit, report the value.

U Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g. 10U), based on necessary concentration dilution actions. (This is not necessarily the instrument detection limit.) The footnote should read U-Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.

J Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g. 10J).

C This flag applies to pesticide parameters where the identification has been confirmed by GC/MS Single component pesticides greater than or equal to 10 ng/ul in the final extract should be confirmed by GC/MS.

B This flag is used when the analyte is found in the blank as well as a sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.

Other specific flags and footnotes may be required to properly define the results. If used, they must be fully described and such description attached to the data summary report.

ORGANICS ANALYSIS DATA SHEET

Contractor: NYTEST ENVIRONMENTAL INC.
Project No: 89-15959

SAMPLE NUMBER: VOC-4
LAB SAMPLE ID NO: N9-9560

Tentatively Identified Compounds

CAS Number	Compound Name	Fraction	RT	Total ug
1	UNKNOWN	VOA	3:02	7.1 J
2	UNKNOWN	VOA	3:14	0.7 J
3	UNKNOWN	VOA	3:36	7.1 J
4	UNKNOWN	VOA	4:08	4.4 J
5	UNKNOWN	VOA	4:18	2.0 J
6	UNKNOWN	VOA	4:32	5.5 J
7	TRICHLOROFLUOROMETHANE	VOA	10:18	4.7 J
8	UNKNOWN ALKANE	VOA	16:22	1.4 J
9	2,2-DIMETHYL 1,3-DIOXOLANE	VOA	19:18	1.7 J
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				

nytest environmental

ORGANICS ANALYSIS DATA SHEET

Contractor: NYTEST ENVIRONMENTAL INC.
Project No: 89-15969

SAMPLE NUMBER: VOC-2
LAB SAMPLE ID NO: N9-9558

Tentatively Identified Compounds

CAS Number	Compound Name	Fraction	RT	Total ug
1	UNKNOWN	VOA	2:46	6.2 J
2	UNKNOWN	VOA	3:18	12.5 J
3	UNKNOWN	VOA	3:44	14 J
4	UNKNOWN	VOA	4:16	8 J
5	UNKNOWN	VOA	4:24	4 J
6	UNKNOWN	VOA	4:42	8 J
7	UNKNOWN	VOA	4:54	7 J
8	UNKNOWN ACID	VOA	5:10	6 J
9	UNKNOWN	VOA	6:02	0.7 J
10	UNKNOWN	VOA	8:18	1.7 J
11	UNKNOWN	VOA	10:24	1 J
12	UNKNOWN	VOA	13:16	1.3 J
13	FREON	VOA	14:54	1.6 J
14	UNKNOWN	VOA	16:46	0.7 J
15	1,3-DIMETHYL 2,2-DIOLOXANE	VOA	19:22	1 J
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				

104321

Contractor: NYTEST ENVIRONMENTAL INC.

Lab Sample ID No: N9-9558

Sample Matrix: TUBE

Data Release Authorized By.

Project No: 89-15969

Date Sample Received: 07/7/89

VOLATILE COMPOUNDS

Concentration: Low Medium (Circle One)
 Date Extracted/Prepared: NA
 Date Analyzed: 07/14/89
 Conc/Dil Factor: 0.1 pH:
 Percent Moisture (Not Decanted): NA

CAS Number		Total ug	CAS Number		Total ug
74-87-3	Chloromethane	1.0 U	79-34-5	1,1,2,2-Tetrachloroethane	0.5 U
74-83-9	Bromomethane	1.0 U	78-87-5	1,2-Dichloropropane	0.5 U
75-01-4	Vinyl Chloride	1.0 U	10061-02-6	Trans-1,3-Dichloropropene	0.5 U
75-00-3	Chloroethane	1.0 U	79-01-6	Trichloroethane	0.5 U
75-09-2	Methylene Chloride	0.6 U	124-48-1	Dibromochloromethane	0.5 U
67-64-1	Acetone	1.0 U	79-00-5	1,1,2-Trichloroethane	0.5 U
75-15-0	Carbon Disulfide	0.5 U	71-43-2	Benzene	0.5 U
75-35-4	1,1-Dichloroethane	0.5 U	10061-01-5	cis-1,3-Dichloropropene	0.5 U
75-34-3	1,1-Dichloroethane	0.5 U	110-75-8	2-Chloroethylvinylether	1.0 U
540-59-0	Total-1,2-Dichloroethane	0.5 U	75-25-2	Bromoform	0.5 U
87-88-3	Chloroform	0.5 U	591-78-6	2-Hexanone	1.0 U
107-06-2	1,2-Dichloroethane	0.5 U	108-10-1	4-Methyl-2-Pentanone	1.0 U
78-93-3	2-Butanone	1.0 U	127-18-4	Tetrachloroethane	0.5 U
71-55-6	1,1,1-Trichloroethane	0.5 U	108-88-3	Toluene	0.5 U
56-23-5	Carbon Tetrachloride	0.5 U	108-90-7	Chlorobenzene	0.5 U
108-05-4	Vinyl Acetate	1.0 U	100-41-4	Ethylbenzene	0.5 U
75-27-4	Bromodichloromethane	0.5 U	100-42-5	Styrene	0.5 U
				Total Xylenes	0.5 U
				Total Dichlorobenzene	3.0 U

Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used.
 Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

- VALUE If the result is a value greater than or equal to the detection limit, report the value.
- U Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g. 10U), based on necessary concentration dilution actions. (This is not necessarily the instrument detection limit.) The footnote should read U-Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g. 10U).
- C This flag applies to pesticide parameters where the identification has been confirmed by GC/MS Single component pesticides greater than or equal to 10 ng/u1 in the final extract should be confirmed by GC/MS.
- B This flag is used when the analyte is found in the blank as well as a sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action.
- Other specific flags and footnotes may be required to properly define the results. If used, they must be fully described and such description attached to the data summary report.



nytest environmental inc.

REPORT OF ANALYSIS

Date: September 21, 1989

Project No.: 89-15969

Log in No: 2224

Client:

Fred C. Hart Associates

Material:

(4) Waste Samples

Identification:

As below (sample received: 08/17/89)

Client's Order No:

00265-02-00003-01

We find as follows:

Sample IdentificationParameter(s)Anion Concentration, ug

		Chloride	Fluoride	Nitrate	Sulfate
IOA-11	N901777	1.86	3.28	0.09	1.01
IOA-12	N901778	0.41	2.78	< 0.09	< 0.9
IOA-13	N901779	0.55	1.49	< 0.09	< 0.9
IOA-14	N901780	2.82	1.37	0.10	1.0

Note: The samples were analyzed for inorganic acids according to NIOSH method 7903. Results are given as micrograms of the anion in the sample front and back sorbant sections.

REPORT PREPARED BY:
MARLIN McCRICKARD
INORGANICS LAB MANAGER

DOUGLAS SHEELEY
LABORATORY DIRECTOR

To: Fred C. Hart Associates
530 Fifth Avenue
New York, NY 10036

Att: Karl Boldt
Ref: LI Tungsten

ma

We certify that this report
is a true report of results
obtained from our tests of
this material.

Respectfully submitted,

Nyttest Environmental, Inc.

Remo Gigante, Exec. V.P.

REFERENCE NO. 29

104324

CONTROL NO:

02-8907-78

DATE:

10/23/89

TIME:

1415

DISTRIBUTION:

TO FILE: LI TUNGSTEN

BETWEEN:

ROBERT THESSIFELD

OF: NASSAU COUNTY

DEPT. OF HEALTH

PHONE:

(516) 535-3313

AND:

STEVEN OKULEWICZ

DISCUSSION:

I ASKED MR. THESSIFELD ABOUT BACKGROUND RADIATION RESULTS FOR THE LI TUNGSTEN SITE. HE SAID THAT NO ON-SITE RADIATION SURVEYS WERE EVER DONE TO DETERMINE BACKGROUND RADIATION, BUT OFF-SITE SOIL SAMPLES WERE TESTED AND HAD "NEGATIVE RESULTS."

ACTION ITEMS:

CONFIDENTIAL-NOT FOR PUBLIC RELEASE

HRS

	S	S ²
Groundwater Route Score (S _{gw})	83.67	7000.67
Surface Water Route Score (S _{sw})	9.45	89.30
Air Route Score (S _a)	0	0
$S_{gw}^2 + S_{sw}^2 + S_a^2$		7089.97
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		84.20
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M$		48.67

WORKSHEET FOR COMPUTING S_M

PRO

	S	S ²
Groundwater Route Score (S _{gw})	100	10,000
Surface Water Route Score (S _{sw})	10.91	119.03
Air Route Score (S _a)	58.46	3417.57
$S_{gw}^2 + S_{sw}^2 + S_a^2$		13536.60
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2}$		116.35
$\sqrt{S_{gw}^2 + S_{sw}^2 + S_a^2} / 1.73 = S_M$		67.25

WORKSHEET FOR COMPUTING S_M

CONFIDENTIAL-NOT FOR PUBLIC RELEASE

Ground Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)	Multi-plier	HRS	Max. Score	PRO		
1 Observed Release	0 45	1	0	45	45		
If observed release is given a score of 45, proceed to line 4 . If observed release is given a score of 0, proceed to line 2 .							
2 Route Characteristics							
Depth to Aquifer of Concern	0 1 2 3	2	6	6	6		
Net Precipitation	0 1 2 3	1	3	3	3		
Permeability of the Unsaturated Zone	0 1 2 3	1	3	3	3		
Physical State	0 1 2 3	1	3	3	3		
Total Route Characteristics Score			15	15	15		
3 Containment	0 1 2 3	1	3	3	3		
4 Waste Characteristics							
Toxicity/Persistence	0 3 6 9 12 15 18	1	18	18	18		
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 8	1	8	8	8		
Total Waste Characteristics Score			26	26	26		
5 Targets							
Ground Water Use	0 1 2 3	3	6	9	9		
Distance to Nearest Well/Population Served	0 4 8 12 16 18 20 24 30 32 35 40	1	35	40	40		
Total Targets Score			41	49	49		
6 If line 1 is 45, multiply 1 x 3 x 5							
If line 1 is 0, multiply 2 x 3 x 4 x 5							
			47970	57,330	57330		
7 Divide line 6 by 57,330 and multiply by 100							
			Sgw = 83.67		100		

HRS SCORE 0

PRO SCORE 45

CONFIDENTIAL-NOT FOR PUBLIC RELEASE

Surface Water Route Work Sheet							
Rating Factor	Assigned Value (Circle One)		Multi- plier	HRS	Max. Score	PRO	
1 Observed Release	0	45	1	0	45	45	
If observed release is given a value of 45, proceed to line 4 . If observed release is given a value of 0, proceed to line 2 .							
2 Route Characteristics							
Facility Slope and Intervening Terrain	0	1	2	3	1	2	3
1-yr. 24-hr. Rainfall	0	1	2	3	1	2	3
Distance to Nearest Surface Water	0	1	2	3	2	6	6
Physical State	0	1	2	3	1	3	3
Total Route Characteristics Score				13	15	13	
3 Containment	0	1	2	3	1	3	3
4 Waste Characteristics							
Toxicity/Persistence	0	3	6	9	12	15	18
Hazardous Waste Quantity	0	1	2	3	4	5	6
Total Waste Characteristics Score				26	28	26	
5 Targets							
Surface Water Use	0	1	2	3	3	6	9
Distance to a Sensitive Environment	0	1	2	3	2	0	6
Population Served/Distance to Water Intake Downstream	0	4	6	8	10	12	16
Total Targets Score				6	55	6	
6 If line 1 is 45, multiply 1 x 4 x 5				6084			
If line 1 is 0, multiply 2 x 3 x 4 x 5				7020			
7 Divide line 6 by 64,350 and multiply by 100				S _{SW} = 9.45			
				10.91			

HRS SCORE 0
PRO SCORE 1

CONFIDENTIAL-NOT FOR PUBLIC RELEASE

Air Route Work Sheet						
Rating Factor	Assigned Value (Circle One)	Multi- plier	HRS	Max. Score	PRO	
1 Observed Release	<u>0</u> <u>45</u>	1	<u>0</u>	45	<u>45</u>	
Date and Location:						
Sampling Protocol:						
If line 1 is 0, the $S_a = 0$. Enter on line 5 If line 1 is 45, then proceed to line 2						
2 Waste Characteristics						
Reactivity and Incompatibility	0 1 <u>2</u> 3	1		3	<u>2</u>	
Toxicity	0 1 2 <u>3</u>	3		9	<u>9</u>	
Hazardous Waste Quantity	0 1 2 3 4 5 6 7 <u>8</u>	1		8	<u>8</u>	
Total Waste Characteristics Score				20	<u>19</u>	
3 Targets						
Population Within 4-Mile Radius	0 9 12 15 18 <u>21</u> 24 27 30	1		30	<u>21</u>	
Distance to Sensitive Environment	<u>10</u> 1 2 3	2		6	<u>0</u>	
Land Use	0 1 2 <u>3</u>	1		3	<u>3</u>	
Total Targets Score				39	<u>24</u>	
4 Multiply 1 x 2 x 3				35,100	<u>20520</u>	
5 Divide line 4 by 35,100 and multiply by 100			$S_a =$ <u>0</u>		<u>58.46</u>	

HRS SCORE 0
PRO SCORE



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION II
EDISON, NEW JERSEY 08837

AUG 15 1989

Mr. Michael J. O'Toole, Jr., P.E.
Director
Division of Hazardous Waste Remediation
New York State Department of Environmental
Conservation
50 Wolf Road
Albany, New York 12233

Dear Mr. O'Toole:

This is in reply to your April 14, 1989, request for a CERCLA removal action at the Li Tungsten Site in Glen Cove, Nassau County, New York. Mr. Charles Fitzsimmons, of the Response and Prevention Branch, was assigned as the On-Scene Coordinator (OSC) for this site.

A preliminary assessment and removal site inspection was conducted on April 16, 1989, and also April 26 through April 28, 1989. Based on the findings of this inspection, we determined that there is a substantial threat of release of hazardous substances as described under Section 104 of CERCLA, as amended by SARA. As a result of this determination, negotiations were initiated between the Primary Responsible Party (Old Court Savings and Loan) and EPA's Office of Regional Counsel. On June 30, 1989, an agreement was reached.

This Consent Order requires the responsible party to remove all hazardous substances as regulated by CERCLA, RCRA and the CWA. The large quantity of slag material bearing above background levels of select radionuclides will have to be addressed under the State's remedial program. The responsible party will provide a short term mitigative fix by stabilizing these piles.

104330

Should you have any questions or require additional information, please have your staff contact Mr. Fitzsimmons at (201) 321-6608.

Sincerely yours,

Stephen D. Luftig

Stephen D. Luftig, Director
Emergency and Remedial Response Division

cc: R. Salkie, 2ERR-ADREPP
B. Sprague, 2ERR-RPB
C. Fitzsimmons, 2ERR-RPB



OFFICE OF THE MAYOR
CITY OF GLEN COVE
NEW YORK 11542

DONALD P. DeRIGGI
MAYOR AND SUPERVISOR

FEB 2 1990

516-676-2000

January 31, 1990

RE: Glen Cove - LiTungsten Site

Gentlemen:

In April of 1989, anhydrous ammonia and other volatile chemicals were found at the above location, together with 32 million pounds of slag containing thorium and other radioactive elements.

The EPA is finishing its emergency removal of the laboratory chemicals, asbestos, PCBs and other elements it has deemed to be part of its mandate. Remaining will be the 32 million pounds of thorium slag. Our concern is that the radioactive elements should be included in the emergency removal plan or should at least be characterized by the DEC as requiring high priority on its removal list.


The Li Tungsten site is located next to Glen Cove Creek which empties into Hempstead Harbor. The 32 million pounds of thorium poses a serious leachate question. Run-off and seepage seem inevitable. It should also be noted that our fire department has expressed great concern about having to enter onto the premises. They have been advised that if there is a fire, or if indeed there are aggravated wind conditions at the location, the radioactive particles will become volatilized and airborne and, therefore, possibly ingested. The EPA has indicated that most of the radioactive elements are being stored within buildings on the premises. These buildings are wooden and in a dilapidated condition. Therefore, the chance of fire is real and the volatilization of the particles is a very serious question.

104332

Page 2
January 31, 1990

I, therefore, respectfully request your assistance in securing the removal of the radioactive substances by having this aspect incorporated into the emergency removal plan of EPA or, in the alternative if this is not possible, having Li Tungsten characterized as having high priority on the DEC's list of sites.

Very truly yours



DONALD P. DE RIGGI
Mayor and Supervisor

DPD:dag

104333

FEB 7 1990


Mr. Michael J. O'Toole, Jr., P.E.
Director
Division of Hazardous Waste Remediation
New York State Department of Environmental
Conservation
50 Wolf Road
Albany, New York 12233

Dear Mr. O'Toole:

This is in regard to the Li Tungsten, Glen Cove, Long Island time critical removal action presently being performed by the Responsible Party under a Section 106 Order on Consent. As you are aware, field activities have been ongoing since this agreement was reached on June 30, 1989, as described in my letter to you dated August 15, 1989 (attached).

A great deal of site stabilization and clean-up activity has taken place since the initiation of the removal action. However, it is anticipated that the removal action, as described in the above order, will come to a conclusion on or about February 10, 1990. Shortly thereafter, a final report from the Responsible Party should be completed and submitted to EPA. As you are also aware this site is not listed on the National Priorities List (NPL) and nomination for such may not occur until sometime in 1991, after the new EPA hazard ranking system is finalized.

Mr. Charles Fitzsimmons, On-Scene Coordinator of my staff, would like to coordinate a meeting with members of your staff to effect a smooth transition of overall site leadership. This meeting would also serve to provide an update on the present site conditions, specifically with regard to the large quantity of radioactive slag material, that remains on-site.



104334

Dick Salkie or Mr. Fitzsimmons will be contacting Al Rochmore to arrange this discussion. Should you have additional questions on this transition, please contact Mr. Fitzsimmons at 201-321-6608 or myself.

Sincerely yours,

Stephen D. Luftig

Stephen D. Luftig, Director
Emergency and Remedial Response Division

cc: R. Salkie, 2ERR-ADREPP
B. Sprague, 2ERR-RPB
C. Fitzsimmons, 2ERR-RPB
J. Doyle, ORC-NYCSUP
M. Hauptman, ERRD-SC
A. Hess, ERRD-SC
A. Fellman, AWM-RAD

Left on site

*final report just received by EPA
16,000+ tons - pits and drums
Low level RAD facility*

High level - was removed - not immediately dangerous



STATE OF NEW YORK
DEPARTMENT OF HEALTH

Corning Tower The Governor Nelson A. Rockefeller Empire State Plaza Albany, New York 12237

David Axelrod, M.D.
Commissioner

OFFICE OF PUBLIC HEALTH

Linda A. Randolph, M.D., M.P.H.
Director

William F. Leavy
Executive Deputy Director

March 9, 1990

Mr. Michael J. O'Toole, Jr. P.E., Director
Division of Hazardous Waste Remediation
NYS Department of Environmental Conservation
50 Wolf Road
Albany, NY 12233

Dear Mr. O'Toole:


We recently received a copy of a letter dated February 7, 1990 to you from Stephen Luftig of EPA relative to the Li Tungsten site in Glen Cove, NY. In the letter, EPA asked for a meeting to effect a transition of overall site leadership.

We would like to be included in any such meeting due to the concerns about the large quantities of radioactive materials on this site. Please contact me or William Condon at 458-6461 if you have any questions.

Sincerely,

Karim Rimawi, Ph.D.
Director
Bureau of Environmental Radiation
Protection


cc: Dr. Hetling
Dr. Merges
Mr. Condon



104336

New York State Department of Environmental Conservation
50 Wolf Road, Albany, New York 12233 7010

JUN 4 1990



Thomas C. Jorling
Commissioner

Mr. Stephen Luftig
Director
Emergency and Remedial Response Division
USEPA Region II
26 Federal Plaza
New York, New York 10278

Dear Mr. Luftig:

Re: Site Code #130046
Li Tungsten, Glen Cove
Nassau County


Thank you for your expert assistance as lead agency during the recent PRP remedial efforts at the referenced site. This is yet another example of how EPA's timely response and cooperation are helping to clean up and remediate sites, such as this, to the benefit of all.

As you are aware, radioactive contamination is not a hazardous waste in New York State and the New York State Department of Environmental Conservation (NYSDEC), therefore, cannot use State Superfund money to address the problem of the remaining radioactive slag. This site is a Class 2 site on our registry (significant threat to public health or environment) due to other contaminants. It is not scheduled in our program in the immediate future.

The enclosed letter from the City of Glen Cove Mayor and Supervisor, Mr. Donald Riggi, explains the grave concern of the residents of Glen Cove regarding the Li Tungsten site. The NYSDEC, therefore, requests that the USEPA remain as lead agency at the site until such time as the problem of the radioactive contaminated slag is solved.

If you have any questions regarding this request, please contact Alan Rockmore, P.E., of my staff at (518) 457-9280.

Sincerely,


Michael J. O'Toole, Jr., P.E.
Director
Division of Hazardous Waste Remediation

Enclosure

cc: R. Tramontano - NYSDOH
K. Rimawi - NYSDOH
R. Salkie - USEPA Region II

104337

FILE 100-100000
FILE COPY

Mr. Donald P. De Riggi
Mayor and Supervisor
Glen Cove, New York 11542

Dear Mayor De Riggi:

In reference to your January 14, 1991 letter concerning the placement of the Li Tungsten site on EPA's National Priorities List (NPL) of Superfund sites, please be advised that the next NPL update (Update #11) is scheduled to be released by EPA-Headquarters, Washington, D.C., in the Spring of 1991.

As you know, candidates for Update #11 include the Li Tungsten site; moreover, the final selection of NPL sites from the candidate list will be announced at the time Update #11 is released.

If I may be of further assistance, please let me know. I can be reached at (212) 264-0522.

Sincerely yours,

Edward G. Als, Remedial Project Manager
Eastern New York/Caribbean Section I

bcc: D. Santella ✓